

Greg Kruger Concrete Contractors

941 County Road 286

Collinsville, Texas 76233

940 391-3279

February 5, 2019

16' wide crosswalk by 40' long 6" thick concrete with #3 rebar 16" o.c.e.w on chairs. Brick in road removed and will be saved. Saw out curbs, remove and pour new ones.

16'x9' to be tore out and removed and poured back with concrete and rebar.

15x15 sq. feet radius to be removed and poured back with concrete and a handicap ramp put in.

18'x16' parking area to be tore out and replaced with concrete

Two – 16'x12" water drain's put in on each side of road with cat walk metal covers for water drainage installed and included in price.

All tore out materials to be hauled off and cleaned up when job is completed.

Price - \$19,750.00

