

BITUMINOUS MATERIALS, LLC

680 NW 24TH STREET
PO BOX 246
FARIBAULT, MN 55021
507-334-5155 OFFICE
507-334-0114 FAX

**ESTIMATE & AGREEMENT****TO: Faribault Public Schools****DATE:** 4/5/2023

BID: We hereby propose to furnish material and labor to complete the work outlined herein for the sum of:

As Stated Below Dollars

\$ 89,289.50 Payment to be made as follows:

Net 30 from Billing Date

We hereby submit specifications and bid for:

FARIBAULT: MIDDLE SCH 2.0" MILL/PAVE 2023**PROJECT LOCATION:**

ITEM	DESCRIPTION	UNITS	U/M	UNIT PRICE	EXTENDED
MOBILIZATION	PEOPLE AND EQUIP. MOVES	1.00	LS	\$ 1,150.00	\$ 1,150.00
PEOPLE AND EQUIPMENT LOGISTICS NECESSARY TO COMPLETE QUOTED SCOPE OF WORK.					
MILLING 2.0"	MILL 2.0" AND CLEAN FOR PAVING	6,520.00	SY	\$ 2.85	\$ 18,582.00
PROFILE MILL ASPHALT SURFACE 2.0", DETAIL MILL CORNERS/MATCH-IN AREAS, AND CLEAN SURFACE FOR PAVING.					
TACK COATING	BIT. MAT FOR TACK COATING	365.00	GAL	\$ 3.50	\$ 1,277.50
BITUMINOUS MATERIAL FOR TACK COATING.					
WEAR LIFT	SPWEB240B, 2.0" THICK	6,520.00	SY	\$ 10.25	\$ 66,830.00
TYPE SP 12.5 WEARING COURSE MIXTURE (2,B), 2.0" COMPACTED THICKNESS.					
MISC. PATCHING	REMOVE REPLACE PATCHING	-	SY	\$ 20.25	\$ -
REMOVE AND DISPOSE OF DETERIORATED ASPHALT, AS DIRECTED. SHAPE, COMPACT, AND PATCH REPAIR AREAS. TYPE SP 12.5 WEARING COURSE MIXTURE (2,B), 2.0" COMPACTED THICKNESS. THIS ITEM QTY IS NOT KNOWN AT THIS TIME.					
LOT STRIPING	RESTRIPE PARKING LOT	1.00	LS	\$ 1,450.00	\$ 1,450.00
STRIPING BY SEYKORA STRIPING.					
CONTINGENCY ADD-ONS: PROJECT OWNER APPROVAL ONLY					
SOIL CORRECTION	EXCAVATE W/ROCK BACKFILL	-	CY	\$ 47.50	\$ -
EXCAVATE AND DISPOSE OF UNSUITABLE SOILS. BACK FILL WITH 1.0" - 1.5" CRUSHED CONCRETE/ROCK AND COMPACT.					
CLASS 5 BASE	SUPPLEMENTAL CLASS 5	-	TON	\$ 22.00	\$ -
SUPPLEMENTAL CLASS 5 AGGREGATE DELIVERED AND PLACED. AS NEEDED.					
TOTAL					\$ 89,289.50

PRICE INCLUDES: MOBILIZATIONS, ASPHALT REMOVAL, GRADING, ASPHALT SUPPLY, ASPHALT PAVING, TACK COATING, APPLICABLE WORK CLEAN UP, AND LOT STRIPING.

EXCLUSIONS: BONDING, STAKING, EXCAVATION, AGGREGATE BASE SUPPLY, ROUGH GRADE, SOIL CORRECTIONS, CASTING ASSEMBLY ADJUSTS, TRAFFIC CONTROL, AND SIGNAGE.

CONTRACTOR'S GUARANTEE

We guarantee all material used in this contract to be specified above and the entire job to be done in a neat, workmanlike manner. Any variations from the plan or alterations requiring extra labor or material will be performed only upon written order and billed in addition to the sum covered by this contract. Agreements made with our workmen are not recognized.

DATE

4/5/2023

SIGNED

ACCEPTANCE OF BID

The above specifications, terms and contract are satisfactory, and (I/We) hereby authorize the performance of this work.

DATE

SIGNED

THIS CONTRACT IS VOID 30 DAYS FROM DATE UNLESS ORIGINAL IS SIGNED AND RETURNED TO BIDDER

WE COMPLY WILL ALL WORKMAN'S COMPENSATION & PROPERTY DAMAGE LIABILITY INSURANCE LAWS

www.bituminousmaterials.com**An Equal Opportunity Employer**