

Alpena County
Courthouse Roof Replacement
Scope of Work
Feb 2022

1. Remove existing membrane and dispose of in a legal manner.
2. Inspect the existing insulation and replace wet or damaged insulation at a pre-determined square foot price.
3. Install 3/8" fan fold insulation board over exiting insulation.
4. Install a 50 mil, Duro-Last roof system to entire roof area. Roof system is to be mechanically fastened per manufacturers specifications. Duro Last or Duro-Last X membrane is approved.
5. Flash and seal all roof penetrations per manufacturers specifications.
6. Install two way breather vents per manufacturers specifications.
7. Perimeter termination is to be term bar on the inside of the parapet wall secured just below the bottom leg of the existing coping cap.
8. Remove the existing roof hatch and replace with a Bilco S hatch with a Ladder up safety post.
9. Roofing contractor is responsible to secure services of a licensed electrical contractor for any modifications to electrical lines that may be required for install of the roof system.
10. Provide complete clean up of all job related debris.
11. Roofing contractor is responsible for any damage to landscaping, sidewalks and parking lots that occur due to their actions.
12. Provide a 20 year NDL, manufacturer's warranty covering 100% materials and 100% labor