



1719 Yensch Rd.
Dundee, MI 48131
734-347-5717

Project Quotation

DATE: 8/22/24

ATTN: Tim Salenbien (Monroe Schools)

Desbrough Excavating and Trucking, LLC

PROJECT: Road Project

We are pleased to submit our quotation for the scope of Work identified on the bid package below.

Total lump sum quotation for areas to perform the scope indicated, subject to the following notes and clarifications, shall be **\$10,000**

Prep for work

1. Mobilize equipment

Underground / site work

1. Install a new driveway 570' x 12'
2. Cut out sod and make the new road area smooth
3. loose all the spoils on site
4. Lay down road fabric
5. Place 21aa for a total thickness to be 6"
6. Roll the stone in lifts with a vibratory roller
7. Install a section of schedule 40 pvc pipe for a future basin and drainage
8. Take down 1 pine tree
9. Take down a section of berm
10. Remove 3 wood post

Clean up

1. Clean up site
2. Seed and straw everything that was disturbed

Desbrough Excavating appreciates the opportunity to quote this work. Please do not hesitate to call if you have any questions. We look forward to hearing from you.

Desbrough Excavating and Trucking, LLC

David Desbrough

Phone: 734-347-5717

Email: desbroughexcavating3@gmail.com