

Veteran Pride A/C & Heat, LLC
2332 Sandy Ln.
Longview, Tx. 75605
903-738-7073
LIC.# TACLA76148C

Bill To: Harleton I.S.D.
17240 TX-154
Harleton, Tx. 75651

Quote

This quote is for installing two new 15-ton all electric package units at the old Jr. High gym for a total of 30-tons. We will set the units on new pads or racks provided by the school on the east side of the gym and we will run new metal square duct ductwork up the outside wall into two of the old windows stopping the return duct just inside the gym and covering the end openings with expanded metal. The supply duct will come just inside the gym also but then go from square duct to a round fabric duct sock which will extend the length of the gym. We will need to get a scissor lift on the gym floor so we will put down 3/4" plywood under the lift.

Quote Includes:

- Two (2) ICP R-454B Comfortmaker 15-ton electric Package units
- Two (2) 25KW electric heat kits
- Two (2) Fabric duct socks
- Two (2) hail guards
- Four (4) smoke detectors
- Two (2) 2 heat 2 cool programmable thermostats
- Necessary metal square duct
- Scissor Lift rental
- Crane rental
- Labor

Not included:

- Necessary pads or racks for the package units to set on outside
- Any other materials or equipment not listed above

Total Quote: 87,145.00

This proposal is valid for 30 days.

Thank you for this opportunity to serve you. Please feel free to contact me with any questions.

Robert Cubine

Owner: Veteran Pride A/C & Heat, LLC

Email: rcubine1203@gmail.com



Date 5/5/2025

Veteran Pride A/C & Heat, LLC
2332 Sandy Ln.
Longview, Tx. 75605
903-738-7073
LIC.# TACLA76148C

Bill To: Harleton I.S.D.
17240 TX-154
Harleton, Tx. 75651

Quote

This quote is for installing two new 20-ton all electric package units at the old Jr. High gym for a total of 40-tons. We will set the units on new pads or racks provided by the school on the east side of the gym and we will run new metal square duct ductwork up the outside wall into two of the old windows stopping the return duct just inside the gym and covering the end openings with expanded metal. The supply duct will come just inside the gym also but then go from square duct to a round fabric duct sock which will extend the length of the gym. We will need to get a scissor lift on the gym floor so we will put down $\frac{3}{4}$ " plywood under the lift.

Quote Includes:

- Two (2) ICP R-454B Comfortmaker 20-ton electric Package units
- Two (2) 25KW electric heat kits
- Two (2) Fabric duct socks
- Two (2) hail guards
- Four (4) smoke detectors
- Two (2) 2 heat 2 cool programmable thermostats
- Necessary metal square duct
- Scissor Lift rental
- Crane rental
- Labor

Not included:

- Necessary pads or racks for the package units to set on outside
- Any other materials or equipment not listed above

Total Quote: 96,170.00

This proposal is valid for 30 days.

Thank you for this opportunity to serve you. Please feel free to contact me with any questions.

Robert Cubine

Owner: Veteran Pride A/C & Heat, LLC

Email: rcubine1203@gmail.com

_____

Date 5/5/2025