



1630 Commerce Pkwy, suite 1, bloomington, Illinois 61704 \* 3092758661

Date: Oct 21, 2025

**Quote Number: Q-25-1614**

*Re: Room 124 heating coil replacement*

Attn: Robert Bourne  
Property: Ridgeview Jr/Sr High School  
Address: 202 E. Wood St., Colfax, IL 61728

As requested, we are pleased to offer our proposal for the above referenced project as follows:

### **SCOPE OF WORK**

Isolate unit ventilator from the main power supply.  
Isolate unit ventilator from the hydronic heating supply.  
Pump down associated AC condenser.  
Remove associated hydronic heating supply/return piping.  
Remove associated refrigeration piping  
remove DX section of unit ventilator.  
Remove failed heating coil.  
Install new OEM 3-row heating coil.  
Install DX section back into unit ventilator.  
Reconnection hydronic heating piping.  
Reconnection refrigeration piping.  
pressure test, evacuated and charge with existing refrigerant.  
Test, inspect, and record of proper operation.

- \*This quote does not include any additional refrigerant if any is needed.
- \*Heating coil has an eight-day lead time.
- \*This quote is to be performed during normal business hours Monday-Friday 7:00AM-3:30PM
- \*This quote excludes holidays
- \*Classroom will need to be unoccupied for up to three working days.
- \*This quote will be treated as a not to exceed.

### **QUALIFICATIONS**

1. Our offer is firm for 30 thirty days from the date listed above.
2. Our offer is predicated upon a clear and accessible area that will be made available by others, where our work is to be performed.
3. Unless noted in the specific inclusions, our work will be performed during our normal working hours and workweek.

**Total Proposal as Outlined Above.....**

**\$12,107.08**

Our goal is to provide quality construction and competitive pricing. We will accomplish this by performing efficiently, timely, safely and to your complete and total satisfaction. Thank you for allowing us to proceed by authorizing the work in the space provided below.

Sincerely,