Add Item to Schedule

1. COUNTY CODE	2. DISTRICT CODE/NAME	3. APPLICATION YEAR/ROUND
022, Dupage	**19022034002, Winfield SD 34**	**2027, 1**

	Item I.D.	Facility Name	Facility Address	Facility Description	Project Description	Project Location	Priority Code	Category Code	Est. cost	Est. Start Date	Est. Completion Date
Open	1	WINFIELD CENTRAL SCHOOL	0s 150 Park St, Winfield	Winfield Central School was built in 1972. An addition was added in 2002. It services 230 students in preschool and 3rd through 8th grade. The building is 68,497 sq ft.	Replace Rusting and inoperable doors. Add safety glazing to gym doors.	Music room, office, and gymnasium	B	WIND	$10,000.00	02/01/2027	08/10/2027
Open	2	WINFIELD PRIMARY SCHOOL	0s 150 Winfield Road, Winfield	The original structure was built in 1882. Additions were added throughout the 1950s. Currently the building house 240 students in grades preschool through second grade. The building is 31,614 square feet.	Replace original doors including exit doors, bring door knobs up to compliance.	East Wing	B	WIND	$21,500.00	02/01/2027	08/10/2027
Open	3	WINFIELD CENTRAL SCHOOL	0s 150 Park St, Winfield	Winfield Central School was built in 1972. An addition was added in 2002. It services 230 students in preschool and 3rd through 8th grade. The building is 68,497 sq ft.	Bring wiring up to code. Replace use of extension cords with properly wired junction boxes and conduit, enclose exposed wiring, and replace broken electrical receptacles	Throughout Central school	B	ELEC	$20,000.00	02/01/2027	08/10/2027
Open	4	WINFIELD PRIMARY SCHOOL	0s 150 Winfield Road, Winfield	The original structure was built in 1882. Additions were added throughout the 1950s. Currently the building house 240 students in grades preschool through second grade. The building is 31,614 square feet.	Bring wiring up to code. Replace use of extension cords with properly wired junction boxes and conduit, enclose exposed wiring, replace broken electrical receptacles, add illumination to electrical panel area	Throughout Building.	B	ELEC	$11,000.00	02/01/2027	08/10/2027
Open	5	WINFIELD CENTRAL SCHOOL	0s 150 Park St, Winfield	Winfield Central School was built in 1972. An addition was added in 2002. It services 230 students in preschool and 3rd through 8th grade. The building is 68,497 sq ft.	Add smoke detectors to increase coverage in order to meet code to 4 areas. Add fire alarm strobe lights to 6 instructional areas.	Throughout Central school -	B	FIRE	$12,000.00	02/01/2027	08/01/2027
Open	6	WINFIELD PRIMARY SCHOOL	0s 150 Winfield Road, Winfield	The original structure was built in 1882. Additions were added throughout the 1950s. Currently the building house 240 students in grades preschool through second grade. The building is 31,614 square feet.	Add emergency fuel burner switch	Room 004A (basement)	B	HVAC	$5,000.00	02/01/2027	08/10/2027
Open	7	WINFIELD CENTRAL SCHOOL	0s 150 Park St, Winfield	Winfield Central School was built in 1972. An addition was added in 2002. It services 230 students in preschool and 3rd through 8th grade. The building is 68,497 sq ft.	Add emergency lighting to multiple areas of the building. Replace inadequate lighting fixtures and partially covered fixtures.	Throughout Building	B	ELEC	$18,000.00	02/01/2027	08/01/2027
Open	8	WINFIELD PRIMARY SCHOOL	0s 150 Winfield Road, Winfield	The original structure was built in 1882. Additions were added throughout the 1950s. Currently the building house 240 students in grades preschool through second grade. The building is 31,614 square feet.	Add emergency lighting to multiple areas of the building. Replace partially covered fixtures.	Throughout building	B	ELEC	$6,250.00	02/01/2027	08/10/2027
Open	9	WINFIELD CENTRAL SCHOOL	0s 150 Park St, Winfield	Winfield Central School was built in 1972. An addition was added in 2002. It services 230 students in preschool and 3rd through 8th grade. The building is 68,497 sq ft.	Route plumbing termination out of building	Storage room 130	B	PLMB	$3,000.00	02/10/2027	08/10/2027

Open	10	WINFIELD PRIMARY SCHOOL	0s 150 Winfield Road, Winfield	The original structure was built in 1882. Additions were added throughout the 1950s. Currently the building house 240 students in grades preschool through second grade. The building is 31,614 square feet.	Investigate and repair plumbing emitting discolored water.	Rooms 111 and 113	B	PLMB	$2,000.00	02/01/2027	08/10/2027

Total Estimated Project Cost	$108,750.00
Total Requested Grant Amount	$50,000.00
Total Reserved Local Funds(District Responsibility):	$50,000.00
Total Reserved Remaining Funds (District Responsibility):	$8,750.00