

[Add Item to Schedule](#)

1. COUNTY CODE 019, Dekalb						2. DISTRICT CODE/NAME 16019429026, Hinckley Big Rock CUSD 429			3. APPLICATION YEAR/ROUND 2027, 1		
Item I.D.	Facility Name	Facility Address	Facility Description	Project Description	Project Location	Priority Code	Category Code	Est. cost	Est. Start Date	Est. Completion Date	
Open 1	HINCKLEY-BIG ROCK HIGH SCHOOL	700 E. Lincoln Highway, Hinckley	Hinckley-Big Rock High School was originally built in 1954 with additions completed in 1966 and 2003. The building was constructed via Type II non-combustible construction. HBRHS is a 89,798 (+/-) square feet one story building with mezzanine level. Exterior wall construction is face brick with CMU backup and is built on a concrete slab with vinyl composition tile, terrazzo, and carpet finish. Classrooms are air conditioned by chilled water unit ventilators and VAV air handling systems.	Replacement of the existing roof system on the Hinckley-Big Rock High School gym. The project includes complete removal and disposal of the existing roofing system down to the existing cementitious wood fiber roof deck. The roof deck will be primed and a V-Force vapor barrier installed. Over the structurally sloped deck, the contractor will install two layers of 2.6-inch polyisocyanurate insulation (R-30) set in low-rise foam adhesive, along with 1/2-inch-per-foot tapered insulation panels to direct water to existing roof drains and improve drainage. A new 60-mil black EPDM single-ply roofing membrane will be fully adhered over the new insulation in accordance with manufacturer specifications. The work also includes installation of base flashings at vertical walls and finished flashings at existing vent flues and mechanical curbs. Approximately 320 linear feet of anchor bar edge metal and 310 linear feet of right-angle drip edge will be furnished and installed in 24-gauge prefinished	Hinckley-Big Rock High School gymnasium roof, including the exterior roof area and associated roof perimeter, flashing, vent flue, and mechanical curb areas. The work affects the gym roof only and does not include the roofs of other areas of the high school.	D	ROOF	\$295,515.00	06/01/2027	08/15/2027	

Total Estimated Project Cost	\$295,515.00
Total Requested Grant Amount	\$50,000.00
Total Reserved Local Funds(District Responsibility):	\$50,000.00
Total Reserved Remaining Funds (District Responsibility):	\$195,515.00