TCI GEOTHERMAL
A DIVISION OF TCI COMPANIES, INC.

Test Well Proposal

www.tcicompaniesinc.com

Project: Monroe Center Elementary School	Re: Geothermal Boring and Test
Location: 17500 IL-71, Monroe Center, IL 61052	
Date: October 2, 2026	

WORK INCLUDED

- 1 – 500' boring
- 1.25" SDR9 U-Bend grouted with thermally enhanced bentonite grout to achieve 1.0 Btu/hr-ft-F
- (1) Thermal Conductivity test and report
- (1) Drill Log
- (1) Permit

Total $30,000.00

ALTERNATE

-

NOTES/WORK NOT INCLUDED:

- Construction Fence
- Private Utility Locates by others
- Spoil Removal – Spoils to remain onsite at test well location
- Contaminated Spoil Testing/Disposal
- Well location staking
- Hydrant Permit/Meter – Access to 2" water line will be required for drilling.

* If you have any questions, please contact me at 309-965-2057.

Submitted by: Joe Barth

Approved By:

Name:_____

Date:_____

Signature:_____