Nesci Landscapes Inc.

11080 Maudlin rd
New Buffalo, Michigan 49117
7082059886
nescilandscapes@Gmail.com

ESTIMATE
EST0011

DATE
Feb 23, 2026

TOTAL
USD $74,270.00

TO

NBAS

1112 East Clay st. New Buffalo,MI

DESCRIPTION	RATE	QTY	AMOUNT
Option 1 retaining wall: Install natural stone, outcropping, retaining wall along retention area by third base line of baseball field. Wall to be approximately 5 feet tall and taper down to 1 feet. Wall to stop behind dugout area. Excavate and install gravel footing for wall. Install natural stone outcropping layered between 6 inches and 10 inch thick pieces. Backfill with open drainage limestone. Prep to allow concrete to be poured up to wall. Install tubes for concrete pour of post for future fence. Remove three trees along parking lot near garbage area.l	$49,170.00	1	$49,170.00
Demolition of garbage area: Remove brick wall and dispose. Remove wall to existing concrete foundation. Leave concrete foundation flush to grade.	$3,800.00	1	$3,800.00
Option 2 retaining wall extension:	$21,300.00	1	$21,300.00

TOTAL **USD $74,270.00**

Bid Tabulation Sheet

New Buffalo Area Schools
1112 E. Clay St New Buffalo, MI 49117

Type:	**Retaining Wall**
Project Address:	**1112 E. Clay St.**
Bid Opening Date:	**3/2/2026**

Contactor Name	**Bid Amount**					
	Base	Demolition	Alternate	Total		
Nesci Lanscapes Inc	49,170.00	3,800.00	21,300.00	74,270.00		
BG Construction	90,315.00		57,750.00	148,065.00		
Pavers Plus of West Michigan	54,344.50		25,596.00	79,940.50		