

# Pacific Northwest Fence Co.

3-13-25

Winston/Dillard School Dist.  
McGovern Elementary School  
600 NW Elwood Dr.  
Winston, OR 97496

Installation of approx. 973' of 6' galvanized chain link wire fence with two 12' single cantilever gate.

Installation of three single swing walk gates with panic bars.

Panic bar gates will have 4" x 4" square galvanized posts with 1 1/2" diameter pipe header.  
Gate height to be 7' tall.

Remove existing fence from job site.

\*Use approx. 335' of existing 1 5/8" top rail.

## Materials

1. 9 gauge commercial weight chain link wire
2. 1 5/8" diameter top rail 16 gauge tubing
3. 1 1/2" square walk gate frame and header
4. 1 7/8" diameter line post set 10' on center or less apart
5. 2 3/8" diameter terminal post
6. 4" diameter swing & cantilever gate post (Double Swing)
7. 4" x 4" square gate and latch post (Panic Bar)
8. 9 gauge bottom tension wire
9. All post set in concrete
10. All welded gate construction
11. All posts are schedule 40 commercial weight
12. Lockeye Panic bar
13. 24" Shield
14. Self closing hinges for walk gate with panic bar

A contract with all required State forms will be delivered before start of any work.

Prices include all materials and labor.

Payment to be made upon completion.

Price -----\$31,745.00

Please call with any questions.

John Heselius  
P.O. Box 179  
Roseburg, Oregon 97470  
office: (541)672-0482  
fax: (541)464-8671  
[john@pacificnorthwestfence.com](mailto:john@pacificnorthwestfence.com)