

E.T. PADDOCK ENTERPRISES, INC.

1475 Canal Street
P.O. Box 175
Lockport, Illinois 60441
Ph: 815/838-1300
FAX 815/838-1376

December 20, 2024

Tracy Reaska
Putnam County CUSD #535
400 East Silverspoon
Granville, IL. 61326
PH: 815-257-2238
EM: reaskat@pcschools535.or

RE: Putnam County Junior High School
13183 N. 350th Ave
McNabb, IL 61355

Tracy:

Enclosed is the proposal to install new power operation to the balcony bleachers at Putnam County Junior High School. Also, we highly recommend a bleacher service to ensure proper bleacher operation and safety.

OVERVIEW: Balcony Bleacher Bank: 13 Rows high X 78'-0" Approximate

Remove the existing power units and existing wiring from the balcony bleacher bank. Install (4) new PK-962 power units, (1) new wiring harness and (1) new pendant switch.

PRODUCT SPECIFICATION: MAIN GYMNASIUM

- Demolish existing power system and remove from each gymnasium.
- Install (4) new power units "PK-962" to the main bleacher bank (1) new wiring harness and (1) pendant switch.
- The floor traction power operation system shall consist of one motor frame assembly, for each section of bleacher within a single bleacher bank, or special arrangement of motors. All power units wired in parallel and operate as a single unit, extending as many rows of bleachers as desired. Each frame assembly shall have **two axles** with three wheels per axle. The floor traction wheels designed to be six inches in diameter, with a non-marking 50 to 55 durometer rubber surface approximately three inches wide. The rubber wheel surface shall be 3/4 inches thick and molded to a 4-1/4" diameter by 3" wide solid steel core wheel.
- Each frame assembly shall have a 1/2 horsepower electric motor, 143/1 ger ratio, 1.63 amps and 992 LBS of torque. Electrical requirements shall be 208-volt, three phase power.
- The assembly shall have a 16-gauge steel cover that protects the entire

motor, drive wheels, chain, and sprocket from debris. Each assembly shall have an 18 X 3-inch strip brush secured to the back of the unit to clear large debris from the path of the wheels during the stacking operation.

- Provide wiring, junction boxes, contactor boxes, motors, starters, and fuses from existing disconnect. All electrical work shall be completed per the requirements of the National Electrical Code and NFPA-70.
- Each bank of power operated bleachers shall be equipped with a single plug-in receptacle located at one end of the bleacher bank and installed in the face of the first-row kick board for easy access. Provide one hand-held walk-along pendant switch, with cord. The hand-held pendant switch shall be made of high-impact shock-resistant plastic with two push buttons, one for extending the bleachers and a separate push button for stacking the bleachers.

Total delivered and installed price balcony bleachers: \$18,820.00


BLEACHER SERVICE. Service includes, but is not limited to the following:

- Tighten all fasteners.
- Replace all missing fasteners.
- Straighten all bent brackets and components.
- Straighten and align all wheel channels.
- Remove excessive lubricants and grease.
- Lubricate all moving parts.
- Adjust and align each bleacher section in each bank to assure proper extending and stacking.

Total service cost balcony bleachers: \$2,384.00 ADD.

Notes: The above-listed service work does not include, unless otherwise noted and quantity given; repair or replacement of any components such as wheels, plastic seats, end rails, zero gravity ramps, aisle ways, tape, row locks, motor components, bleacher boards, handrails etc. Those listed items will be quoted separately and completed at a future time. The above power operating system does not include any electrical work; except a final hook up from the existing disconnect. A two-year standard warranty for defects is included in the new power operation. Please Note: Wheel Cleaning or cleaning underneath bleachers is not included and to be complete "by others." Any work not listed above deemed excluded.

✓ *Prevailing wage considerations are included for all above listed work for Putnam County, Illinois.*

Signed  _____
John Paddock