



GRAND STAGE

Chicago Spotlight art drapery studios

Rentals, Events & Production

Stage Rigging & Drapery

Lincoln Hall Middle School
Phase One Additions and Remodeling
Lincolnwood, Illinois

January 17, 2018

Page 1 of 1

Grand Stage drapery and rigging equipment, consisting of:

set# - description (distance from plasterline)

- #1 - Front curtain; 25 oz. IFR Charisma velour fabric, inherently flame retardant, 40 ft. wide pair x 14 ft. high, with 50% fullness sewn into flat box pleats, 12" onstage turnbacks, dust ruffle, chain weighted bottom, and H & H Specialties #416S heavy duty curtain track complete with all necessary accessories for manual, bi-parting operation, and 3/16" proof coil chain for dead hung installation (1 ft. 0 in.)
- #2 - Grand border; 25 oz. IFR Charisma velour fabric, inherently flame retardant, 34 ft. wide x 5 ft. high, with 50% fullness sewn into flat box pleats, grommet and tie top, 23 oz. black welding fabric protection border, sewn flat, 32 ft. wide x 4 ft. 6 in. high, and 1.5" schedule 40 pipe batten complete with internal expanding splice and 3/16" proof coil chain for dead hung installation (2 ft. 0 in.)
- #3 - First Electric; Electronic Theatre Controls #P1000E motorized batten hoist; designed for 208 volt, 3 phase operation, at 30 ft. per minute, 1.5 horsepower, 1500 lbs. capacity, with 1000 lbs. working load, 3 lift lines, 28 ft. long 1.5" schedule 40 pipe batten, integral plug-in strip, electrical cable management system, motor control station and all necessary accessories for complete installation (3 ft. 4 in. - electrical installation work by others)
- #4 - First pair legs; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 12 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and 2 sections of H & H Specialties #416W heavy duty curtain track complete with all necessary accessories for walk draw operation, and 3/16" proof coil chain for dead hung installation (2 ft. 0 in. to 7 ft. 6 in.)
- #5 - First border; ; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 34 ft. wide pair x 5 ft. high, with 50% fullness sewn into flat box pleats, and 1.5" schedule 40 pipe batten complete with internal expanding splice and 3/16" proof coil chain for dead hung installation (8 ft. 0 in.)
- #5A - Second pair legs; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 12 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and 2 sections of H & H Specialties #416W heavy duty curtain track complete with all necessary accessories for walk draw operation, and 3/16" proof coil chain for dead hung installation (8 ft. 6 in. to 14 ft. 0 in.)
- #6 - Rear traveler; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 34 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and and H & H Specialties #416S heavy duty curtain track complete with all necessary accessories for manual, bi-parting operation, and 3/16" proof coil chain for dead hung installation (15 ft. 0 in.)

Voluntary Alternate - Delete above motorized first electric pipe batten hoist (item #3), and provide:

- #3 - First Electric; 1.5" schedule 40 pipe batten, 28 ft. long, complete with internal expanding splice and 3/16" proof coil chain for dead hung installation (3 ft. 4 in.)

www.grandstage.com
312-332-5611

DEDUCT (\$26,550⁰⁰)



GRAND STAGE

Chicago Spotlight art drapery studios
Rentals, Events & Production Stage Rigging & Drapery

January 18, 2018

QUOTATION

RE: Lincoln Hall Middle School
Phase One Additions and Remodeling
Lincolnwood, Illinois

Grand Stage Company is pleased to provide the following proposal for your consideration:

Stage curtain and tracks at Lincoln Hall Middle School, Lincolnwood, Illinois; per the attached bill of materials dated 1/17/18

total work - \$ 54,900.00

voluntary alternate (deduct) - (\$ 26,550.00)

The above pricing includes complete delivery and installation at prevailing wage rates, and is firm for 45 days. The above pricing includes certificates of insurance, approval drawings, all manufacturer's services as specified and jobsite consultation as required by the contractor, theatre consultant, architect, engineer or owner. The above pricing does not include any electrical connections or electrical installation work. The above pricing does not include PE stamps or any structural engineering work that may be required for proper completion of the work. The above pricing includes all manufacturer's standard warranties. The above pricing does not include any applicable taxes or performance bonding. Terms are net 30 days on approved accounts. We will be happy to provide a quotation for performance bonding or alternate proposals upon request.

Thank you for the opportunity of quoting on your requirements.

Sincerely,

Grand Stage Company

Michael W. Hostetler

www.grandstage.com
312-332-5611