

# ***Olalla Onsite Services Inc.***

**Dustin Pippin: 541-530-6448 Address: 460 Hidden Hill lane Winston OR, 97496**

**Email: [olallaonsiteservices@gmail.com](mailto:olallaonsiteservices@gmail.com)**

**CCB: 233166**

**Date: 11/22/24**

**Bid Proposal For: DHS Greenhouse parking.**

**Location of Work: 1381 NW Douglas Blvd, Winston OR, 97496**

**Scope of Work:**

- Excavate area in front of greenhouse to make a consistent slope.
- Excavate 140' of ditch line for curtain drain that is 1' wide by 1' deep. Lay 4" perforated pipe in ditch and backfill with drain rock.
- Lay woven geo textile fabric on all 4 sides of greenhouse.
- Lay fabric 10' wide x 150' long on East side.
- Lay fabric 15' wide x 75' long on North side.
- Lay fabric 30' wide x 150' long on west side.
- Lay fabric 42' wide across south end.

- Cover with approximately 120 yards of 3/4" minus approximately 6" deep and pack rock.
- This a non prevailing wage project.

**General Exclusions:**

- Any work not listed in the "Scope of Work" section of this bid proposal.

**Total Cost of Project: \$9,500.**

Thank you for the opportunity to bid on this project! We hope to hear from you soon!