

Site Address

Client Details

McGovern Elementary School
Shelby Beard 541-671-6331
beards@wdsd.org
600 Elwood St.
Winston , Douglas, OR 97496

Sales Representative

Rick Randleman
[Cell: 541-802-6056](tel:541-802-6056)
rick@roseburgfence.com

We propose to provide and install the following:

Description	Quantity
A) Removal and Disposal of Existing 4ft High Chain Link Fence Included Exclusions: Existing footings, unless needed	
B) 72" High Galvanized Chain Link Fence 2 3/8" DIA SCH40 terminal posts, 1 7/8" DIA Line posts SCH40, set in approximately 24" deep concrete footings. 1 5/8" DIA 16 gauge top rail assembly. 2" diamond, knuckle x barb (barbs facing up) 9 gauge chain link fabric. 9 gauge continuous bottom tension wire assembly. Note: Approximately 325' of existing top rail to be re-used.	1,002 LF
C) 84" High x 48" Wide - Walk Gate Assembly 4" x 4" Square galvanized support posts, set in approximately 30" deep concrete footings. Custom fabricated gate assembly to consist of: 1.5" square frame work, 1.5" Square header, self closing mammoth hinges, free exit panic bar with 24" high shield. 9 gauge chain link fabric in-fill and construction ready lock cylinder. Note: Locksmith to re-key lock cylinder (by others).	3
D) 72" High x 144" Wide - Cantilever Slide Gate Assembly 4" DIA SCH40 support posts, set in approximately 36" deep concrete footings. Supporting 144" wide (clear opening) cantilever slide gate, with nylon cantilever industrial wheels, with covers. Cantilever gate assembly to be fabricated of: 2 3/8" DIA top and bottom frame, continuously, 2 3/8" DIA end supports, with top bump stop. 1 7/8" vertical support and 1 5/8" diagonal bracing. All material to be SCH40, galvanized. 9 gauge chain link fabric in-fill.	2

Total Price \$43,830.00

Deposit Amount \$21,915.00

Payment Balance \$21,915.00

