Conceptual Engineer's Opinion of Probable Costs

William Hatch Elementary School

Oak Park, IL September 15, 2014




				Unit	Extended
tem	Description	Unit	Quantity	Price	Price
	Remove Existing Vegetation & Landscaping	LS	1	\$750.00	\$750.00
	Saw Cut (Full Depth)	LF	130	\$4.50	\$585.00
	Bit. Pavement Removal (Bit. Layer Only)	SY	115	\$15.00	\$1,725.00
	Bit. Pavement Removal (Full Depth)	SY	300	\$25.00	\$7,500.00
	Re-Grade Existing Subgrade	SY	300	\$15.00	\$4,500.00
	Remove Handrail & Dispose	LF	40	\$10.00	\$400.00
	Concrete Curb Removal	LF	45	\$10.00	\$450.00
	Concrete Sidewalk Removal	SY	100	\$20.00	\$2,000.00
	Remove Existing Signage	Ea.	1	\$200.00	\$200.00
	Off Site Disposal	LS	1	\$2,000.00	\$2,000.00
	Subtotal		Visit Edition		\$20,110,00

				Unit	Extended
tem	Description	Unit	Quantity	Price	Price
	Bituminous Surface Course Only	SY	115	\$20.00	\$2,300.00
	Full Depth Pavement Section	SY	300	\$50.00	\$15,000.00
	Pavement Striping	LS	1	\$2,000.00	\$2,000.00
	Concrete Curb	LF	45	\$20.00	\$900.00
	Concrete Sidewalk	SY	110	\$65.00	\$7,150.00
	Concrete Steps	LS	1	\$1,000.00	\$1,000.00
	Retaining Wall (Pour in Place)	LF	21	\$175.00	\$3,675.00
	Handrail Free Standing	LF	115	\$175.00	\$20,125.00
	Subtotal		2-10-01		\$52,150.00

Item	Description	Unit	Quantity	Unit Price	Extended Price
	Accessible Parking Space Sign And Installation	Ea.	2	\$750.00	\$1,500.00
	Seeding & Landscape Restoration	LS	1	\$5,000.00	\$5,000.00
	Erosion Control Measures	LS	1	\$1,200.00	\$1,200.00
	Subtotal		a large		\$7,700.00

Opinion of Total Construction Costs	\$111,944.00
12% A/E Fees	\$11,994.00
Subtotal	\$99,950.00
15% Contingency	\$11,994.00
10% General Conditions	\$7,996.00
Total Costs from Above	\$79,960.00



DUTING

DUTING

DO TOM Branch

DO TO

ERIKBSON
ENGINEERING
ABSOCIATES, LTD.
19 BOOMERS DRIVE, SELL
19 BOOMERS
10 BOOMERS

WILLIAM HATCH
ELEMENTARY SCHOOL
ORLAND PARK SCHOOL DISTRICT 97
1000 N. Ridgeland Ave,
Oak Park, Illinols


Noo	erent for	lank .	
		on Debe:	
No.	Equirals Date		
_			
_			_
_			


200 09/15/14

CONCEPTUAL DEMOLITION PLAN

__ C-1

NOT FOR CONSTRUCTION





C 782.79 C 782.79 C 782.70 F 793.71 F 794.70 1/9 795.20 -3% (<u>)</u>

ENGINEERING

ASSOCIATES, LTD.


WILLIAM HATCH
ELEMENTARY SCHOOL
ORLAND PARK SCHOOL DISTRICT 97
1000 N. Ridgeland Ave,
Oak Park, Illinois

09/15/14

CONCEPTUAL GEOMETRY PLAN

C-2

NOT FOR CONSTRUCTION



DOSTING

DOS

Milliarrelation Provident Removed (Full Depth)

Milliarrelation Provident Removed (Mill & Resources)

* Concrete Shievash Section

WILLIAM HATCH
ELEMENTARY SCHOOL
ORLAND PARK SCHOOL DISTRICT 97
1000 N. Ridgeland Ave,
Oak Park, Illinois

ENGINEERING

ASSOCIATES, LTD.

In. Date Description

09/15/14

CONCEPTUAL GRADING AND PAVING PLAN

NOT FOR CONSTRUCTION

EEA → P.\R.an\Dok Park Schools Accessibility\Drawings\Siteplon_William He Pictted: 9/22/1s @ 12:1spm By: ckappner

C-3

Conceptual Engineer's Opinion of Probable Costs

Lincoln Elementary School

Oak Park, IL September 15, 2014





Divisi	Division A - Site Demolition					
				Unit	Extended	
Item	Description	Unit	Quantity	Price	Price	
	Saw Cut (Full Depth)	LF	35	\$4.50	\$157.50	
	Concrete Sidewalk Removal	SY	30	\$20.00	\$600.00	
	Remove Existing Ramp Walls / Footings / Handrail	LF	38	\$100.00	\$3,800.00	
	Off Site Disposal	LS	1	\$500.00	\$500.00	
10:151	Subtotal			TOTAL NEWS	\$5,057.50	


Ramp Retaining Wall (Pour in Place) LF 48 \$175.00 \$				Unit	Extended
Ramp Retaining Wall (Pour in Place) LF 48 \$175.00 \$	Description	Unit	Quantity	Price	Price
	ewalk	SY	30	\$65.00	\$1,950.00
Handrail LF 50 \$175.00 \$	ng Wall (Pour in Place)	LF	48	\$175.00	\$8,400.00
		LF	50	\$175.00	\$8,750.00


Divisio	Division C - Misc.						
				Unit	Extended		
Item	Description	Unit	Quantity	Price	Price		
	Seeding & Landscape Restoration	LS	1	\$750.00	\$750.00		
	Erosion Control Measures	LS	1	\$500.00	\$500.00		
	Subtotal		767 7002		\$1,250.00		

Total Costs from Above	\$25,407.50
10% General Conditions	\$2,541.00
15% Contingency	\$3,811.00
Subtotal	\$31,759.50
12% A/E Fees	\$3,811.14
Opinion of Total Construction Costs	\$35,571.00









ENGINEERING ASSOCIATES, LTD. LINCOLN ELEMENTARY SCHOOL ORLAND PARK SCHOOL DISTRICT 97 1111 S. Grove Ave, Oek Park, Illinois

CONCEPT SKETCH

EX-3

Recognic At Reptore 247 ST of Edited & Recognic

NOT FOR CONSTRUCTION

Preliminary Engineer's Opinion of Probable Costs

Whittier Elementary School

Oak Park, IL September 15, 2014





Divisio	n A - Site Demolition				
				Unit	Extended
ltem	Description	Unit	Quantity	Price	Price
	Saw Cut (Full Depth)	LF	35	\$4.50	\$157.50
	Concrete Sidewalk Removal	SY	65	\$20.00	\$1,300.00
	Off Site Disposal	LS	1	\$500.00	\$500.00
2000	Subtotal		1211		\$1,957.50


Divisi	on B - Site Pavement Improvements				
				Unit	Extended
Item	Description	Unit	Quantity	Price	Price
	Concrete Sidewalk	SY	65	\$65.00	\$4,225.00
	ADA Tactile Warning Surface	LS	2	\$250.00	\$500.00
	Subtotal				\$4,725.00

Divisio	on C - Misc.				
				Unit	Extended
Item	Description	Unit	Quantity	Price	Price
	Seeding & Landscape Restoration	LS	1	\$750.00	\$750.00
	Erosion Control Measures	LS	1	\$500.00	\$500.00
	Subtotal				\$1,250.00

Total Costs from Above	\$7,932.50
10% General Conditions	\$793.00
25% Contingency	\$1,983.00
Subtotal	\$10,708.50
12% A/E Fees	\$1,285.02
Opinion of Total Construction Costs	\$11,994.00








WHITTIER ELEMENTARY SCHOOL ORLAND PARK SCHOOL DISTRICT 97
715 N. Harvey Ave., Oak Park, Illinols

ENBINEERING ASSOCIATES, LTD.

CONCEPT SKETCH

NOT FOR CONSTRUCTION

EX-2



Preliminary Engineer's Opinion of Probable Costs

Longfellow Elementary School

Oak Park, IL

September 15, 2014




				Unit	Extended
ltem	Description	Unit	Quantity	Price	Price
	Saw Cut (Full Depth)	LF	50	\$4.50	\$225.00
	Concrete Sidewalk Removal	SY	80	\$20.00	\$1,600.00
	Remove Existing Ramp Walls / Footings / Handrail	LF	42	\$100.00	\$4,200.00
	Off Site Disposal	LS	1	\$1,000.00	\$1,000.00
3	Subtotal		8-50 m340 p		\$7,025.00

				Unit	Extended
tem	Description	Unit	Quantity	Price	Price
	Concrete Sidewalk	SY	80	\$65.00	\$5,200.00
	ADA curb cuts at street	Allow	1	\$800.00	\$800.00
	Ramp Retaining Wall (Pour in Place)	LF	42	\$175.00	\$7,350.00
	Handrail - Free Standing	LF	44	\$175.00	\$7,700.00
	ADA Tactile Warning Surface	LS	1	\$250.00	\$250.00
	Subtotal				\$21,300.00

DIVISIO	on C - Misc.			Unit	Extended
Item	Description	Unit	Quantity	Price	Price
	Seeding & Landscape Restoration	LS	1	\$750.00	\$750.00
_	Erosion Control Measures	LS	1	\$500.00	\$500.00
	Subtotal				\$1,250.00


Opinion of Total Construction Costs	\$41,405.00
12% A/E Fees	\$4,436.28
Subtotal	\$36,969.00
15% Contingency	\$4,436.00
10% General Conditions	\$2,958.00
Total Costs from Above	\$29,575.00




Parraya & Radages Juli SE

£ 6.60 Can







NOT FOR CONSTRUCTION



LONGFELLOW ELEMENTARY SCHOOL ORLAND PARK SCHOOL DISTRICT 97 715 N. Highland Ave, oak Park, Illinols

CONCEPT SKETCH

EX-4