FLR Sanders, Inc.
3079 92nd Avenue
Princeton, MN 55371

Proposal

DATE: 12/3/2024

PROPOSAL FOR:

Maple Lake
Brad Neutz
200 Hwy 55 East
Maple Lake MN 55358

Project:

DESCRIPTION

Project: Elementary Gym Floor Sanding
Discounted Project Pricing per Cooperative Purchasing Connection Contract Award for RFP 20.7 Hardwood Flooring

SAND, SEAL, FINISH AND PAINT GAME LINES ON GYMNASIUM FLOOR:

- Sand wood flooring using custom built double riding sanders designed to assure uniform finished surface. FLR Sanders, Inc. is an MFMA member and will sand and finish floor to exceed MFMA recommendations.
- Seal and finish wood floor utilizing Bona SuperSport, Advantage Defense or Hillyard Pro Series waterborne formula finish according to manufacturer instructions. Apply two (2) coats seal and two (2) coats finish.
- Game lines shall be applied utilizing compatible gymnasium floor paint applied according to manufacturer instructions. Precision taping machines will be used as required. As specified by the governing authority, game lines shall include the following:
  - Main Basketball Court
  - Main Volleyball Court

OPTION TO UPGRADE GRAPHICS AND COURT LAYOUT: Cost will be bid separately. FLR Sanders, Inc. offers artwork design services free of charge with any sand and finish project. Artwork revisions are designed and produced by FLRSanders. Inc. in conjunction with District. Associated costs will be determined by selected layout.

*** Proposal may be withdrawn if not accepted within 60 days.*

Total **$20,068.75**

All material is guaranteed to be as specified. All work to be completed in a substantial workmanlike manner according to specifications submitted, per standard practices. Customer responsible for all costs of collection including reasonable attorney fees and expenses. 208 three phase power and dumpsters by owner. Slab testing by FLR Sanders, Inc. Slab leveling by others. Unlimited access to jobsite required for schedule and drying times. List after hours contact:

FLR Sanders, Inc. *date*

Authorized Signature *date*

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made for material at time of delivery. Labor will be paid within 7 days of completion. Overdue invoices will acrue interest at 1.5% per month.