



# Beyond Budget Details

Total Lineal Feet = 78

- Based on ceiling height of 99-3/4"
- Framed 1/4" thick glass walls
- Clear laminated glass (STC 32)
- No electrical
- Trims and frames to be clear anodized aluminum or painted aluminum in standard color
- Walls ship unitized from the factory installed with integrated top trim and base channels including the leveling mechanisms
- Total adjustment +/- 3/4" at the base and +/- 3/4" float adjustment at the top
- Walls have an assembled panel thickness of 3"
- No structural header required; can connect to ceiling grid or drywall

Total Number of Doors = 3

- Single sliding doors (Qty: 2)
  - Frameless 3/8" Clear Tempered Glass
  - Partial Strike
  - 20" Ladder Pull
- Freeway opening (Qty: 1)
  - 83.75" Wide

## Exclusions

- Distraction markers and / or film application.
- Master keying of door hardware.
- Sensors, push button, exit button, and other security devices.
- Card readers, harnesses, position switches, power supplies, and other wiring.

## Lead Time

- Approximately 6-8 weeks from time of signed shop drawings to time of ship.
- After Customer acceptance and prior to order, field dimensions are verified and hold dimensions are agreed upon in writing.
- Orders are contingent upon approval of shop drawings
  - Includes product, freight, and installation (tax excluded)
  - Installation budgeted based on non-union unload and installation during regular hours
  - 50% deposit required upon order
  - Quote valid for 30 days

Product: \$21,725.15

Freight: \$731.25

Install: \$6,206.25

**Total: \$28,662.65**