

Scope of Work: Track Resurfacing

The scope of this project includes all labor, materials, equipment, and supervision necessary to complete the resurfacing of the athletic track. The work shall be performed in accordance with industry standards and applicable regulations to ensure a safe, durable, and high-performance running surface.

Project tasks include, but are not limited to:

1. Site Preparation:

- Inspection and assessment of the existing track surface.
- Cleaning, removal of debris, and minor vegetation around the track area.
- Repair of any structural damage or surface irregularities.

2. Surface Repairs:

- Crack filling and patching of damaged or deteriorated sections.
- Leveling of any uneven areas to restore proper grading and drainage.

3. Resurfacing:

- Application of a new synthetic or polyurethane track surface as specified.
- Installation of multiple layers, including base and top coats, to ensure durability and performance.
- Color coating and texture finishing of the surface.

4. Line Marking and Striping:

- Accurate layout and painting of lane lines, start/finish lines, and event markings according to NFHS/NCAA standards (or relevant governing body).

5. Clean-Up and Final Inspection:

- Site clean-up and removal of all construction-related debris.
- Final walkthrough and inspection with owner representatives to confirm completion to specifications.