



101 Josephine Ln (P) 972-721-9796
Grand Prairie, TX 75050 (F) 972-721-1755

Bid Proposal

Date	Rep	Estimate #
12/20/2018	RRA	89224

Billing / Customer Name
Quanah ISD PO Box 150 Quanah, TX 76252

Service Address
Quanah ISD PO Box 150 Quanah, TX 76252

PO Number	Terms	Project
	Net 30	

Item	Description
Concrete	INSTALL NEW CONCRETE SPEED HUMP/RAISED WALKWAY: (Approx 480 SqFt (16x30 driveline), 1 area, 15CY, 50R, 2D,96H) 1. Sawcut, excavate and remove concrete, pavers and related debris from job site. 2. Rework and compact base with vibratory compactor as needed. 3. Install cushion sand pad as necessary. 4. Drill and dowel vertical surfaces on adjacent concrete. 5. Install 8" of 3500 PSI concrete with #3 rebar on 18" centers (6" above grade). 6. Install PVC piping beneath concrete along curbs for water to flow 7. Saw control joints to match existing or a maximum 15' on center and perimeter of each repair. 8. Hand trowel and broom to finish. ***Not responsible for irrigation or items buried in concrete.
Concrete Sidew...	INSTALL SIDEWALK LEVEL WITH NEW WALKWAY/SPEED HUMP: (Approx 80 SqFt (10X4 each side of street), 2areas) 1. Barricade work area, excavate and remove damaged debris from job site. 2. Rework and compact base with vibratory compactor as needed. 3. Install cushion sand pad as necessary. 4. Drill and dowel vertical surfaces on adjacent concrete. 5. Install 6-8" of 3500 PSI concrete with #3 rebar on 18" centers. 6. Hand trowel and broom to finish. **Does not include landscape repair.
Trip Charge	

Thank you for the opportunity.	Subtotal
CI Pavement is not responsible for damage to underground utilities or graffiti on new pavement. Any invoice past due will be subject to a late fee compounded at a rate of 2.0% per month prorated. Any alteration from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the proposal. Payment terms shall be 50% up front 50% upon completion. This proposal expires 30 days from date listed.	Sales Tax (0.00)
	Total

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. CI Pavement. is authorized to do the work as specified. Payment will be made as outlined above.

Signature: _____

Phone #	Fax #
972-721-9796	972-721-1755



101 Josephine Ln (P) 972-721-9796
Grand Prairie, TX 75050 (F) 972-721-1755

Bid Proposal

Date	Rep	Estimate #
12/20/2018	RRA	89224

Billing / Customer Name
Quanah ISD PO Box 150 Quanah, TX 76252

Service Address
Quanah ISD PO Box 150 Quanah, TX 76252

PO Number	Terms	Project
	Net 30	

Item	Description
	Notes: 1) Includes approximately 20 square feet in asphalt parking area to accomdate new slope 2) Estimate exludes permit from city of Quanah 3) Entire area to be shut down and work completed in one mobilization

Thank you for the opportunity.	Subtotal \$10,920.00
CI Pavement is not responsible for damage to underground utilities or graffiti on new pavement. Any invoice past due will be subject to a late fee compounded at a rate of 2.0% per month prorated. Any alteration from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the proposal. Payment terms shall be 50% up front 50% upon completion. This proposal expires 30 days from date listed.	Sales Tax (0.00) \$0.00
	Total \$10,920.00

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. CI Pavement. is authorized to do the work as specified. Payment will be made as outlined above.

Signature: _____

Phone #	Fax #
972-721-9796	972-721-1755