

# Pacific Northwest Fence Co.

4-2124

Winston/Dillard School Dist.  
620 NW Elwood Dr.  
Winston, OR 97496

Job Site: Lookingglass Elementary School

Installation of approx. 863' of 6' galvanized finish chain link fence.  
Installation of five approx. 6' x 3' single swing walk gates with panic bars and self closers.  
Installation of one approx. 6' x 3' single swing walk gate.  
Installation of one approx. 6' x 12' single swing drive gate.  
Installation of one approx. 6' x 10' single swing drive gate supplied by school dist.

Panic bar gates to have 4" square frame built around and over top of gate. Gate to have adjustable hinges.

## Chain Link Materials

1. 11 gauge chain link wire
2. 1 5/8" diameter top rail
3. 2 3/8" diameter line post set 10' on center or less apart
4. 2 7/8" diameter terminal post
5. 4" diameter drive gate post
6. 4" square posts (Panic Bar)
7. 1 1/2" square gate frame and frame header (Panic Bar)
8. 9 gauge bottom tension wire
9. All post set in concrete
10. All welded gate construction
11. All posts commercial 40 weight
12. Lockeye 36" panic bar V-40 grade
13. Lockeye 24" tall shield
14. Keyed cylinder
15. Self closer
16. Adjustable hinges

A contract and all required state forms will be delivered before start of any work.

Price include all materials and labor.

Payment to be made upon completion.

Price-----\$48,593.00

Please call with any questions.

John Heselius  
P.O. Box 179  
Roseburg, Oregon 97470  
office: (541)672-0482  
fax: (541)464-8671  
[john@pacificnorthwestfence.com](mailto:john@pacificnorthwestfence.com)

# Pacific Northwest Fence Co.

Best Regards,

Brett Heselius

John Heselius  
P.O. Box 179  
Roseburg, Oregon 97470  
office: (541)672-0482  
fax: (541)464-8671  
[john@pacificnorthwestfence.com](mailto:john@pacificnorthwestfence.com)