

11/8/2022

Brian Johnson  
ARCON

**Project:** SD23 2023 HVAC- Equipment Pre-purchase

**Scope Summary:**

- This proposal constitutes cost for equipment being supplied by IMBERT for the upcoming 2023 HVAC modifications/installations. Please see attached IMBERT document showing details of equipment purchased.

**Annotations & Exclusions**

- ❖ Installation costs not included
- ❖ Extended equipment warranties

**Financial Investment**

Equipment only pricing      **\$402,333**


*Breakdown*

*IMMBERT*      *\$362,100*

*EMCOR MARKUP @ 10%*      *\$40,233*

Thank you

Christopher Beller  
Vice President of Construction  
EMCOR Team Mechanical  
(847) 521-0047  
[cbeller@emcor.net](mailto:cbeller@emcor.net)



# IMBERT INTERNATIONAL INC.

7030 N. Austin Avenue • Niles, Illinois 60714 • Main 847.588.3170 • Fax 847.588.3173 • www.imbertcorp.com

## QUOTATION

**Customer:** Chris Beller  
EMCOR Team Mechanical  
431 Lexington Ave  
Buffalo Grove, IL.

**Project:** School District 23  
2023 Phase 2  
Pre-Purchase

**Location:** Prospect Heights, IL.

**Date:** November 7, 2022

Chris –


The following is our proposal to for your review. The proposal includes replacing Thirty Two (32) Climatemaster heat pumps with new Climatemaster units including Climadry reheat option and adding Eight (8) electric heaters for the TS\_009 and 012 Climatemaster units.

### Tag: Climatemaster Heat Pumps

HP-110,304, 209, 121, 207, 205, 303, 310, 313, 411, 315A, 315B, 503, 418, 601, 704, 100, 107, 109, 112B, 114, 112A, 115, 117,395, 708/710, 119, 120, 600A, 600B, 307, 308

(32) Replacement Climatemaster Horizontal Style Ground Water Source Heat Pumps with New Units with Climadry Option

Quantity (3) TEH-026  
Quantity (2) TEH-038  
Quantity (5) TEH-049  
Quantity (3) TEH-064  
Quantity (4) TEV-026  
Quantity (2) TEV-049  
Quantity (1) TLV-084  
Quantity (1) TLV-192  
Quantity (1) TLV-300  
Quantity (4) TRE-060  
Quantity (2) TRE-072  
Quantity (1) TSV-018  
Quantity (3) TSV-024  
32 Total



**ITEM 2: Electric Duct Heaters for Existing TS\*09 and 12 Heat Pumps**

**HP-301, 302, 706, 113, 101, 102, 103, 104**


**(8) Adding electric duct heaters for reheat**

Quantity (5) Brasch 12" x 12" 2 KW 2 Stage Electric Duct Booster Heating Coil  
Quantity (3) Brasch 12" x 12" 3 KW 3 Stage Electric Duct Booster Heating Coil

Electric heaters include Two or Three stage magnetic contactor, control transformer air flow switch and manual reset temperature switch. All other duct accessories and control interface are provided by others.

**SUMMARY OF UNITS/TAGS**

<b>Tag</b>	<b>New Model W/Climadry</b>
HP-110	TEH064
HP-304	TEH038
HP-209	TEH026
HP-121	TEH026
HP-207	TEH026
HP-205	TEH049
HP-303	TEH049
HP-310	TEH038
HP-313	TEH064
HP-411	TEV026
HP-315A	TEH049
HP-315B	TEH049
HP-503	TEH049
HP-418	TEH049
HP-601	TEV038
HP-704	TSV024
HP-100	TSV024
HP-107	TSV024
HP-109	TSV018
HP-112B	TEV049



# IMBERT INTERNATIONAL INC.

7030 N. Austin Avenue • Niles, Illinois 60714 • Main 847.588.3170 • Fax 847.588.3173 • www.imbertcorp.com

HP-114		TEV026
HP-112A		TEV049
HP-115		TEV026
HP-117		TLV192
HP-395		TLV300
HP-708/710		TLV048
HP-119		TRE060
HP-120		TRE060
HP-600A		TRE072
HP-600B		TRE072
HP-307		TRE060
HP-308		TRE060
HP-301	TSH009	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-302	TSH009	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-706	TSV012	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-113	TSV012	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-101	TSV009	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-102	TSV009	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-103	TSV012	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT
HP-104	TSV009	ADD FIELD INSTALLED AND WIRED ELECTRIC REHEAT

## General Notes:

1. Field provided and installed –Honeywell Control Board Interface – Provided by others
2. Thermostats, dehumidistats, CO2/Occupancy Sensors – Provided by others.
3. New power and control wiring to new duct heaters required – Provided by others
4. Roof curbs not included – We assume reuse of existing curbs.
5. Current Lead Times – Subject to change
  - a. TRE Series Rooftops are currently 20-22 weeks
  - b. TE, TLV, and TS Series Indoor units are currently 18- - 20 weeks
6. Modification to Tag HP-305, existing Climatemaster model TCH096 horizontal heat pump, is under review by AMSCO and not included in this proposal.
7. All materials provided carry a one year parts only warranty. (18 months from shipment or 12 months from startup.
8. Start Up assistance by factory trained technician is included



IMBERT INTERNATIONAL INC.

---

7030 N. Austin Avenue • Niles, Illinois 60714 • Main 847.588.3170 • Fax 847.588.3173 • [www.imbertcorp.com](http://www.imbertcorp.com)

Thank you for the opportunity to make this  
proposal.

Please advise any questions.

Very truly yours,

Bruce Svec