Request for Change Order



La Vernia ISD 2023 Bond Projects (231091)

No. RCO0050

Printed: October 01, 2025

Description PR#28 - HS Front Sidewalk & Switchback Date 2025-09-25

Status: Pending Review Days Impact: 45

Scope of Work

5M: Demolition of existing concrete flatwork, grading of new flatwork areas, set up and pour of new concrete sidewalks and switchback ramp. Includes haul off of demolition and spoils produced from concrete work.

RTM: Demolition and pour of new asphalt paving. Includes haul off of demolition and spoils produced from asphalt work.

Anchor Fence: Demo and reinstallation of wood privacy fence at HS Library per drawings. New 8' chain link fence with (3) new mangates that have panic egress hardware and lockable opening on public side.

Roadway Striping: Relocation of ADA parking signs and fire lane painting of new concrete curbs (By others)

JSR: Handrails for ramps and switchback.

Tree Protection: Cost for arborist to establish tree protection at designated trees.

Construction Aid: GPRS Cost to assist with locating underground utilities in the area of work.

See comments
on Trade Partner
Pricing

Site Fencing: Cost to deliver and remove construction fence required at the areas of work.

BC Self Perform: Fence Maintenance & Layout

Qualifications:

All work is assumed to be during normal working hours. Temporary Fence will be used secure limits of construction, vehicle and foot traffic to be diverted if affected.

Does not include any re-routing of UG Utilities (none shown). Cost for unforeseen conditions is not included.

Landscaping repairs, replacement, or re-establishing not included. (none shown).

Dumpsters and Sanitary Facilities to be taken from Cost of Work

All work shown on PR affects critical path activities at the High School Foundation Pad and Utilities. It is our understanding that all construction must be completed before student traffic can be re-routed.

Construction Impact: 30 working days.

Total Impact: 45 working days

This cost is to be funded from the owner's contingency allowance. Total of \$181,835.00

RCO Detail

| From | Description | Amount (\$) | |
|----------------------|-----------------------------|-------------|----|
| 5M Concrete LLC | Concrete | 81,400.00 | x |
| RTM Construction LTD | Earthwork | 10,822.00 | x |
| The Anchor Group Inc | Fences & Gates | 31,705.00 | x |
| Roadway Striping Inc | Pavement Markings | 1,665.00 | x |
| JSR Inc | Decorative Railings | 31,264.00 | x |
| | Landscaping Tree Protection | 4,627.84 | ok |

Construction Aids

Site Fencing

1,225.00 4,739.66

ok

x

Bartlett Cocke General Contractors LLC

BC Self Performed Work
Owner Contingency

14,386.50 **x**

-181,835.00 **ok**

Total (\$) \$0.00

| Submitted: | Approved: |
|--|-------------------------|
| Bartlett Cocke General Contractors LLC | Pfluger Architects, Inc |
| A Lexanter 1. Paylow | |
| Ву: | Ву: |
| Date: 10/1/2025 | Date: |

Alexander Ragland; Asst. Project Manager

| ı | | | | F . | | | | | | | | |
|----------------------|---------------------|---------------|-----------------------------|-----|------------|----|--------------|---------------|------------------|--------------------------|-----------------|------------|
| | | | \$ (36,169.14) | \$ | 181,835.00 | \$ | 145,665.86 | | | | | |
| Comp. Code No. | DESCRIPTION | | DELTA - Unfair + Fair | | BARTLETT | | AGCM COST | LABOR COST | MATERIAL COST | DELIVERY/ EQUIPMENT COST | OH & PROFIT | TOTAL |
| DEFINE | SCOPE | | | | | | | 65,818.30 | 49,406.83 | 17,198.39 | 13,242.35 | 145,665.86 |
| Div 01 | GPRS | GPRS | (0.00) | \$ | 1,225.00 | \$ | 1,225.00 | 0.00 | 1,113.64 | 0.00 | 111.36 | 1,225.00 |
| Div 03 | 5 M CONCRETE | Consusta | (14 540 62) | | 81,400.00 | \$ | 65 959 27 | 29 103 40 | 16 070 00 | 6 500 95 | 6.079.13 | 66 950 27 |
| DIV US | S W CONCRETE | Concrete | (14,540.63) | - | 81,400.00 | , | 66,859.37 | 38,102.40 | 16,079.00 | 6,599.85 | 6,078.12 | 66,859.37 |
| Div 05 | JSR, INC | Misc Metals | (7,507.23) | \$ | 31,264.00 | \$ | 23,756.77 | 9,004.80 | 10,657.26 | 1,935.00 | 2,159.71 | 23,756.77 |
| Div 32 | THE ANCHOR GROUP | Fencing | (3,537.70) | \$ | 31,705.00 | \$ | 28,167.30 | 9,461.10 | 11,825.00 | 4,320.54 | 2,560.66 | 28,167.30 |
| Div 32 | DAVEY TREE | Tree Protecti | 0.00 | \$ | 4,627.84 | \$ | 4,627.84 | 0.00 | 4,207.13 | 0.00 | 420.71 | 4,627.84 |
| Div 32 | ROADWAY STRIPPING | Stripping | (433.00) | \$ | 1,665.00 | \$ | 1,232.00 | 50.00 | 1,070.00 | 0.00 | 112.00 | 1,232.00 |
| Div 31 | RTM | Discipline | (2,104.72) | \$ | 10,822.00 | \$ | 8,717.28 | 5,000.00 | 2,624.80 | 300.00 | 792.48 | 8,717.28 |
| Div# | BARTLETT | Discipline | (4,455.70) | \$ | 14,386.50 | \$ | 9,930.80 | 4,200.00 | 785.00 | 4,043.00 | 902.80 | 9,930.80 |
| Div# | UNITED FENCE PANELS | Discipline | (3,590.16) | \$ | 4,739.66 | \$ | 1,149.50 | 0.00 | 1,045.00 | 0.00 | 104.50 | 1,149.50 |
| | | | | | | | | | | | | |
| | | | | | | | | 65,818.30 | 49,406.83 | 17,198.39 | 13,242.35 | 145,665.86 |
| | | | | | | | | 65,818 | 49,407 | 17,198 | 13,242.35 | 145,665.86 |
| | | | | | | | | | | TOTAL C | OST FOR THIS PR | 145,665.86 |

5M CONCRETE, LLC

480 Cibolo Point La Vernia, TX 78121 830-391-3519 Break out unit cost Reflect man hours and crew rate.

PR 28 LVISD - PR 28- priced per Cubic yard

Labor to Demo, Excavate & Haul off, Set up and Pour Back \$725.00 x 60 cubic yards Total:\$43,500.00

Concrete, Reinforcing Steel, Chairs & Compound, 2" Base under new sidewalks \$416.68 x 60 cubic yards Total:\$25,000.00

Equipment (skidsteer, saws, plate tamper) \$91.67 x 60 cubic yards

Total:\$5,500.00

Subtotal: \$74,000.00 10% OHP:\$7,400.00 **Total:\$81,400.00**


*Work to be performed on weekdays and normal working hours

***Exclude asphalt demo or replace, traffic control, temporary fencing, damage to unknown underground utilities, sprinkler work or landscaping, handrail or handrail coring/ sleeves, truncated dome pavers or plates, stair nosings or treads


Provide feedback how long it takes to do the work

This pricing appears to be high.

AGCM estimate - \$ 66,859.37




PR # 28 3 of 4



LEGEND

PROPERTY LINE EXISTING CONTOUR 780 PROPOSED CONTOURS + 786.75 ---- GB---- PROPOSED GRADE BREAK — — SWALE — PROPOSED SWALE

PROPOSED SPOT ELEVATION EXISTING ROOF DRAIN EXISTING ROOF DOWNSPOUT PROPOSED ROOF DOWNSPOUT



ABBREVIATIONS

EX EXISTING

TOC TOP OF CURB G GUTTER

INVERT SD STORM DRAIN

TW TOP OF WALL BW BOTTOM OF WALL

NOTES: SEE GENERAL NOTES C1.00 SEE GRADING NOTES C4.00

SCHOOL DISTRICT
S / RENOVATIONS
HIGH SCHOOL PENDENT SEADDITIONS SECHOOL 8 WIDE HIGH DISTRICT \ VERNIA


LA VERNIA INDEPENDENT SCHOOL DISTRICT 13600 US HIGHWAY 8 LA VERNIA, TX 78121



PROJECT NO. 05/30/2024 REVISIONS: 43 NEW SHEET/PR28 9/12/25

GRADING PLAN -LIBRARY WALK

PACKAGE 2



BASE OF EDGE TURNDOWN ALONG THIS RAMP MAY STEP
UP AS LONG AS BASE REMAINS
AT LEAST 1' BELOW ADJACENT GRADE

-WALKWAYS OTHER THAN RAMPS

TO INCORPORATE 12" THICKENED

RELOCATE EXISTING FENCE

EDGES BOTH SIDES, REF. DETAIL

ALL WALKWAYS ALONG
ACCESSIBLE ROUTE TO HAVE MAX
1:12 SLOPE ON RAMPS, MAX 5%

GRADE ON SLOPES, MAX 2%
SLOPE ON LANDINGS/CHANGES IN
DIRECTION, AND MAX 2% CROSS
SLOPE THROUGHOUT. CONTACT

ENGINEER IF ANY EXISTING
CONDITIONS REQUIRE
ADJUSTMENTS TO GRADES TO

MAINTAIN COMPLIANCE

∕-508.26 EX G

8.76 cu yd

₋509.30

12.06 cu yd ភ

TWO SETS OF 6"

HIGH BY 16" | WIDE STEPS

_508.64 EX G

TURNDOWN EDGES ALONG BOTH SIDES OF RAMPS AND LANDING REF. DETAIL SECTION THIS SHEET

Flush Curb

509.407

PROTECT EXISTING TREES AND
MINIMIZE DISTURBANCE WITHIN
TREE CANOPY/ROOT ZONE. TRIM
ANY TREE BRANCHES CONFLICTING
WITH PATHS. COORDINATE
TRIMMING WITH LANDSCAPE
ARCHITECT

ARCHITECT.

0.14 cu yd 509.10

Concrete Sidewalk

9.8 cu yd

6.24 cu yd

—— DOWEL TO EXISTING FLATWORK WITH #3 @ 12"

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

511.10 ~ MATCH EX-\

'/////

This takeoff accounts for the

deeper concrete at the ramp

ends and the stair steps



RTM Change Order #: 24-122-CO-21

JOB NAME: LVISD

DATE: 9/23/2025

High: \$4.50 - \$5.00 **DESCRIPTION: PR#28 Asphalt Patch** Material & Total Unit Takeoff Labor & Bid Item Bid Description Units Quantity Equipment Sub **Bid Total** 10 Saw Cut LF 226 5.50 5.50 1,243.00 20 2" Thick Asphalt Patch TON 75.00 225.00 2,700.00 12 \$ \$ 30 Mobilized Asphalt Crew EΑ \$ 5,500.00 \$ 5,500.00 \$ 5,500.00 40 Haul Off LOAD 450.00 Sub-Total \$9,893.00 10% OH&P \$989.30 Total: \$10,882.30 I get 7.47 tons NOTES: ${\bf 1.)}\ Change\ order\ for\ saw\ cutting\ and\ removing\ asphalt,\ replacement\ and\ haul\ off.$ 2.) Fine grading and curb replacement by others 3.) Asphalt to be 2" Type "D" Asphalt RTM Signature: What kind of machine Cold Planers can run \$ 5,000.00 Date: Rate appears high regardless Responsible Party Signature: Date:

Pricing, material cost and unit rates are subject to change, if this document is not signed and approved by responsible party 30 businesses days after issued date above.

Provide feedback how long it takes to do the work
This pricing appears to be high.

AGCM estimate - \$ 8,717.28

Anchor Fence

THE ANCHOR GROUP, INC.

Anchor Access

1470 N Business IH 35 New Braunfels, TX 78130 (830)606-5516

PROPOSAL

DATE: 9/23/25

BUYER: BARTLETT COCKE

ADDRESS:

ATTN: ALEXANDER RAGLAND PROJECT: LA VERNIA ISD **PR28** LOCATION: LA VERNIA, TX

This Proposal is valid for 30 days; otherwise, this Proposal shall be deemed withdrawn.

Anchor proposes to furnish materials, labor, supervision and equipment to perform the following:

PR28

346 LF OF 8' TALL CHAIN LINK FENCE & GATES

1-5/8" OD SCH 40 TOP & BRACE RAILS
2-1/2" OD SCH 40 LINE POST
3" OD SCH 40 TERMINAL POSTS
2" MESH, 9 GAUGE GALVANIZED CHAIN LINK FABRIC
9 GAUGE BOTTOM TENSION WIRE
3 EA 3' 6" OPENING SINGLE GATES
3" SQUARE GATE HINGE & LATCH POST
FURNISH SQUARE FRAME GATES WITH PANIC BAR HARDWARE
INLCUDES LOCINOX MAMMOTH HYDRAULIC SELF CLOSING HINGES
DETEX 40 OUTDOOR RATED PANIC BAR
INCLUDES LOCK BOX WITH INTERCHANGABLE CORE FOR OUTSIDE ENTRY

MATERIAL: \$14,642.00 LABOR: \$8,345.00 EQUIP: \$1,425.00 OH&P: \$2,442.00

SUM ABOVE: \$26,854.00

EXCLUSIONS:

SALES TAX, PERMITS, STAKES, GRADING, CLEARING, LOCATING UNDERGROUND UTILITIES, PAINTING, BONDS (WE ARE BONDABLE), CORE DRILLING,
SURVEYING, ELECTRICAL OR CONTROL WIRING, CONDUITS, ELECTRICAL HOOKUPS, GROUNDING OF FENCE OR GATES, MOW STRIPS, EMBEDS,
INSTALLATION OF EMBEDS, BOLLARDS, SIGNS, TRAFFIC CONTROL, GRADE BEAMS, TEMPORARY FENCE, FENCE REMOVAL, INSTALLATION OF SLEEVES, REMOVAL OF DIRT FROM POST HOLE
EXCAVATION (DIRT TO BE SPREAD EVENLY AROUND HOLES) INDEMNIFICATION FOR ACTIONS OF ANY OTHERS BESIDES ANCHOR OR ITS SUBCONTRACTORS

PAYMENT TERMS: NET 30 DAYS W.A.C.

The Anchor Group reserves the right to review any bond form, provided by the General Contractor, before accepting the Sub-Contract Agreement.

| SELL | ER: CHRIS RODRIGUEZ | BUYER accepts this proposal, the Conditions of Proposal, and all its terms as binding contract subject only to approval of credit by SELLER. |
|--------|------------------------|--|
| | THE ANCHOR GROUP, INC. | Company: |
| By: | | By: |
| Title: | | Title: |
| Date: | | Date: |

THE ANCHOR GROUP, INC.

PROPOSAL

ANCHOR FENCE (830) 606-5516 1470 N BUSINESS 35 NEW BRAUNFELS, TX 78130

ANCHOR ACCESS

DATE: 9/23/2025 ATTN: ALEXANDER RAGLAND

BUYER: Bartlett Cocke PROJECT: La Vernia PR28 ADDRESS: LOCATION: La Vernia, TX

PHONE:

FAX: This Proposal is valid only if accepted by execution below by the E-MAIL: Buyer and returned to the Seller on or before_____ 30 Days

CELL: otherwise, this Proposal shall be deemed withdrawn.

Anchor proposes to furnish materials, labor, supervision and equipment to perform the following:

PR 28

| Labor | # of Men | Hours | Manhours | Rate | ! | Total | |
|---------------|----------|-------|----------|------|----------|-------|----------|
| Supervision | 1 | 20 | 20 | \$ | 50.00 | \$ | 1,000.00 |
| Foreman | 1 | 65 | 65 | \$ | 35.00 | \$ | 2,275.00 |
| General Labor | 2 | 65 | 130 | \$ | 30.00 | \$ | 3,900.00 |
| Truck | 1 | 65 | 65 | \$ | 18.00 | \$ | 1,170.00 |
| Rental/Equip | 1 | | 1 | \$ | 1,425.00 | \$ | 1,425.00 |
| Total Labor | | • | • | • | | \$ | 9,770.00 |

| Materials | Quantity | UOM | Unit Cost | Total |
|----------------------|----------|-----|-------------|--------------|
| Chain Link 8' Fabric | 7 | | \$ 306.00 | \$ 2,142.00 |
| PIPE | 1 | | \$ 3,400.00 | \$ 3,400.00 |
| Fittings | 1 | | \$ 1,450.00 | \$ 1,450.00 |
| Misc | 1 | | \$ 1,200.00 | \$ 1,200.00 |
| Gate Hardware | 3 | | \$ 1,450.00 | \$ 4,350.00 |
| Concrete | 5 | | \$ 420.00 | \$ 2,100.00 |
| Total Material | | | | \$ 14,642.00 |

| Total | | \$ 24,412.00 |
|-------------|-----|-----------------|
| OH&P | 10% | \$ 2,441.35 |
| | | \$ - |
| | | |
| Grand Total | | \$ 26,853.35 |

120 bags @ \$7.00

High - \$ 840.00

EXCLUSIONS Sales Tax

bonds or permits. No clearing, grading, staking or surveying of the fence line. G.C. to provide all field engineering.

No delegated-engineering design, structural performance engineering or special warranty.

No removal, grounding, electrical, conduits, grade beams, mow strip, gate track landings or signs unless otherwise noted.

No fixed or removable bollards, Fire Department locks or other hardware on gates.

All post to be removed to be cut off at grade and concrete footings to remain.

General Contractor to remove all trees, brush and other obstacles prior to removal or installation of fence and gates.

Anchor reserves the right to review any bond form, provided by the General Contractor,

before accepting the Sub-Contract Agreement.

If paying with a credit card please add a 3-1/2% convenience fee to total above.

Anchor reserves the right to review any bond form, provided by the General Contractor, before accepting the Sub-Contract Agreement.

| Seller: Chris Rodriguez | BUYER accepts this proposal, the Conditions of Proposal, and all its terms as a binding contract subject only to approval of credit by SELLER. |
|-------------------------|--|
| Γhe Anchor Group, Inc. | Signed By: |
| | Printed Name: |
| By: Chris Rodriguez | Title: |
| <u> </u> | Date: |

THE ANCHOR GROUP, INC.

Anchor Access

1470 N Business IH 35 New Braunfels, TX 78130 (830)606-5516

PROPOSAL

DATE: 9/24/25

BUYER: BARTLETTE COCKE

ADDRESS:

ATTN: ALEXANDER RAGLAND

PROJECT: LA VERNIA ISD PR28 WOOD FENCE

LOCATION : LA VERNIA, TX

This Proposal is valid for 30 days; otherwise, this Proposal shall be deemed withdrawn.

Anchor proposes to furnish materials, labor, supervision and equipment to perform the following:

PR28 WOOD FENCE

DEMO 31 LF OF 8' TALL WOOD PRIVACY FENCE

REMOVE POST & CONCRETE FOOTINGS STAGE MATERIAL ON SITE

30 LF REINSTALL DEMOED WOOD FENCE AT LATER TIME

NEW 4X4 TREATED POST REPLACE PICKETS AS NEEDED REPLACE 2X4 RAILS AS NEEDED

MATERIAL: \$407.00 LABOR: \$4,003.00 OH&P: \$441.00

LUMP SUM: \$4,851.00

EXCLUSIONS:

SALES TAX, PERMITS, STAKES, GRADING, CLEARING, LOCATING UNDERGROUND UTILITIES, PAINTING, BONDS (WE ARE BONDABLE), CORE DRILLING, SURVEYING, ELECTRICAL OR CONTROL WIRING, CONDUITS, ELECTRICAL HOOKUPS, GROUNDING OF FENCE OR GATES, MOW STRIPS, EMBEDS, INSTALLATION OF EMBEDS, BOLLARDS, SIGNS, TRAFFIC CONTROL, GRADE BEAMS, TEMPORARY FENCE, FENCE REMOVAL, INSTALLATION OF SLEEVES, REMOVAL OF DIRT FROM POST HOLE EXCAVATION (DIRT TO BE SPREAD EVENLY AROUND HOLES) INDEMNIFICATION FOR ACTIONS OF ANY OTHERS BESIDES ANCHOR OR ITS SUBCONTRACTORS

The Anchor Group reserves the right to review any bond form, provided by the General Contractor, before accepting the Sub-Contract Agreement.

| SELLER: CHRIS RODRIGUEZ | BUYER accepts this proposal, the Conditions of Proposal, and all its terms as binding contract subject only to approval of credit by SELLER. |
|-------------------------|--|
| THE ANCHOR GROUP, INC. | Company: |
| Ву: | Ву: |
| Title: | Title: |
| Date: | Date: |

THE ANCHOR GROUP, INC.

PROPOSAL

ANCHOR FENCE (830) 606-5516 1470 N BUSINESS 35 NEW BRAUNFELS, TX 78130

ANCHOR ACCESS

DATE: 9/24/2025 ATTN: ALEXANDER RAGLAND

BUYER: Bartlett Cocke PROJECT: La Vernia PR28 ADDRESS: LOCATION: La Vernia, TX

PHONE:

FAX: This Proposal is valid only if accepted by execution below by the E-MAIL: Buyer and returned to the Seller on or before_____ 30 Days

CELL: otherwise, this Proposal shall be deemed withdrawn.

Anchor proposes to furnish materials, labor, supervision and equipment to perform the following:

PR 28 WOOD FENCE

| Labor | # of Men | Hours | Mar | nhours | Rate | | Tota | al |
|------------------|----------|-------------|------|--------|------|----------|------|----------|
| Supervision | | | | | | | \$ | - |
| Foreman | 1 | 31 | | 31 | \$ | 35.00 | \$ | 1,085.00 |
| General Labor | 2 | 31 | | 62 | \$ | 30.00 | \$ | 1,860.00 |
| Truck | 1 | 31 | | 31 | \$ | 18.00 | \$ | 558.00 |
| Mobilizations | 2 | | | | \$ | 250.00 | \$ | 500.00 |
| Total Labor | | | | | | | \$ | 4,003.00 |
| | | | | | | | | |
| Materials | Quantity | UOM | Unit | t Cost | | | Tota | al |
| 4X4 Treated Post | 5 | | \$ | 15.00 | | | \$ | 75.00 |
| Pickets | 1 | | \$ | 22.00 | | | \$ | 22.00 |
| 2x4x8 | 1 | | \$ | 20.00 | | | \$ | 20.00 |
| Stain | 1 | | \$ | 170.00 | | | \$ | 170.00 |
| | | | | | | | \$ | - |
| Concrete | 15 | | \$ | 8.00 | | | \$ | 120.00 |
| Total Material | | | | | | | \$ | 407.00 |
| | | | | | | | | |
| | | Total | | | \$ | 4,410.00 | | |
| | | OH&P | | 10% | \$ | 441.15 | | |
| | | | | | \$ | - | | |
| | | | | | | | | |
| | | Grand Total | | | \$ | 4,851.15 | . • | |

EXCLUSIONS Sales Tax

bonds or permits. No clearing, grading, staking or surveying of the fence line. G.C. to provide all field engineering.

No delegated-engineering design, structural performance engineering or special warranty.

No removal, grounding, electrical, conduits, grade beams, mow strip, gate track landings or signs unless otherwise noted.

No fixed or removable bollards, Fire Department locks or other hardware on gates.

All post to be removed to be cut off at grade and concrete footings to remain.

General Contractor to remove all trees, brush and other obstacles prior to removal or installation of fence and gates.

Anchor reserves the right to review any bond form, provided by the General Contractor,

before accepting the Sub-Contract Agreement.

If paying with a credit card please add a 3-1/2% convenience fee to total above.

Anchor reserves the right to review any bond form, provided by the General Contractor, before accepting the Sub-Contract Agreement.

| 3 | BUYER accepts this proposal, the Conditions of Proposal, and all its terms |
|-------------------------|--|
| Seller: Chris Rodriguez | as a binding contract subject only to approval of credit by SELLER. |
| he Anchor Group, Inc. | Signed By: |
| | Printed Name: |
| By: Chris Rodriguez | Title: |
| | Date: |



Roadway Striping Inc. Serving San Antonio / Austin Cities and Surrounding Areas. Settle for Great Service, Nothing Less. Office: (512) 392-4717

Est. Qty.

180

Company: Attn:

Phone:

Project:

City:

Unit

LS EA

1 F

Location:

Bid Date:

Cell: E-mail:

Proposal Submitted To:

9/23/2025 Taylor Cruz Bids@roadwaystripinginc.com

7/15/2024

Bartlett Cocke General Contractors

PRICES GOOD FOR 30 DAYS FROM BID DATE UNLESS CONTRACTED

1,665.24

ARagland@bartlettcocke.com

LVISD High School PR #28 225 Bluebonnet Rd.

Unit Price

Alexander Ragland

La Vernia, TX 78121

Bid Request

Web Request Call In Request

Total

1,665.24

1,665.24

1.665.24

C.O. Date: RSI Estimator Email:

Description of Job - Tax Exempt Project Install On-Site ADA Signs, Fire Lane Striping, Per Plan Sheets: A01.01 PR #28

> **Description: Markings Proposed on Concrete** Base Bid ADA Signs - Fence Mounted

Fire Lane Painting Power washing is included where paint is to be laid only

POWER WASHING CONDITIONS / EXPLANATION

- Power Washing of Concrete for Paint Adhesion Only Washing area is only where paint is laid.
- RSI is happy to provide 1 year warranty based on our Company performing the power washing.

NOTE If your project needs additional cleaning, feel free to give us a call and we will get you pricing

ABOVE ITEMS ARE ITEMIZED FOR YOUR CONVENIENCE. RSI WILL ONLY BE PROVIDING WHAT IS LISTED. IF SOMETHING IS MISSING PLEASE LET US KNOW.

SUB TOTAL

WARRANTY - TOTAL \$

IF YOU ARE GOING TO COLLECT AND PAY SALES TAX OR THIS PROJECT IS TAX EXEMPT. PLEASE REMOVE SALES TAX AND FORWARD US THE TX SALES AND USE TAX RESALE CERTIFICATE. THANK YOU

INCLUDES: Fire Lane Painting, ADA Signs, Labor.

1 Mobilization(s) per scope of work. Additional Mobilizations are >>

EXCLUDES: Bonds or Permits, Union Agreements, Monument or Electrical Signs, Raised Profile Rumble Strip Thermoplastic, Pipe Bollards unless specified on this proposal, Off-Site Work, Water Reclamation, Traffic Control Items, Guardrail, Barricades, 'Paid if Paid" Clauses, Landscaping, ADA Ramp Staining, Paint, Wheel Stops, Fire Lane Signs, Thermoplastic, Glass Beads, Sandblasting Removals, Power washing, Regulatory Signs,

Raised Pavement Markers, Sealcoat, Hot Crack Fill, Cold Crack Fill, Bike Racks, Etc...

PARKING LOT NEEDS TO BE CLEANED, CLEAR AND DRY.

WEEKEND AND AFTER HOURS WORK SUBJECT TO ADDITIONAL OVER TIME CHARGES.

Please allow 10 work day lead time prior to our mobilization

Power Washing of Concrete for Paint Adhesion* Work to be preformed prior to striping mobilization.

Preparation for paint application via Power washing as Required by the Paint Manufacturer for 1 Year Warranty. We must be the ones to provide this service if you wish to obtain a written warranty from us.

Hours are estimated Port to Port. The Additional Hourly Charge Rate is applied if delay occurs due to general contractor not having the surfaces cleared of equipment and materials as well as

yeneral contraction for the surfaces calend or equipment and internals as went as not having the surfaces properly swept before our arrival. This proposal for power washing includes cleaning of surface Areas to be painted only, so if you need us to come in and clean the rest of the parking lot, as well as providing heavy cleaning and sweeping of the parking lot, we can provide pricing. Water to be provided on-site. Power washing does not remove oil out of concrete.

On The Job allotted Hours Additional Hourly Charge Rate Please Note there will be a 3% credit card fee if paid with Credit Card.

248.00

EA \$

1,000.00

PLEASE READ ALL CONDITIONS BELOW IN CONSIDERATION OF DRAFTING CONTRACTS. SUBCONTRACTS OR ACCEPTANCE OF THIS PROPOSAL. THIS PROPOSAL SHALL BECOME APART OF ANY CONTRACT OR UNLESS ALL LISTED CONDITIONS ARE EXHIBITED AND AGREED UPON. YOU MAY ALSO SIGN THIS AS OUR CONTRACT PRIOR TO SCHEDULING WORK.

PARKING LOT NEEDS TO BE CLEANED, CLEAR AND DRY

Warranties: Projects following the following criteria are Warrantable for 1 Year:

- All Concrete Surfaces must have a cure time of 30 days or more.
 Asphalt Surfaces need to be 14 Days Cure time
- 3. We must have 24 hours dry time after rain and 4 hours prior to rain.
 4. New Concrete surfaces must be power washed to insure that all curing
- compounds and dust are totally removed. We must be the ones to provide this service if you wish to obtain a written warranty from us. Please let us know if you need pricing from us.
- 5. Our striping work is a perishable product when subjected to heavy construction work, equipment, Landscaping dirt and abuse. For these reasons we cannot provide written warranty if heavy equipment and landscaping services are provided after we are completed with our work.

To avoid these issues it is recommended that we are the last team in to help you have a turn key result for your customer.

6. We can only warranty our product for one (1) year from the date it was installed.

RSI IS A NON-UNION COMPANY INSURANCE COVERAGE INCLUDED

| GENERAL AGGREGATE | \$2,000,000.00 |
|--------------------------|----------------|
| PRODUCTS-COMP/OP AGG | \$2,000,000.00 |
| PERSONAL & ADV INJURY | \$1,000,000.00 |
| EACH OCCURRENCE | \$1,000,000.00 |
| DAMAGE TO RENTED PREM. | \$100,000.00 |
| MED EXP (any one person) | Excl |
| UMBRELLA LIAB / EA. OCC. | \$3,000,000.00 |
| UMBRELLA AGGREGATE | \$3,000,000.00 |

Excessive Umbrella Policies, Waivers of Subrogation are subject to additional Fees.

A BINDING PART OF ANY CONTRACT OR SUBCONTRACT.

Contract Conditions and Qualifications

- RSI will not preform work until either a signed proposal or executed contract is received.
- If sales tax does not apply, please remit a tax exempt/resale certificate.
- Additional charges will be incurred to add additional Insureds and/or a Waiver of Subrogation. You MUST notify us in advance if this is your company's requirement.
- Roadway Striping, Inc. will not be responsible for damage to unmarked utilities or irrigation.
 Roadway Striping, Inc. does not warranty against vegetation growth coming through any type of surface worked

- Payment is due upon receipt of the invoice, or as otherwise indicated on contract.
- 7. A Notice of Intent will be mailed if payment not made within 30 days. Liens will be placed if payment is not
- 8. Roadway Striping, Inc. will not be responsible for base failure unless stated otherwise.
- All areas under construction will be barricaded.
 Any damages caused by others crossing barricades will not be the responsibility of Roadway Striping, Inc.
- 11. Roadway Striping Inc. is not responsible for the cost of any additional items not listed to be provided in this proposal. This proposal is our "Scope of Work" and any changes in the project cannot be
- assumed to be in our scope of work if we didn't list the change items in our proposal.

 12. All additional work will be charged accordingly. However, no additional work will be completed without a
- signed change order.
- 13. Based on the fluidity of fuel & Product costs, the pricing on this proposal is good for 30 days from the date of Proposal for Proposed Work.
- 14. General Contractor Contracts "Paid when Paid Clause". Please be aware that Roadway Striping Inc., If deciding to Sign this agreement, will exercise all Preliminary Lien Notices and of Placing Liens on property
- as stated in the Texas Lien Rights Laws and filing times.
- 15. In all subcontracts please provide all owner information Bond Information, Phone #, Address, & Name of contact in charge of contract payment and administrations.
- 16. Roadway Striping Inc. owners or representatives shall not and cannot sign sub-contractor language referring to "Paid If Paid" Clauses. Please strike these references from contracts.
- 17. Move-ins are figured to be done with no conflictions with Contractor or Subcontractors.
- Move-in Fees will be assessed if our scope of work for the day (as planned with General Contractor) is obstructed, un-prepared, or inaccessible due to other contractors
- 18. Roadway Striping Inc. is not obligated to provide a indefinite amount of move-ins.
- Upon proposal acceptance, number of move-ins shall be stated and recognized by the General Contractor.

 19. Customer is responsible for all legal/collection fees. R.S.I Shall not be held Liable for any Item of work not specifically described in above descriptions or clauses or for any other work performed by other trades or contractors
- 20. We will not sign contracts stating LD Charges. Also Testing requirements, Safety classes or special endorsements of any kind maybe subject to the cost of those charges charged to the contractor or customer.

 21. We acknowledge addendas/RFI's at the best of our ability. We will NOT be responsible for any work other than
- what is shown in the above proposal.

 22. Customer subject to a 10% cancellation fee if signed proposal or contract is cancelled.

SEAL COATING PROCESS & WARRANTIES:

Seal coat products have changed over the years for environmental reasons.

Coal tar use to be the base component of parking lot sealant. As of 2018 both San Antonio and

Austin Metropolitan areas have out lawed the use of Coal Tar products.
Currently we are using an asphalt emulsion product from Seal Master Co

Due to the different natures of these products the asphalt emulsion takes and additional 24-48 hours of cure time to harden then does coal tar sealants.

For this reason when asphalt surfaces are subject to traffic prior to the proper cure they will experience quicker wear rates.

Asphalt condition is also a factor. The rougher the asphalt the quicker top wear and rock

exposure occurs. This is a normal process, just opening the asphalt to traffic early will

WARRANTY: Our warranty covers pealing issues in the valleys between the rocks in the asphalt. This is caused from inadequate cleaning and we will take care of this Issue. RSI will only provide Warranty Letters if all applicable instalment agreements are meet. Warranty Letters will only be issued with RSI's letterhead pertaining to our scope of work.

30 Day Accounts that are late are subject

to interest fee of 1.5% per month COD Accts not paid at time of delivery will be charged 3% plus an interest fee of 1.5% per month

Authorized Signature

Project: LVISD High School PR #28

| Check Box | | | | | |
|------------------|---|----|----------|--|--|
| \$ | - | \$ | | | |
| WARRANTY - TOTAL | | \$ | 1,665.24 | | |
| | | | | | |

Authorized Signature MATTHEW HATHAWAY

| AUTO LIAB: Single limit: | \$1,000,000.00 |
|--------------------------------|----------------------------------|
| EACH OCCURRENCE: AGGREGATE: | \$1,000,000.00 \$1,000.000.00 |
| WORKERS COMP: | \$1,000,000.00 |
| E.L. Each Accident: | \$1,000,000.00 |
| E.L. Disease-E. Emp. | \$1,000,000.00 \$1,000,000.00 |
| E.L. Disease- Plcy Lmt | \$1,000,000.00 |

The Roadway Striping Inc. Difference

We believe that quality is the highest priority, and when its done right, money is saved.




From our own observations, our standard is higher than any other striping company. Our training has to be done in-house, because when we hire other "experienced" stripers, their standards are ALWAYS lower than our standard.

This is why we are rarely the cheapest bid, but ALWAYS the bid providing the highest value.

It will take us longer to complete the project the right way, but we will utilize technology, management, and extra manpower to complete the project on time.

The key to saving money on projects is our project management.

We know that our customers have extraordinary deadlines and challenges to meet. This is why we assert our processess in when its our time on the project. Our team will work with your superintendents and other subcontractors to move mountains when you need critical services completed fast.





In the specialties industry, the cheap bidders will ALWAYS fail to deliver.



Unacceptable

Details are extremely important in the striping industry. Most people don't care about what the parking lot looks like, so most striping companies stop caring about quality and focus on volume.

WE CARE.

Our obsession over making the highest quality striping product means we get less volume, but our customers are always given a striping product thats easy to sell.

Our bid to you is an offer to make your project look nothing short than the highest quality road or parking lot that money can build.

Our extreme dedication to our quality is what makes us different than our competition. We strive to achieve higher and higher standards with each project we build.

Let us help you give your customer the project that will look good and last years beyond project completion.



Thank you for the Bidding Opportunity!!!

Any future bid invites should go to bids@roadwaystripinginc.com for the quickest service.



If you have any questions about this proposal or would like revisions, do not hesitate to contact us. We believe that our quality process starts at the bidding process, and we aim to meet every expectation.

Call us at 512-392-4717 to discuss any questions about this project.

JSR Incorporated

Planning & Construction

Change in Work - Cost Analysis Form

| Cont | ect No. & Na ractor Name ription of Cl | »: | Bartlett Cocke PR# 028 HS Front Sidewalk Additi | v 1,4 ivery | 31.36 and I | lbs \$ Pickup | 20') - \$ 4 3.50/lb - 5 - \$ 450. 5 - \$ 9,70 7 | \$5,595.0 00 | 9/25/2025 | | |
|------|--|---------------------------|---|----------------|----------------|------------------|---|-----------------|-------------------------|-----|----------|
| | Item | | Description | Q | uantity | Unit | Unit Cost | Labor | Material & Equipment | Sub | contract |
| | | Add | | | | | | | V | | |
| | Material | 1 1/2" (| DD 3 Line Galvanized Hand Rail | ~ | 192 | LF | \$ 85.35 | | \$ 16,387.20 | \$ | - |
| F | ield Labor | Core Dri | Ill In Place and Secure With Non-Shrink Grout | / | 144 | HRS | \$ 47.00 | \$ 6,768.00 | ⁄\$ | \$ | - |
| 0 | ffice Labor | PM Tim | e and Detailing Time | Y | 56 | HRS | \$ 6 0.00 | \$ (3,360.00) | / | | |
| | Tools | JSR Trı | ack and Equipment | | 9.0 | Dy | \$ 165.00 | | \$ 1,485.00 | \$ | - |
| Fie | eld Material | Non-Sh | rink Grout (Rockite) | ~ | 5.0 | EA | \$ 84.35 | | \$ \(\square 421.75 \) | \$ | - |
| | | | | | | | | | \$ - | \$ | - |
| | | | | | | | | \$ - | \$ - | \$ | - |
| | Note | 1 1/2" | is nominal OD. Rails are 1 1/4" Sch 40 | | | | | \$ - | \$ - | \$ | - |
| | | | | | | | | \$ | \$ - | \$ | - |
| | \$ 28.00 \$ 6.80 40% lb \$ 48.72 | 0 / hr fring 2 / hr | es | | the v This | work pric | eedback ing app | how lo | be hig | | to do |
| | | | | | | | | \$ - | \$ - | \$ | _ |
| | installers make around \$ 28.00 - | | | | | | \$ - | \$ - | \$ | | |
| | \$35.00. | | | | | | \$ - | \$ - | \$ | - | |
| | | | | | | | \$ - | \$ - | \$ | - | |
| | \$ 34 with 40% LB = \$ 47.60 | | 0% LB = \$ 47.60 | | | | | \$ - | \$ - | \$ | - |
| | , | | | | | | | \$ - | \$ - | \$ | - |
| | | | | | | | | \$ - | \$ - | \$ | |
| | | | | • | | | SUBTOTAL | \$ 10,128.00 | \$ 18,293.95 | \$ | - |

| | SUBTOTAL | \$ 28,421.95 |
|---------------------|--------------------------------|-----------------|
| Overhead and Profit | 10.0% | \$ 2,842.05 |
| | TOTAL FOR THIS CHANGE PROPOSAL | \$ 31,264.00 |

The oth



The Davey Tree Expert Company ("Company") 18838 FM 2252 Suite 500 San Antonio, TX 78266-3010

Phone: (210) 981-2870 Fax: (210) 981-2871

Email: Jacob.Young2@davey.com





Client Service Location 9/30/2025 BARTLETT COCKE GENERAL CONTRACTOR Sernia ISD Proposal #: 20064739-1758816582 ATTN JOSH RIVERA Attn: Alexander Ragland Account #: 6186844 8706 LOCKWAY ST 225 Bluebonnet Rd Home: (210) 655-1031 SAN ANTONIO. TX 78217-4837 La Vernia, TX 78121-4793 Work: (830) 421-1193 Home: (210) 655-1031

> Work: (830) 421-1193 Mobile: (210) 638-9912

Email: aragland@bartlettcocke.com

Mobile: (210) 638-9912

Email: aragland@bartlettcocke.com

| Tree Care | Service Period | Price* | Tax | Total |
|----------------|----------------|------------|----------|------------|
| ☐ Tree Pruning | | \$1,815.00 | \$131.59 | \$1,946.59 |

Jake will start the crew.

Red oak and live oak between the main high school and the building with the parking canopy.

Red oak: Uplift 6'-7' (closer to 7') over the yard to make way for a new sidewalk that will go around the tree. Thin the interior by removing rubbing/crossing limbs and removing dense areas of small deadwood.

Live oak: Uplift 14'-16' over the roadway and 4'-6' over the roof. Remove deadwood 2" in diameter and larger. Thin the interior by removing rubbing/crossing branches and thinning sapling growth.

Sanitize pruning and cutting tools before work begins. Cuts made on living oak tissues 1/2" inch and larger will be painted to prevent Oak Wilt. Clean well and remove debris. All cuts will be made by ANSI-A300 pruning standards for overall tree health and future viable growth.

Tree Protection Fence Install

\$1.300.00

\$94.25

\$1.394.25

Red oak and live oak between the main high school and the building with the parking canopy: Install fencing under the drip line of both trees to protect the critical root zone from any construction damage.

| Fertilization/SoliCare | Service Period | Price* | ıax | iotai |
|---------------------------|----------------|----------|---------|----------|
| Liquid Humate Application | | \$600.00 | \$43.50 | \$643.50 |

Camilaa Daviad

Recommended to be done after construction.

Red oak and live oak between the main high school and the building with the parking canopy: Soil injection application of PolyPhosphite 30 and liquid natural organic compounds to help with heat/winter stress and stimulate the plant's defenses, promote tree health by supplying necessary nutrients, and improve both soil biology and structure.

☐ Deep Root Fertilize w/ Arbor Green PRO

\$600.00

\$43.50

\$643.50

Recommended to be done before construction.

Red oak and live oak between the main high school and the building with the parking canopy. Deep root fertilization with Davey Arbor Green Pro soil injections provides adequate nutrients and promotes healthy canopy growth. By injecting the trees with Arbor Green Pro we can provide needed nutrients for increased resistance to insects and diseases while promoting overall appearance and health. This application lasts one full year. This service is the single most important thing you can do for the long-term health of your trees.

Total of All Services

\$4,315.00

\$312.84

\$4,627.84

YES, please schedule the Services marked above.

No Exception Taken

Catherine Blackler - AGCM Man Man

* Sales tax will be added per local jurisdiction unless a tax exempt form is on file.

Other Important Terms: See the attached "Terms and Conditions" either set forth on the reverse side of this Agreement or attached to this Agreement for additional information, such as early termination, maintenance responsibilities, warranties, late and default charges and insurance.

Printed: 9/30/2025 Page 1 of 2



CI IENT.

The Davey Tree Expert Company ("Company") 18838 FM 2252 Suite 500 San Antonio, TX 78266-3010

Phone: (210) 981-2870 Fax: (210) 981-2871

Email: Jacob.Young2@davey.com





| Client | Service Location | 9/30/2025 |
|------------------------------|-----------------------------------|-----------------------------------|
| BARTLETT COCKE GENERAL CONTI | RACTD®Sernia ISD | Proposal #: 20064739-1758816582 |
| ATTN JOSH RIVERA | Attn: Alexander Ragland | Account #: 6186844 |
| 8706 LOCKWAY ST | 225 Bluebonnet Rd | Home: (210) 655-1031 |
| SAN ANTONIO, TX 78217-4837 | La Vernia, TX 78121-4793 | Work: (830) 421-1193 |
| | Home: (210) 655-1031 | Mobile: (210) 638-9912 |
| | Work: (830) 421-1193 | Email: aragland@bartlettcocke.com |
| | Mobile: (210) 638-9912 | |
| | Email: aragland@bartlettcocke.com | |

ACCEPTANCE OF PROPOSAL: By signing below, Client agrees and accepts the terms and conditions stated above and the Terms and Conditions either set forth on the reverse side of this Agreement or attached to this Agreement. Company is authorized to do this work as specified. All deletions have been noted. I understand that once accepted, this Agreement constitutes a binding contract. If Client is a legal entity, the undersigned hereby represents that the undersigned has full authority to enter into this Agreement on behalf of Client. This proposal may be withdrawn if not accepted within 30 days.

YOU ARE ENTITLED TO A COMPLETELY FILLED IN COPY OF THIS AGREEMENT, SIGNED BY BOTH YOU AND US, BEFORE ANY WORK MAY BE STARTED

DOOR-TO-DOOR SALE/ HOME SOLICITATION: If this Agreement is the result of a Door-to-Door or Home Solicitation Sale (under applicable state or federal law), the following provision applies:

You, the buyer, may cancel this transaction at any time prior to midnight of the third business day after the date of this transaction. See the attached notice of cancellation form for an explanation of this right. If you cancel this agreement, the seller may not keep all or part of any cash down payment.

| | CLIENT. | COMPANI. | | | |
|---------------|---------|---------------|--------------------------|--|--|
| Signature: | | Signature: | Jacob Young | | |
| Name (print): | | Name (print): | Jacob Young ^O | | |
| Title: | | Title: | Sales Arborist | | |
| Date: | | Date: | 9/30/2025 | | |
| | | | · | | |

CLIENT CARE GUARANTEE:

COMPANY.

We guarantee to deliver what we contract to deliver. If we fail to deliver, we will work with you until you are satisfied, or we will not charge you for the disputed service.

Printed: 9/30/2025 Page 2 of 2

TERMS AND CONDITIONS

- 1. Exclusive Terms. Client and Company agree that these Terms and Conditions are the sole and exclusive terms and conditions of this Services Agreement (this "Agreement"). Any additional or different terms or conditions not contained herein, including, without limitation, any request or communication by Client regarding the Services, are hereby rejected by the parties, unless agreed to in writing, identified as an amendment to this Agreement, and signed by both parties.
- 2. <u>Client</u>. If Client is a legal entity, the term Client shall include all parent, subsidiary, related, and affiliated entities and each of their respective officers, directors, members, owners, employees, agents, representatives, contractors, and insurers.
- 3. <u>Limited Scope of Services</u>. Company agrees to perform only the services (the "Services") expressly listed on the first page of this Agreement. Client understands and agrees that Company is not required to perform any services other than the Services. Notwithstanding the foregoing, if Company provides additional or different services with Client's written approval, additional fees, costs, and charges will apply, and Client agrees to pay such additional fees, costs, and charges.
- 4. <u>Jobsite</u>. Client represents and warrants that Client has, and at all times will have, authority to grant access, and does hereby authorize and grant access, to Company to enter the property or properties where the Services are performed ("Job Site"), including all streets, sidewalks, and all surrounding property or areas necessary to gain access to or remove material from the Job Site. Client understands and agrees that Company has relied upon this representation and warranty to perform the Services. Client further represents and warrants that the Job Site is not in violation of any applicable codes, ordinances, statutes, or other governmental regulations. While Company may assist, Client is responsible for obtaining any necessary permits in connection with the Services, unless otherwise agreed in writing. Unless otherwise agreed to in writing, Company has made no survey of the property.
- 5. <u>Payment</u>. Company will provide one or more invoices for the Services provided to Client, and in consideration of Client receiving the Services, Client shall pay the fees set forth on each invoice in full within thirty (30) days of the invoice date. If Company initiates litigation or other collection action against Client to recover any amount, Client agrees, to the extent permitted by applicable law, to pay all litigation or collection costs and expenses, including reasonable attorney's fees and expert witness fees, incurred by Company in connection with such litigation or collection action.
- 6. <u>Limited Warranty</u>. Company agrees to perform all Services in accordance with applicable federal, state and local laws and industry standards, and it shall exercise due care and act in good faith at all times in the performance of its obligations under this Agreement. Company will repair, at its own expense, any material defects with its Services for a period of six months following completion of the applicable Services.
- 7. Working with Living Things. As trees and other plant life are living, changing organisms affected by factors beyond Company's control, no guarantee on tree, plant, or general landscape safety, risk, health, or condition is expressed or implied and is disclaimed in this Agreement, unless that guarantee is specifically stated in writing by Company. Arborists cannot detect or anticipate every condition or event that could possibly lead to the structural failure of a tree or guarantee that a tree will be healthy or safe under any circumstances. There are many unseen and unforeseen items and hazards that may or may not exist now, or in the future, over which Company has no control. Site inspections do not include internal or structural considerations unless so noted. Unless otherwise specified, this is not a Tree Risk Assessment and will not include investigations to determine a tree's structural integrity or stability. Company may recommend a Tree Risk Assessment be conducted for an additional charge. All trees present some degree of risk and will eventually fail. The only way to eliminate tree risk is to remove trees. By choosing to preserve trees, Client hereby accepts this risk. Client also accepts the risk of, and Company

- will not be liable for, any accident, damage, or injury occurring prior to the scheduled Services.
- 8. <u>Product Usage</u>. To the extent the Services include application of product on the Jobsite, Company is relying on the applicable manufacturer's representations regarding the product used and makes no independent representations regarding the product, including, without limitation, safety or efficacy.
- 9. Indemnification by Client. To the fullest extent permitted by applicable law, Client shall indemnify, defend, and hold harmless Company from and against all claims, damages, losses, and expenses, including reasonable attorney's fees, arising out of, resulting from, or relating to (a) Client's negligence or willful misconduct in connection with this Agreement, (b) any breach by Client of this Agreement, (c) the condition of the Job Site or any hazards on the Job Site existing prior to the execution of this Agreement or caused by Client or a third party, (d) Client's grant of access to the Job Site or surrounding areas, and (e) any acts or omissions by a third-party, Client, or any of Client's employees, agents, contractors (other than Company), or representatives.
- 10. <u>Indemnification by Company</u>. To the fullest extent permitted by applicable law, Company shall indemnify, defend, and hold harmless Client from and against all claims, damages, losses, and expenses, including reasonable attorney's fees, to the extent caused by the negligence or willful misconduct of Company or its employees or agents in connection with this Agreement. Company's indemnification, defense and hold harmless obligations shall survive the expiration or earlier termination of this Agreement for a period of one year.
- 11. <u>LIMITATION OF LIABILITY</u>. CLIENT AGREES THAT COMPANY SHALL NOT BE LIABLE TO CLIENT FOR ANY SPECIAL, INDIRECT, INCIDENTAL, OR CONSEQUENTIAL LOSSES, DAMAGES, OR EXPENSES OF ANY KIND, INCLUDING, BUT NOT LIMITED TO, ANY BUSINESS INTERRUPTION LOSSES OR LOST REVENUE, ARISING DIRECTLY OR INDIRECTLY OUT OF, RESULTING FROM, RELATING TO, OR IN CONNECTION WITH THIS AGREEMENT OR THE SERVICES.
- 12. DAMAGE AND LIABILITY RELEASE. UNLESS CAUSED BYCOMPANY'S NEGLIGENCE, **CLIENT HEREBY** RELEASES COMPANY FROM ANY AND ALL CLAIMS AND DAMAGES AS A RESULT OF OR IN ANY WAY RELATING TO THE SERVICES PROVIDED BY COMPANY AT OR NEAR THE JOB SITE (INCLUDING, BUT NOT LIMITED TO, ABOVE-GROUND ITEMS SUCH AS SIDEWALKS, BUILDINGS, STRUCTURES, DOG FENCES, DRIVEWAYS, LAWNS, OR LANDSCAPING AND UNDERGROUND ITEMS SUCH AS ELECTRICAL LINES, SEPTIC SYSTEMS, LEACH FIELDS, SEWER SYSTEMS, WELLS, IRRIGATION SYSTEMS, OR WATER LINES).
- 13. **Term and Termination**. The term of this Agreement commences on the date of this Agreement and continues until the Services are completed, unless and until earlier terminated as provided under this Agreement (the "Term"). Either party may terminate this Agreement at any time upon at least ten (10) day's written notice, provided Client shall pay Company for any Services performed prior to the termination date.
- 14. **Assignment**. Client may not assign any of its rights under this Agreement without the prior written consent of Company. This Agreement does not confer upon any third-party any right to claim damages against Company.
- 15. <u>Severability</u>. If any term of this Agreement is held invalid, illegal, or unenforceable, such term shall be limited to the extent necessary to comply with applicable law and if such limitation is not possible, severed and inoperative, and the remainder of this Agreement shall remain operative and binding on the parties.

NOTICE OF CANCELLATION

| Date of Transaction |
|---|
| You may CANCEL this transaction, without any Penalty or Obligation, within THREE BUSINESS DAYS from the above date. |
| If you cancel, any property traded in, any payments made by you under the contract or sale, and any negotiable instrument executed by you will be returned within TEN BUSINESS DAYS following receipt by the seller of your cancellation notice, and any security interest arising out of the transaction will be cancelled. |
| If you cancel, you must make available to the seller at your residence, in substantially as good condition as when received, any goods delivered to you under this contract or sale, or you may, if you wish, comply with the instructions of the seller regarding the return shipment of the goods at the seller's expense and risk. |
| If you do make the goods available to the seller and the seller does not pick them up within 20 days of the date of your Notice of Cancellation, you may retain or dispose of the goods without any further obligation. If you fail to make the goods available to the seller, or if you agree to return the goods to the seller and fail to do so, then you remain liable for performance of all obligations under the contract. |
| To cancel this transaction, mail or deliver a signed and dated copy of this Cancellation Notice or any other written notice, or send a telegram, to The Davey Tree Expert Company, at 18838 FM 2252 Suite 500, San Antonio, TX 78266-3010 NOT LATER THAN MIDNIGHT OF |
| Date |
| I HEREBY CANCEL THIS TRANSACTION |
| Date |
| Buyer's Signature |
| Printed Name |
| 20064739-1758816582 |
| Proposal Number |



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 08/29/2025

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on

| _ | s certificate does not confer rights | to th | e cerl | tificate holder in lieu of | Such e | ndorsement(| | one & Tachnology | | <u> </u> |
|--|--|--------------|--------------|--|---|---|----------------------------|---|---------------|---|
| PROD | MARSH USA LLC. | | | į | CONTACT Marsh (U.S. Operations & Technology IPRIMANE: (869)(-35,40) (A/C. No. 1 | | | | | |
| | 200 Public Square, Suite 3760 Cleveland, OH 44114-1824 | | | | [AIC, No. Ext]) (dob)c=100의 (AVC, No.] E-MAIE ADBRESS: Clevela@eriRequest@marsh.com | | | | | |
| | Cievelano, On 44114-1624 | | | | ADDRES | | | | | NAIC 8 |
| | | | | | | | | DING COVERAGE | | 24147 |
| | | | | COLE | 348 U | RER AGM Republ | c slora cenCo∺ | ipany | | 24 147 |
| NSUR | ED The Davey Tree Expert Company | | | | INSURE | R B: | | | | |
| include all affiliates | | | INSURE | RC: | | | | | | |
| | 1500 N. Mantua Street | | | | INSURE | RD: | | | | |
| | Kent, OH 44240 | | | | INSURE | RE: | | | | |
| | | | | | INSURE | RF · | ••••• | | | |
| COV | ERAGES CER | TIFIC | ATE | NUMBER: | CL | E-005564473-43 | | REMON NUMBER: 30 | | |
| INE | S IS TO CERTIFY THAT THE POLICIE DICATED. NOTWITHSTANDING ANY F RTIFICATE MAY BE ISSUED OR MAY CLUSIONS AND CONDITIONS OF SUCI | REQUI | REME TAIN | NT, TERM OR CONDITION THE INSURANCE AFFOR | DED B | Y THE POLICI REDUCED B | ES DESCRIB Y PAID CLAIM | ED HEREIN IS SUBJECT | | |
| SR TR | TYPE OF INSURANCE | | SUBR | POLICY NUMBER | | POLICY EFF (MMUDB/YYYY) | POLICY EXP | LIMITS | | |
| A | X COMMERCIAL GENERAL LIABILITY | 11556 | ZEX1 | MWZY 314042 25 | | 09/01/2025 | 09/01/2026 | | \$ | 5,000,000 |
| - | The second second | | | | ·. · | | | DAMAGE TO RENTED PREABSES (Ea occure | \$ | 5,000,000 |
| - | CLAIMS-MADE X OCCUR | 1 | 1 | | ** | | | MED EXPly one person) | ···\$ | 25,000 |
| - | - Company of the comp | 4 1. | [| | | | | PERSONAL & ADV INJURY | . <u> </u> | 5,000, 000 |
| - | | 1 1 | ļ | | ٠ | | | GENERAL AGGREGATE | \$ \$ | 5,000.000 |
| | GENT AGGREGATE LIMIT APPLIES PER: | 1 | | | | | | PRODUCTS - COMP/OP AGO | | 5,000,000 |
| - | X POLICY PRO- | | 3 | | | | | PRODUCTS - COMPTOR AGE | \$ \$ | |
| | OTHER: | | | Martnessee | ,,,,,,,,,,,,, | 09,01,202 5 | 09/01/2026 | COMBINED SINGLE LIMIT (5s accident) | | 5,000,000 |
| A J | AUTOMOBILE LIABILITY | 1 : | | MWTB14041 26 | • | 50000 | 03/01/2020 | | , <u>{</u> | 2,000,000 |
| 1 | X ANY AUTO OWNED SCHEDULED | 1 | 1. | | | | | BODILY INJURY (Per accider | | |
| · Į | AUTOS ONLY AUTOS | - | | | | | | PROPERTY DAMAGE | \$ | |
| | X AUTOS ONLY X NON-OWNED AUTOS ONLY | j | | | | | | (Per accident) | <u> </u> | |
| 1 | | ļ | | ··········· | | | ······ | | | |
| | UMBRELLA LIAB OCCUR | | | | | | | | <u>\$</u> | |
| 1 | EXCESS LIAB CLAIMS-M.D. | | | | | | | AGGREGATE | 5 | |
| ľ | DED RETENTIONS | 7 | | | | <u></u> | | | \$ | |
| A | WORKERS COMPENSATION | 1 | | MWC 34040 25 (AOS) | | 09/01/2025 | 09/01/2026 | PER OTH SYATUTE ER | | |
| | AND EMPLOYERS LIABILTY ANYPROPRIETOR PARTNER E XECUTIVE | ٦ | | | | | | E.L. EACH ACCIDENT | \$ | 5,000,000 |
| 3 | ANYPROPRIETOR PARTNER LECUTIVE N COPPICER MEMBER EXCLUDED ? (Mandatory in NH) | N/A | | | | | | E.L. DISEASE - EA EMPIGOY | \$ | 5,000,000 |
| | il yes, describe under DESCRIPTION OF OPERATIONS selow | | | | | | | E.L. DISEASE - POLICY LIMI | E | 5,020,000 |
| ······ | Excess Workers Compensation | | | MWXS 314043 25 (NC, OH, F | A. WA) | 09/01/2025 | 09/01/2026 | Workers Compensation | | Statulo |
| Α | • | | | MWXS 316391 25 (CA) | | 09/01/2025 | 09/01/2026 | Employer's Liability | | 1,000,00 |
| Α | 'SIR: \$5,000,000 | | | WWW. 3 10391 23 (OA) | | 09/01/2020 | . 00.0 | | | |
| Evide | RIPTION OF OPERATIONS / LOCATIONS / VEH ence of Insurance. y Injury is included in the Combined Single Limit f | | | | | | iore space is rec | guired) | | 100000000000000000000000000000000000000 |
| CEF | RTIFICATE HOLDER | | | | CA | NCELLATIO | N. | | | |
| The Davey-Tree Expert Company 1500 N. Mantua Street Kent, OH 44240 | | | - | HE EXPIRATI | ON DATE | E DESCRIBED POLICIES BE THEREOF, NOTICE WILL LICY PROVISIONS. | CANO BE | ELLED BEFORE DELIVERED IN | | |
| i | | | | | AUT | HORIZED REPRE | SENTATIVE | | | |
| | | | | | | | | Marsh USA | 1 1 | 40 |
| | | | | | | | | ACORD CORPORATION | | |

AGENCY CUSTOMER ID: CN101565730

LOC #: Cleveland



PEMARKS SCHEDULE

Page 2 of 2

| ACORD AUDITION | WE KEIAIN | ARNO SCHEDULE | |
|--|----------------------|--|--|
| AGENCY MARSH USA LLC. | | NAMED INSURED The Davey Tree Expert Company include all affiliates | |
| POLICY NUMBER | : | 1500 N. Mantua Street Kent, OH 44240 | |
| CARRIER | NAIC CODE | EFFECTIVE DATE: | |
| ADDITIONAL REMARKS | | | |
| THIS ADDITIONAL REMARKS FORM IS A SCHEDULE TO A | ACORD FORM, | | |
| FORM NUMBER: 25 FORM TITLE: Certificate of | f Liability Insur | ance | |
| FORM NUMBER, | | | |
| Workers Compensation does not apply in MN. Coverage is obtained from Workers Employers Liability is covered by policy number MWC 314040 25. | Compensation reinsur | ance association (W.C.R.A.) as required by the state. Minnesota | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |



PLANT HEALTH CARE TIPS

THESE ARE DESCRIPTIONS FROM THE

AMERICAN NATIONAL STANDARDS

INSTITUTE FOR TREE CARE

OPERATIONS.



CLEANING DEAD AND BROKEN BRANCHES CAN HELP THE HEALTH OF A TREE.



USING A POLE PRUNER TO REACH HIGH SPOTS WITHOUT THE USE OF CLIMBING GEAR

This information is being provided to help you understand what type of pruning will be performed on your property. Please refer to the specifications on your proposal for what has been specifically recommended for your property.

PRUNING OBJECTIVES


Pruning objectives shall be established prior to the beginning of any pruning operation.

SPECIES AND LOCATION


The species and location of the trees to be pruned shall be identified. This may be provided as a written description or as a map.

BRANCH SIZE

A minimum or maximum diameter of branches to be pruned off shall be specified to establish the extent of the pruning.



A THINNING / COLLAR CUT



EXAMPLE OF A REDUCTION CUT

Most Common Pruning Types

Cleaning: Selective pruning to remove one or more of the following parts: Dead, diseased, and/or broken branches.

Thinning: Selective pruning to reduce the density of live branches.

Raising: Selective pruning to provide vertical clearance.

Reduction: Selective pruning to decrease height and/or spread.

Restoration: Selective pruning to improve the structure, form, and appearance of trees that have been improperly pruned, vandalized, or damaged.

Visit www.davey.com/pruning to learn more.

BARTLETT COCKE PROPOSAL GENERAL CONTRACTORS







IN PURSUIT OF 100% SUBSURFACE DAMAGE PREVENTION













GPRS Intelligently Visualizes The Built World® above and below ground for customers who need accurate, efficient damage prevention, existing condition as-built documentation, or project & facility management tools. Our elite nationwide team of Project Managers are experts in locating buried infrastructure, reality capture, and mapping – delivered via SiteMap®, our digital visualization software platform, with a 99.8% accuracy rate in utility locating and concrete imaging – thanks to our industry-leading Subsurface Investigation Methodology (SIM).

VISUALIZING

//// THE BUILT WORLD



GPRSING COM /////

September 24, 2025 Submitted By:

Client: BARTLETT COCKE GENERAL CONTRACTORS - SAN ANTONIO TX

Kobi Kirkland

Project Address: 225 Bluebonnet Road La Vernia, TX 78121

To schedule, please email:

Quote Number: GPRSQUOTE-232568 texasinfo@gprsinc.com

GPRS Opportunity Name/Number: 225 Bluebonnet Rd - Utility locating

GPRS appreciates the opportunity to provide this proposal. We encourage you to visit our website (www.gprsinc.com) and contact any of the numerous references listed. Our insurance certificate and W-9 can also be downloaded here. Please feel free to contact us if you have any questions or need additional information. Visit for an overview of our industry-leading best practices.

SCOPE OF WORK

Underground Utility: We understand the scope of work on this project is to search for underground utilities in the areas defined by the client as seen on page 3. We will attempt to trace any utilities for which structures are visible from the work area. Utilities will be marked on the surface using paint, pin flags, or other appropriate means. The client will be responsible for providing drawings or notifying GPRS of any utilities entering the work area for which there are no apparent surface features or structures visible from the work area. To avoid additional charges, the areas should be laid out, marked, and cleared of obstructions before our arrival. Please visit www.simspec.org for an overview of our industry-leading best practices that will be applied to this project.

- GPRS is not responsible for housekeeping. Any debris, equipment, or other obstructions in the area at the time of scanning could potentially block out needed data.
- A thorough utility search can only be completed if GPRS is given access to all utility structures, interior and exterior. This service is never a replacement for the use of the state One Call system (811).
- All of our technicians have OSHA-10 safety training or greater. Site-specific safety training is not included in this quote. Please notify us if this project requires
 additional safety training.

EQUIPMENT

- Underground Scanning GPR Antenna. This GPR Antenna uses frequencies ranging from 250 MHz to 450 MHz and is mounted in a stroller frame that rolls over the surface. Data is displayed on a screen and marked in the field in real-time. The surface needs to be reasonably smooth and unobstructed to obtain readable scans. Obstructions such as curbs, landscaping, and vegetation will limit the efficacy of GPR. The total effective scan depth can be as much as 8' or more with this antenna but can vary widely depending on the soil conditions and composition. Some soil types, such as clay, may limit maximum depths to 3' or less. As depth increases, targets must be larger to be detected, and non-metallic targets can be challenging to locate. The depths provided should always be treated as estimates as their accuracy can be affected by multiple factors. For more information, please visit: Link
- Electromagnetic Pipe Locator. This receiver can passively detect the signals from live AC power or radio signals traveling along some conductive utilities. Operators can connect a transmitter directly to accessible metallic pipes, risers, or tracer wires to generate a current at a specific frequency. The receiver can then detect the resulting signal along the pipe or tracer wire. Various factors may impact this device's effectiveness, including (but not limited to) access to the utility, conductivity, grounding, and interference from other utilities. The depths provided should always be treated as estimates as their accuracy can be affected by multiple factors. For more information, please visit: Link
- Traceable Rodder. The rodder consists of a copper wire encased in fiberglass. This device is pushed through a pipe with direct access, such as a sewer line at a cleanout or a storm drain catch basin. Operators then induce a current on the wire and trace the signal from the surface. The maximum traceable depth is 10' depending on the soil conditions, and the maximum distance is 200'. Inserting the rodder into deeper pipes within manholes may not be feasible depending on site conditions. GPRS will not access electrical conduits. The signal is not detectable through metallic pipes. For more information, please visit: Link
- **GPS.** This handheld unit offers accuracy down to 4 inches; however, the accuracy achieved will depend on the satellite environment at the time of collection and is not considered survey-grade. Features can be collected as points, lines, or areas and then exported as a KML/KMZ or overlaid on a CAD drawing. For more information, please visit: <u>Link</u>

UTILITY LOCATING - VIDEO PIPE INSPECTION - LEAK DETECTION - MAPPING 8 MODELING - CONCRETE IMAGING - 3D LASER SCANNING



GPRSING COM

Supporting Documentation



UTILITY LOCATING VIDEO PIPE INSPECTION LEAK DETECTION MAPPING & MODELING CONCRETE IMAGING 3D LASER SCANNING

GPRSQUOTE-232568 v.2

Page 3 of 4

GPRSING COM //////

PROJECT COSTS

No Exception Taken

| SERVICE | | Catherine Blackler - AGCM (Maria Math. |
|---------------------------|--|---|
| FIELD SERVICES | Described on Page 2 | |
| JOB SUMMARY REPORT | PDF including a brief descri the conclusion of every job. | ption of equipment used, findings, limitations, and site photos sent at |
| SITEMAP® PERSONAL LICENSE | | with GPS and made available on SiteMap to access the automated SHP files and map viewer access on SiteMap. Results are not survey-formation, please visit: Link |
| TOTAL | | \$1,225.00 |

GENERAL TERMS & CONDITIONS


This proposal is subject to the General Terms and Conditions for Services of Ground Penetrating Radar Systems, LLC posted at Link (the "Terms and Conditions") and the Authorized User License Agreement for SiteMap® Accounts at Link and is hereby incorporated by reference into and made a part of this proposal. Customer acknowledges it has read and agrees to be bound by such Terms and Conditions. In the event of any conflict between the terms of this proposal and the Terms and Conditions, the Terms and Conditions will prevail.

- Customer agrees to meet and perform all requirements described in this document and has fully read and understands all items listed within this document.
- It is the customer's responsibility to prepare the site for scanning, including clearly identifying areas to be scanned, securing access to all areas required for 2. scanning, removing and keeping these areas clear and free of obstructions. Delays caused by customer's failure to do so may result in an increased price.
- GPRS does not conduct an investigation, analysis, or interpretation of soil composition, soil/concrete conditions, or geophysical, geological, engineering, or land 3. surveying information. The customer acknowledges understanding that we are merely reporting retrieved data and that we do NOT provide geophysical, geological, engineering, or land surveying services. Customer should contact a professional in those fields if such services are needed. Data collected during may only be suitable for use within the scope of this proposal.
- If any work to be performed is within a road or street, unless specifically included by GPRS within this proposal, it is the customer's responsibility to provide adequate traffic control to allow GPRS' personnel to safely and efficiently work in the road/street.
- Time-on-site in excess of 8-hours will be billed at overtime rates. 5.
- This price assumes that we will be given access to perform the work during normal, weekday business hours. Work performed outside of 6am-5pm Monday-Friday will be billed at overtime rates.
- These rates assume that there are certified payroll and/or prevailing wage requirements for this work. If GPRS receives notice that these conditions change, the 7. project costs will be modified accordingly and a change order may be required.
- If this proposal is not accepted within 90 days of September 24, 2025, then the pricing may be subject to review. 8
- If for some reason the technician arrives on site and the work is cancelled there will be a charge of \$500 per requested technician. 9.
- If your project is in WV, SD, NM, or HI: State sales tax is not included in the total on this proposal, but will be included on the invoice. 10.
- Payment Terms are Net 30; or as specified if a current Master Service Agreement is in place.

ACCEPTED AND AGREED

| Company Phone/Email: PO #: Job #: | |
|-----------------------------------|--|

GPRSQUOTE-232568 v.2 Page 4 of 4



LEGEND

PROPERTY LINE EXISTING CONTOUR 780 PROPOSED CONTOURS + 786.75 ---- GB---- PROPOSED GRADE BREAK -- SWALE --- PROPOSED SWALE

EXISTING ROOF DRAIN EXISTING ROOF DOWNSPOUT PROPOSED ROOF DOWNSPOUT

PROPOSED SPOT ELEVATION

1:12 RAMP (WITH HANDRAILS WHERE LENGTH > 6') SLOPED WALK (2% – 5%)

ABBREVIATIONS

EX EXISTING

TOC TOP OF CURB G GUTTER

~514.10 MATCH EX

- RELOCATE_SIGNAGE_IN_FRONT_OF


LOCATION WITH OWNER)

OR MOUNTED ON FENCE (CONFIRM

INVERT SD STORM DRAIN

TW TOP OF WALL BW BOTTOM OF WALL

NOTES:



DISTRICT \

VERNIA

SEE GENERAL NOTES C1.00
 SEE GRADING NOTES C4.00


LA VERNIA INDEPENDENT SCHOOL DISTRICT 13600 US HIGHWAY 87 V LA VERNIA, TX 78121



PROJECT NO. 05/30/2024 REVISIONS: 43 NEW SHEET/PR28 9/12/25

> GRADING PLAN -LIBRARY WALK

PACKAGE 2



BASE OF EDGE TURNDOWN ALONG THIS RAMP MAY STEP UP AS LONG AS BASE REMAINS

AT LEAST 1' BELOW ADJACENT GRADE

- WALKWAYS OTHER THAN RAMPS TO INCORPORATE 12" THICKENED EDGES BOTH SIDES, REF. DETAIL

178'-10 1/2"

59-1 1/2"

RELOCATE EXISTING FENCE

ALL WALKWAYS ALONG
ACCESSIBLE ROUTE TO HAVE MAX
1:12 SLOPE ON RAMPS, MAX 5%

GRADE ON SLOPES, MAX 5%
GRADE ON SLOPES, MAX 2%
SLOPE ON LANDINGS/CHANGES IN
DIRECTION, AND MAX 2% CROSS
SLOPE THROUGHOUT. CONTACT
ENGINEER IF ANY EXISTING
CONDITIONS REQUIRE
ADJUSTMENTS TO GRADES TO
MAINTAIN COMPLIANCE

514.85

140'-9"

∕-508.26 EX G

-509.30

TWO SETS OF 6"

HIGH BY 16" | WIDE STEPS

_508.64 EX G

TURNDOWN EDGES ALONG BOTH SIDES OF RAMPS AND LANDING REF. DETAIL SECTION THIS SHEET

MILL 1.5" OR REMOVE/REPLACE

ASPHALT TO ENSURE SMOOTH

SURFACE WITH <2% CROSS SLOPE

ALONG ACCESSIBLE PATH

PROTECT EXISTING TREES AND
MINIMAGE DISTURBANCE WITHIN
TREE CANOPY/ROOT ZONE. TRIM
ANY TREE BRANCHES CONFLICTING
AND PATHS. COORDINATE
TRIMMING WITH LANDSCAPE
APPLIETED.

ARCHITECT.

509.28

L_{510.90} EX TC

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

159'-8 1/4"

L510.50 EX TC

509.40¬

—— DOWEL TO EXISTING FLATWORK WITH #3 @ 12"

511.10 ~ MATCH EX-\

^L511.50 EX TC

1/////

509.10 BW——

509.20~

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

b Site

Green

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

RENTAL QUOTE

253423947

Estimated Out : 10/01/25 05:00 PM
Estimated In : 10/29/25 05:00 PM
UR Job Loc : 225 BLUEBONNET RD, L

UR Job # : 497 Customer Job ID: 231091 P.O. # : TBD

Ordered By : OZZY PADILLA Written By : SHEY MURRAY Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

| RENTAL ITEMS: Oty Equipment Description | Minimum | Day | Week 4 Week | Estimated Amt. |
|---|------------------------|---------|--|----------------------|
| 14 375/0525 FENCE MODULAR 12' L X 6' H TEM | PORARY PAN | 8.00 | 8.00 8 | .00 112.00 |
| 14 551/4405 FENCE PANEL METAL BASES | | | | N/C |
| 14 375/0402 FENCE CLAMPS | | | | N/C |
| CALES /MICCELLANEOUS ITEMS | | | Rental Subtotal | : 112.00 |
| SALES/MISCELLANEOUS ITEMS: Oty Item | | Price | Unit of Measure | <u>Extended Amt.</u> |
| 56 SANDBAGS, FILLED - 14X26 [ONE TIME FEE FOR SANDBAGS (4) SANDBAGS PER BASE WHEN APPLYING SCRE EN(56) SANDBAGS TOTAL NEEDED | FILLED SANDBAGS/BARRI] | 7.000 | EACH | 392.00 |
| 4 5'8"X50' GREEN ECON ONE TIME FEE FOR WINDSCREEN ((GRAY)) (50) LF PER PACK (4) PACKS TOTAL | [15700/CINDF] | 95.000 | EACH | 380.00 |
| 1 ASSEMBLY/DISMANTLE LABOR ONE TIME FEE FOR ASSEMBLY LABOR (\$0.75) PER LF (160) LF TOTAL (\$120) TOTAL FOR ASSEMBLY LABOR | [AD LABOR/MCI] | 120.000 | EACH | 120.00 |
| 1 ASSEMBLY/DISMANTLE LABOR ONE TIME FEE FOR DISMANTLE LABOR (\$0.75) PER LF (160) LF TOTAL (\$80) TOTAL FOR DISMANTLE LABOR | [AD LABOR/MCI] | 80.000 | EACH | 80.00 |
| 1 ENVIRONMENTAL SERVICE CHARGE | [ENV/MCI] | | EACH | N/C |
| 1 DELIVERY CHARGE | | 200.000 | EACH | 200.00 |
| 1 PICKUP CHARGE | | 200.000 | EACH | 200.00 |
| | | | Sales/Misc Subtotal | : 1,372.00 |
| | | | Agreement Subtotal Tax Estimated Total | : 122.43 |
| COMMENTS/NOTES: | | | | |

ONSITE CONTACT: OZZY PADILLA

CELL#: 210-870-7175

THERE ARE 103 FENCE PANELS ON SITE THAT CAN CONTINUED BE USED IN THIS AREA. LVISD TAKES EXPECPTION TO PURCHASING MORE FENCE PANELS WHILE OTHER LAY AROUND ON SITE.

This proposal may be withdrawn if not accepted within 3 ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN ge.

NOTICE: This is not a rental agreement. The rental of equipment and any items listed above is subject to availability and subject to the terms and conditions of the Rental and Service Agreement, which are available at https://www.unitedrentals.com/legal/rental-service-terms-US and which are incorporated herein by reference. A COPY OF THE RENTAL AND SERVICE AGREEMENT TERMS ARE AVAILABLE IN PAPER FORM UPON REQUEST.

UlinvPDF Page:

OUnited Rentals[,]

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

RENTAL QUOTE

253423947

Customer # : 205829 Quote Date

: 09/24/25 : 10/01/25 05:00 PM Estimated Out Estimated In : 10/29/25 05:00 PM UR Job Loc : 225 BLUEBONNET RD, L

: 497 UR Job # Customer Job ID: 231091 : TBD P.O. #

Ordered By : OZZY PADILLA Written By : SHEY MURRAY Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

COMMENTS/NOTES:

TO SCHEDULE EQUIPMENT FOR PICKUP, CALL 800-UR-RENTS (800-877-3687) WE ARE AVAILABLE 24/7 TO SUPPLY YOU WITH A CONFIRMATION # IN ORDER TO CLOSE THIS CONTRACT

> THERE ARE 103 FENCE PANELS ON SITE THAT CAN BE USED IN THIS AREA. LVISD TAKES EXPECPTION TO PURCHASING MORE FENCE PANELS WHILE OTHER LAY AROUND ON SITE.

ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

Site

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

BLUE

RENTAL QUOTE

253424216

Estimated Out : 10/01/25 05:00 PM
Estimated In : 10/29/25 05:00 PM
UR Job Loc : 225 BLUEBONNET RD, L

UR Job # : 497 Customer Job ID: 231091 P.O. # : TBD

Ordered By : OZZY PADILLA Written By : SHEY MURRAY Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

| RENTAL ITEMS: Oty _Equipment Description | Minimum | Day | Week 4 We | <u>ek Estimated Am</u> |
|--|-----------------|---------|-------------------|------------------------|
| 15 375/0525 FENCE MODULAR 12' L X 6' H TEMPORARY | PAN | 8.00 | 8.00 | 8.00 120.00 |
| 15 551/4405 FENCE PANEL METAL BASES | | | | N/C |
| 15 375/0402 FENCE CLAMPS | | | | N/C |
| NATIO (MAGGINA NATIONA ATTIMO). | | | Rental Subtot | al: 120.00 |
| SALES/MISCELLANEOUS ITEMS: Oty Item | | Price | Unit of Measu | re Extended Amt |
| 60 SANDBAGS, FILLED - 14X26 [FILLED ONE TIME FEE FOR SANDBAGS (4) SANDBAGS PER BASE WHEN APPLYING SCRE EN(60) SANDBAGS TOTAL | SANDBAGS/BARRI] | 7.000 | EACH | 420.00 |
| 4 5'8"X50' GREEN ECON ONE TIME FEE FOR WINDSCREEN ((GREY)) (50) LF PER PACLK (180) LF TOTAL | [15700/CINDF] | 95.000 | EACH | 380.00 |
| 1 ASSEMBLY/DISMANTLE LABOR ONE TIME FEE FOR ASSEMBLY LABOR (\$0.75) PER LF (180) LF TOTAL (\$135) TOTAL FOR ASSEMBLY LABOR | [AD LABOR/MCI] | 135.000 | EACH | 135.00 |
| 1 ASSEMBLY/DISMANTLE LABOR ONE TIME FEE FOR DISMANTLE LABOR (\$0.50) PER LF (180) LF TOTAL (\$90) TOTAL FOR DISMANTLE LABOR | [AD LABOR/MCI] | 90.000 | EACH | 90.00 |
| 1 ENVIRONMENTAL SERVICE CHARGE | [ENV/MCI] | | EACH | N/C |
| 1 DELIVERY CHARGE | | 200.000 | EACH | 200.00 |
| 1 PICKUP CHARGE | | 200.000 | EACH | 200.00 |
| | | | Sales/Misc Subtot | al: 1,425.00 |
| THERE ARE 103 FENCE PANELS ON SITE | THAT CAN | | Agreement Subtot | ax: 127.47 |

THERE ARE 103 FENCE PANELS ON SITE THAT CAN
BE USED IN THIS AREA. LVISD TAKES EXPECPTION
TO PURCHASING MORE FENCE PANELS WHILE OTHER
LAY AROUND ON SITE.

ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN

CONTINUED

1,672.47

This proposal may be withdrawn if not accepted within 30 days. The above referenced Rental Protection Plan, environmental, and tax charges are estimates and are subject to change.

NOTICE: This is not a rental agreement. The rental of equipment and any items listed above is subject to availability and subject to the terms and conditions of the Rental and Service Agreement, which are available at https://www.unitedrentals.com/legal/rental-service-terms-US and which are incorporated herein by reference. A COPY OF THE RENTAL AND SERVICE AGREEMENT TERMS ARE AVAILABLE IN PAPER FORM UPON REQUEST.

Estimated Total:

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

ob Site

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

RENTAL QUOTE

253424216

Customer # : 205829 Quote Date : 09/24/25 Estimated Out : 10/01/25

Estimated Out : 10/01/25 05:00 PM
Estimated In : 10/29/25 05:00 PM
UR Job Loc : 225 BLUEBONNET RD, L

UR Job # : 497 Customer Job ID: 231091 P.O. # : TBD

Ordered By : OZZY PADILLA Written By : SHEY MURRAY Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

COMMENTS/NOTES:

TO SCHEDULE EQUIPMENT FOR PICKUP, CALL 800-UR-RENTS (800-877-3687) WE ARE AVAILABLE 24/7 TO SUPPLY YOU WITH A CONFIRMATION # IN ORDER TO CLOSE THIS CONTRACT

THERE ARE 103 FENCE PANELS ON SITE THAT CAN BE USED IN THIS AREA. LVISD TAKES EXPECPTION TO PURCHASING MORE FENCE PANELS WHILE OTHER LAY AROUND ON SITE.

ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

b Site

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

RENTAL QUOTE

253424705

Estimated Out : 10/01/25 05:00 PM
Estimated In : 10/29/25 05:00 PM
UR Job Loc : 225 BLUEBONNET RD, L

UR Job # : 497 Customer Job ID: 231091 P.O. # : TBD

Ordered By : OZZY PADILLA
Written By : SHEY MURRAY
Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

Pink

| RENTAL ITEMS Oty Equip | : ment Description | Minimum | Day | Week 4 W | <u> Estimated Amt</u> |
|---------------------------|---|-------------------------|---------|------------------|-----------------------|
| 12 375/0 | 525 FENCE MODULAR 12' L X 6' H | TEMPORARY PAN | 8.00 | 8.00 | 8.00 96.00 |
| 12 551/4 | 405 FENCE PANEL METAL BASES | | | | N/C |
| 12 375/0 | 402 FENCE CLAMPS | | | | N/C |
| | | | | Rental Subto | otal: 96.00 |
| Oty Ite | LANEOUS ITEMS: m | | Price | Unit_of_Meas | sureExtended Amt. |
| ONE T | DBAGS, FILLED - 14X26 IME FEE FOR SANDBAGS ANDBAGS PER BASE WHEN APPLYING S) SANDBAGS TOTAL | [FILLED SANDBAGS/BARRI] | 7.000 | EACH | 392.00 |
| ONE T ((GRE (50) | "X50' GREEN ECON IME FEE FOR WINDSCREEN Y)) LF PER PACK ACKS NEEDED TOTAL | [15700/CINDF] | 95.000 | EACH | 285.00 |
| ONE T (\$0.7 (140) | EMBLY/DISMANTLE LABOR IME FEE FOR ASSEMBLY LABOR 5) PER LF LF TOTAL) TOTAL FOR ASSEMBLY LABOR | [AD LABOR/MCI] | 105.000 | EACH | 105.00 |
| ONE T (\$0.5 (140) | EMBLY/DISMANTLE LABOR IME FEE FOR DISMANTLE LABOR 0) PER LF LF TOTAL TOTAL FOR ASSEMBLY LABOR | [AD LABOR/MCI] | 70.000 | EACH | 70.00 |
| 1 ENV | IRONMENTAL SERVICE CHARGE | [ENV/MCI] | | EACH | N/C |
| 1 DEL | IVERY CHARGE | | 200.000 | EACH | 200.00 |
| 1 PIC | KUP CHARGE | | 200.000 | EACH | 200.00 |
| | | | | Sales/Misc Subto | tal: 1,252.00 |
| | | | | Agreement Subto | Tax: 111.21 |
| OM THE | DE ADE 102 PENCE DANET. | C ON CITE THAT CAN | т | | |

THERE ARE 103 FENCE PANELS ON SITE THAT CAN
BE USED IN THIS AREA. LVISD TAKES EXPECPTION
TO PURCHASING MORE FENCE PANELS WHILE OTHER

CONTINUED

ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN

LAY AROUND ON SITE.

This proposal may be withdrawn if not accepted within 30 days. The above referenced Rental Protection Plan, environmental, and tax charges are estimates and are subject to change.

NOTICE: This is not a rental agreement. The rental of equipment and any items listed above is subject to availability and subject to the terms and conditions of the Rental and Service Agreement, which are available at https://www.unitedrentals.com/legal/rental-service-terms-US and which are incorporated herein by reference. A COPY OF THE RENTAL AND SERVICE AGREEMENT TERMS ARE AVAILABLE IN PAPER FORM UPON REQUEST.

OUnited Rentals[,]

BRANCH 99J 22345 IH 35 N NEW BRAUNFELS TX 78132-4871 830-623-5590

LA VERNIA ISD BOND PROJECTS 225 BLUEBONNET RD LA VERNIA TX 78121-4793

Office: 210-655-1031

BARTLETT COCKE LP SAN ANTONIO 8706 LOCKWAY ST SAN ANTONIO TX 78217-4837

RENTAL QUOTE

253424705

Customer # : 205829 Quote Date

: 09/24/25 : 10/01/25 05:00 PM Estimated Out Estimated In : 10/29/25 05:00 PM UR Job Loc : 225 BLUEBONNET RD, L

: 497 UR Job # Customer Job ID: 231091 : TBD P.O. #

Ordered By : OZZY PADILLA Written By : SHEY MURRAY Salesperson : SHEY MURRAY

This is not an invoice Please do not pay from this document

COMMENTS/NOTES:

TO SCHEDULE EQUIPMENT FOR PICKUP, CALL 800-UR-RENTS (800-877-3687) WE ARE AVAILABLE 24/7 TO SUPPLY YOU WITH A CONFIRMATION # IN ORDER TO CLOSE THIS CONTRACT

THERE ARE 103 FENCE PANELS ON SITE THAT CAN BE USED IN THIS AREA. LVISD TAKES EXPECPTION TO PURCHASING MORE FENCE PANELS WHILE OTHER LAY AROUND ON SITE.

ONLY COST ON HERE ACCEPTABLE IS THE WIND SCREEN

1 of 1 Updated: 9/23/2025 2:41 PM

| | | | Unit Cost | | | | 7 | Fotal Item Co | st | | AX & PTI Include | |
|--|-----|-----|-----------|---------|---------|---------|---------|---------------|---------|---------|------------------|-------|
| | | | Sub | Mat | Equip | Lab | Sub | Mat | Equip | Lab | Total | Total |
| DESCRIPTION | QTY | U/M | Unit \$ | Unit \$ | Unit \$ | Unit \$ | Item \$ | Item \$ | Item \$ | Item \$ | Item \$ | Price |
| ON THE ANALYSE CUEFFE CORVICOLUMNS "P" TURL "U" TO INCEPT THE PETALLINEO IN DOWE PELOW | | | | | | • | | • | | | | |

La Vernia ISD District Wide Additions & Renovations UNIT COST DIRECT COST with TAX & INS. Provide Routine Maintenance of Temporary Construction Fence QTY U/M TOTAL PRICE LABOR Project Duration 6.00 wks Fence Footage 490.00 Equipment/Fuel/Tools/Ties 490.00 2.25 1,193 1,193 6,860 1,193.46 6,860.00 Labor (25 hour per 300LF per week) (Multiple Phases - Active Campus) 245.00 hrs 6,860 on items not incorporated into the finished project 1.00 SUB TOTAL: 1,193 6,860 8,053 403 403 8,859 What is the crew rate that make ups this item What Need to break makes up down man hours this line and crew rate item? \$ 1,193.00 THERE NEEDS TO BE MORE TRANSPARENCY AS TO WHAT EXACTLY description THIS COST IS. IT NEEDS TO BE BROKEN OUT AND ITEMIZED is too vague

| BC - Initial Staking, Maintain Control, and Grade Verification' | | | | | | | | Y202 | 25 |
|--|----|-----|-----|----|----------|-----|------|------|----------|
| | | TV | | | Cub | | | Loh | |
| | Q | II | Sub | | | Lab | | |) |
| Layout Tech | 25 | hrs | \$- | \$ | - | \$3 | 9.20 | \$ | 980.00 |
| Layout Tech Helper | 25 | hrs | \$- | \$ | - | \$3 | 6.40 | \$ | 910.00 |
| Instrument, LM80 Robotic GPS | 1 | mo | \$- | \$ | 2,850.00 | \$ | - | \$ | 2,850.00 |
| Materials/Tools/Paint/Markers | 1 | ls | \$- | \$ | 285.00 | \$ | - | \$ | 285.00 |
| | | | | | | | | \$ | 5,025.00 |
| | | | | | | | | \$ | 502.50 |
| | | | | | | | | \$ | 5,527.50 |



No Exception Taken

Catherine Blackler - AGCM (Manual Manual



$lap{AIA}^{\circ}$ Document G709 $^{\circ}$ – 2018

Proposal Request

PROJECT: (name and address)

La Vernia ISD 2023 Bond

CONTRACT INFORMATION:

Architect's Project Number: 22075

Proposal Request Number: 28

General Construction

Date: December 19, 2002

Contract For:

Proposal Request Date: September 16,

OWNER: (name and address)

La Vernia ISD

13600 US Highway 87 W La Vernia, TX 78121

ARCHITECT: (name and address)

Pfluger Architects 200 E. Grayson Street San Antonio, TX 78215

CONTRACTOR: (name and address) **Bartlett Cocke General Contractors**

8706 Lockway

San Antonio, TX 78217

The Owner requests an itemized proposal for changes to the Contract Sum and Contract Time for proposed modifications to the Contract Documents described herein. The Contractor shall submit this proposal within Fourteen (14) days or notify the Architect in writing of the anticipated date of submission.

(Insert a detailed description of the proposed modifications to the Contract Documents and, if applicable, attach or reference specific exhibits.)

Provide itemized cost proposal to incorporate addition of an accessible path between High School Building 400 and High School Library including grading changes, additional concrete flatwork, and additional details.

PR # 28 (pages 1 thru 4), attached.

THIS IS NOT A CHANGE ORDER, A CONSTRUCTION CHANGE DIRECTIVE, OR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED IN THE PROPOSED MODIFICATIONS.

9.16.2025

REQUESTED BY THE ARCHITECT

ARCHITECT (Signature)

BY: Braden Haley, AIA

(Printed name, title, and license number if required)

BOARD OF TRUSTEES **PRESIDENT** VICE PRESIDENT

SECRETARY

TRUSTEE

TRUSTEE

DR. HELEN WHISENHUNT PAUL GOETZKE

MR. SHAWN STREY

MR. DREW HERLEY

MR. RYAN DOEGE

MR. JOEY GOODE

MR. STEWART KRISCH

MR. JIMMY MCFADIN

MR. JEFF TOWNS

GYMNASIUM FUNCTIONAL DIAGRAMS

GYMNASIUM DETAILS

CAFETERIA DETAILS

MOUNTING DETAILS

GENERAL NOTES & LEGENDS

RCP - FIRST FLOOR - HIGH SCHOOL RCP - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

STRUCTURED CABLING PLATE DETAILS

STRUCTURED CABLING PLATE DETAILS

STRUCTURED CABLING PLATE DETAILS

STRUCTURED CABLING DETAILS

WALL PENETRATIONS

CABLE PATHWAY DETAILS

GENERAL NOTES & LEGENDS

STRUCTURED CABLING LABELING DETAILS

FLOOR PLAN - FIRST FLOOR - HIGH SCHOOL

FLOOR PLAN - FIRST FLOOR - HIGH SCHOO

FLOOR PLAN - FIRST FLOOR - HIGH SCHOO

FLOOR PLAN - FIRST FLOOR - HIGH SCHOOL

FLOOR PLAN - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

GENERAL NOTES & LEGENDS

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL

INTERCOM SYSTEM FUNCTIONAL DIAGRAMS

FLOOR PLAN - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

SECURITY DEVICE SCHEDULE

ACCESS CONTROL DETAILS

ACCESS CONTROL DETAILS

ACCESS CONTROL DETAILS

VIDEO SURVEILLANCE DETAILS

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG B

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

FLOOR PLAN - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG A

FLOOR PLAN - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG B

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG B

NTERCOM FUNCTIONAL LEGEND AND STANDARD DETAILS

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

FLOOR PLAN - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG A

FLOOR PLAN - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG B

ES10.02L

ES18.01

ES18.02

ES18.03

ES18.04

ES18.05

ES18.06

ES18.08

ESD02.00B

IC00.00

IC02.01E

IC02.01F

IC02.01G

IC02.01H

IC02.01J

IC02.01K

IC02.01L

IC02.01M

IC02.02L

IC10.01G

IC10.01H

IC10.01J

IC10.01K

IC10.01L

IC10.01M

IC10.02L

IC10.02M

IC11.00

IC11.10

SC00.00

SC02.01F

SC02.01G

SC02.01J

SC02.01L

SC02.02L

SC02.02M

SC10.01K

SC10.01M

SC10.01L

SC19.10

SC19.70

SC19.71

SC19.72

SC02.01K

SC02.01M

ES10.02M

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - SECOND FLOOR - JUNIOR HIGH SCHOOL SEG B

STRUCTURED CABLING GROUNDING AND BONDING DETAILS

DEMO PLAN - COMPOSITE - HIGH SCHOOL & JUNIOR HIGH

SUPERINTENDENT OF SCHOOLS CHIEF INSTRUCTIONAL OFFICER **DIRECTOR OF HUMAN RESOURCES**


OWNER

La Vernia Independent School District 13600 US Hwy 87 La Vernia, Texas 78121 PH: 830/779-6600 www.lvisd.org

OWNER REPRESENTATION

85 NE Loop 410, Suite 600 San Antonio, Texas 78216 PH: 210/403-2284 www.agcm.com

LOCATION MAP



ALTERNATE BID ITEMS

ALTERNATE 01 - CONTRACTOR TO PROVIDE BID PRICING FROM EACH OF THE FOLLOWING MANUFACTURERS FOR DX VAV ROOF TOP UNITS INCLUDING MATERIAL AND LABOR SEPARATELY: A. DAIKIN, B. TRANE, C. AAON ALTERNATE 02 - CONTRACTOR TO PROVIDE BID PRICING FROM EACH OF THE FOLLOWING MANUFACTURERS FOR SINGLE PACKAGED AIR CONDITIONER UNITS INCLUDING MATERIAL AND LABOR SEPARATELY: A. DAIKIN, B. TRANE, C. YORK ALTERNATE 03 - CONTRACTOR TO PROVIDE BID PRICING FROM EACH OF THE FOLLOWING MANUFACTURERS FOR SERIES FAN POWERED BOXES AND SINGLE DUCT VAV BOXES INCLUDING MATERIAL AND LABOR SEPARATELY: A. PRICE, B. TRANE, C. TITUS ALTERNATE 04 - CONTRACTOR TO PROVIDE BID PRICING FROM EACH OF THE FOLLOWING MANUFACTURERS FOR AIR-COOLED PACKAGED SCREW CHILLER UNITS INCLUDING MATERIAL AND LABOR SEPARATELY: A. DAIKIN, B. TRANE, C. YORK, D. QUANTECH ALTERNATE 05 - CONTRACTOR TO PROVIDE BID PRICING FROM EACH OF THE FOLLOWING MANUFACTURERS FOR PACKAGED OUTSIDE-AIR UNITS WITH PLATE FRAME HEAT EXCHANGERS INCLUDING MATERIAL AND LABOR SEPARATELY: A. DAIKIN, B. TRANE, C. AAON ALTERNATE 06 - CONTRACTOR TO PROVIDE BID PRICING FOR (1) 2500 KVA TRANSFORMER IN LIEU OF (2) 750 KVA PAD MTD.

ALTERNATE 08: PROVIDE PRICE TO INSTALL FIRE LINE INTERCONNECT TO PRIMARY SCHOOL FIRE SERVICE LINE AS SHOWN

DISTRICT WIDE ADDITIONS / RENOVATIONS JUNIOR HIGH SCHOOL & HIGH SCHOOL

LA VERNIA INDEPENDENT SCHOOL DISTRICT

PACKAGE 02 - VOLUME 01 - 100% CONTRACT DOCUMENTS

MAY 31ST, 2024

UNDERFLOOR FLOOR PLAN - AREA H - PLUMBING

UNDERFLOOR PLAN - JUNIOR HIGH - AREA A-1 - PLBG

COMPOSITE FIRST FLOOR - HS & JHS - PLUMBING

FIRST FLOOR - JUNIOR HIGH - AREA B-1 - PLBG

FIRST FLOOR - JUNIOR HIGH - AREA A-1 - PLBG

ENLARGED KITCHEN FLOOR PLANS - PLUMBING

FIRST FLOOR - AREA F - PLBG DEMOLITION

FIRST FLOOR - AREA H - PLBG DEMOLITION

FIRST FLOOR - AREA J - PLBG DEMOLITION

FIRST FLOOR - AREA K - PLBG DEMOLITION

FIRST FLOOR - AREA L - PLBG DEMOLITION

ROOF PLAN - AREA K - PLBG DEMOLITION

ROOF PLAN - AREA L - PLBG DEMOLITION

ROOF PLAN - AREA L - PLBG DEMOLITION

KITCHEN EQUIPMENT FLOOR PLAN SEGMENT F

KITCHEN EQUIPMENT FLOOR PLAN SEGMENT F

KITCHEN EQUIPMENT FLOOR PLAN SEGMENT F

KITCHEN PLUMBING ROUGH-IN PLAN SEGMENT

KITCHEN ELECTRICAL ROUGH-IN PLAN SEGMENT F

KITCHEN SPECIAL CONDITIONS PLAN SEGMENT F

KITCHEN EXHAUST HOOD DETAILS SEGMENT F

KITCHEN EXHAUST HOOD DETAILS SEGMENT F

SERVING COUNTER DETAILS SEGMENT F

CUSTOM FABRICATION DETAILS SEGMENT I

CUSTOM FABRICATION DETAILS SEGMENT I

AUDIO-VIDEO EQUIPMENT RACK DETAILS

FLOOR PLAN - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

RCP - FIRST FLOOR - HIGH SCHOOL

CLASSROOM FUNCTIONALS

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

RCP - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

AUDIO-VIDEO FUNCTIONAL LEGEND AND STANDARD DETAILS

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG A

FLOOR PLAN - FIRST FLOOR - JUNIOR HIGH SCHOOL SEG B

GENERAL NOTES & LEGENDS

ELEVATIONS

ELEVATIONS

KITCHEN WALK-IN COOLER FREEZER DETAILS SEGMENT F

KITCHEN WALK-IN COOLER FREEZER DETAILS SEGMENT F

KITCHEN REFRIGERATION RACK DETAILS SEGMENT F

FIRST FLOOR - AREA M - PLBG DEMOLITION

COMPOSITE FIRST FLOOR - HS & JHS - PLBG DEMOLITION

FIRST FLOOR - AREA F - PLUMBING

FIRST FLOOR - AREA G - PLUMBING

FIRST FLOOR - AREA J - PLUMBING

FIRST FLOOR - AREA K - PLUMBING

ROOF PLAN - AREA J - PLUMBING ROOF PLAN - AREA K - PLUMBING

ROOF PLAN - AREA L - PLUMBING

ROOF PLAN - AREA M - PLUMBING

ROOF PLAN - AREA L - PLUMBING

RISER DIAGRAMS - PLUMBING

RISER DIAGRAMS - PLUMBING

RISER DIAGRAMS - PLUMBING

DETAILS - PLUMBING

DETAILS - PLUMBING

FOOD SERVICE

P3.1M

PD2.1

PD2.1F

PD2.1H

PD2.1L

FS2.01F

FS2.02F

FS3.03F

FS4.03F

FS4.04F

FS4.06F

FS4.07F

FS4.09F

FS4.10F

AV00.90

AV02.01E

AV02.01G

AV02.01K

AV02.02M

AV04.01

AV04.02

AV10.01F

AV10.01H

AV10.01J

AV10.01K

UNDERFLOOR PLAN - JUNIOR HIGH - AREA B-1 - PLBG

FIRST FLOOR - AREA K - HVAC DEMO

FIRST FLOOR - AREA L - HVAC DEMO

FIRST FLOOR - AREA M - HVAC DEMO

ELECTRICAL LEGEND & LIGHT FIXTURE SCHEDULE

ELECTRICAL ONE-LINE DIAGRAM - HS SERVICE

ELECTRICAL ONE-LINE DIAGRAM - HS

ELECTRICAL SCHEDULES - HS & JHS PANELBOARD SCHEDULES - HS - SEG F&G

SITE PLAN - HS & JH - ELECTRICAL

PANELBOARD SCHEDULES - HS - SEG F&G

PANELBOARD SCHEDULES - HS - SEG F&G

ELECTRICAL ONE-LINE DIAGRAM - HS - ATHLETICS-BAND - EXISTING

ELECTRICAL ONE-LINE DIAGRAM - HS - BLDGS. 200 & 300 - EXISTING

ELECTRICAL ONE-LINE DIAGRAM - HS - BLDGS. 400 & 500 - EXISTING

ELECTRICAL ONE-LINE DIAGRAM - JH - BLDG 100 - EXISTING

ELECTRICAL ONE-LINE DIAGRAM - JH - BLDG 600 - EXISTING

PANELBOARD SCHEDULES - JH - SEG M - FIRST FLOOR

PANELBOARD SCHEDULES - JH - SEG M - FIRST FLOOR

OVERALL EXTERIOR LIGHTING PLAN - HIGH SCHOOL

FLOOR PLAN - LEVEL 01 - SEG E -LIGHTING

FLOOR PLAN - LEVEL 01 - SEG F - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG G - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG H - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG J - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG K - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG L - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG M - LIGHTING

FLOOR PLAN - LEVEL 02 - SEG L - LIGHTING

FLOOR PLAN - LEVEL 02 - SEG M - LIGHTING

FLOOR PLAN - LEVEL 01 - SEG E - POWER

FLOOR PLAN - LEVEL 01 - SEG F - POWER

FLOOR PLAN - LEVEL 01 - SEG G - POWER

FLOOR PLAN - LEVEL 01 - SEG H - POWER

FLOOR PLAN - LEVEL 01 - SEG J - POWER

FLOOR PLAN - LEVEL 01 - SEG K - POWER

FLOOR PLAN - LEVEL 01 - SEG L - POWER

FLOOR PLAN - LEVEL 01 - SEG M - POWER

FLOOR PLAN - LEVEL 02 - SEG L - POWER

FLOOR PLAN - LEVEL 02 - SEG M - POWER

FLOOR PLAN - LEVEL 01 - SEG E - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG F - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG G - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG H - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG J - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG K - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG L - FIRE ALARM

FLOOR PLAN - LEVEL 01 - SEG M - FIRE ALARM

FLOOR PLAN - LEVEL 02 - SEG L - FIRE ALARM

FLOOR PLAN - LEVEL 02 - SEG M - FIRE ALARM

SITE PLAN - HS & JHS - ELECTRICAL DEMOLITION

GYM COORDINATION - FLOOR PLAN - SEG L

OVERALL SITE PLAN - PLUMBING

ENLARGED SITE PLAN - PLUMBING

ENLARGED SITE PLAN - PLUMBING

FLOOR PLAN - LEVEL 01 - SEG E - ELECTRICAL DEMOLITION

FLOOR PLAN - LEVEL 01 - SEG H - ELECTRICAL DEMOLITION

FLOOR PLAN - LEVEL 01 - SEG J - ELECTRICAL DEMOLITION

FLOOR PLAN - LEVEL 01 - SEG K - ELECTRICAL DEMOLITION

COMPOSITE UNDERFLOOR PLAN - HS & JHS - PLUMBING

LEGEND. ABBREVIATIONS. GENERAL NOTES & SCHEDULES - PLUMBING

ENLARGED KITCHEN PLAN - POWER

ENLARGED VIEWS - POWER

ROOF PLAN - SEG F - POWER

ROOF PLAN - SEG J - POWER

ROOF PLAN - SEG K - POWER

ROOF PLAN - SEG L - POWER

ROOF PLAN - SEG M - POWER

LIGHTING CONTROLS

LIGHTING CONTROLS

LIGHTING CONTROLS

LIGHTING CONTROLS

DETAILS - ELECTRICAL

DETAILS - ELECTRICAL

DETAILS - ELECTRICA

FLOOR PLAN - LEVEL 01 - SEG E-J - COMPOSITE POWER

FLOOR PLAN - LEVEL 01 - SEG K-M - COMPOSITE POWER

FLOOR PLAN - LEVEL 02 - SEG L-M - COMPOSITE POWER

PANELBOARD SCHEDULES - JH - SEG M&L - FIRST FLOOR

PANELBOARD SCHEDULES - JH - SEG L&M - SECOND FLOOR

OVERALL EXTERIOR LIGHTING PLAN - JUNIOR HIGH SCHOOL

PANELBOARD SCHEDULES - JH - SEG L&M - FIRST SECOND FLOOR

ELECTRICAL ONE-LINE DIAGRAM - HS - BLDG 100 & LIB-GYM - EXISTING

SHEET INDEX

| VOLUME OF | | | | | | |
|-----------|--------|---------|--|--|--|--|
| | | | | | | |
| | G00.12 | Unnamed | | | | |

VOLUME 04

| | 000.02 | 7.67. 2012 |
|---|--------|--|
| | G00.03 | ADA - 2012 |
| | G00.04 | CODE REVIEW & LIFE SAFETY - LEVEL 01 - SEGMENT E |
| | G00.05 | CODE REVIEW & LIFE SAFETY - LEVEL 01 - SEGMENT G-H |
| | G00.06 | CODE REVIEW & LIFE SAFETY - LEVEL 01 - SEG. K-M |
| | G00.07 | CODE REVIEW & LIFE SAFETY - LEVEL 02 - SEG. K-M |
| | G00.08 | EXISTING CONDITIONS PHOTOS - HS |
| | G00.09 | EXISTING CONDITIONS PHOTOS - HS |
| | G00.10 | EXISTING CONDITIONS PHOTOS - JHS |
| | G00.11 | EXISTING CONDITIONS PHOTOS - JHS |
| | С | CIVIL |
| | C1.00 | OVERALL SITE PLAN |
| | C1.01 | DEMOLITION PLAN - HIGH SCHOOL |
| | C1.02 | DEMOLITION PLAN - JUNIOR HIGH SCHOOL |
| | C1.10 | FIRE PROTECTION PLAN - JUNIOR HIGH & HIGH SCHOOL |
| | C2.00 | SWPPP - JUNIOR HIGH & HIGH SCHOOL |
| | C2.10 | SWPPP - DETAILS |
| | C3.00 | DIMENSIONAL CONTROL PLAN - WEST |
| 4 | C3.01 | DIMENSIONAL CONTROL PLAN - EAST |
| | C3.10 | SITE DETAILS |
| | C3.11 | SITE DETAILS |
| | C4.00 | OVERALL GRADING PLAN |
| | C4.01 | GRADING PLAN - HIGH SCHOOL WEST |
| | C4.02 | GRADING PLAN - HIGH SCHOOL EAST |
| | C4.03 | GRADING PLAN - JUNIOR HIGH & BAND HALL |
| | C4.10 | GRADING DETAILS |
| | C5.00 | DRAINAGE PLAN - HIGH SCHOOL WEST |
| | C5.01 | DRAINAGE PLAN - HIGH SCHOOL EAST |
| | C5.02 | DRAINAGE PLAN - JUNIOR HIGH & BAND HALL |
| | C6.00 | OVERALL UTILITY PLAN |
| | C6.01 | UTILITY DETAILS |
| | L | LANDSCAPE |
| | | |

OVERALL LANDSCAPE PLAN HIGH SCHOOL ENLARGED LANDSCAPE PLAN JUNIOR HIGH ENLARGED LANDSCAPE PLAN LANDSCAPE DETAILS L02.00 OVERALL IRRIGATION PLAN L02.01 HIGH SCHOOL ENLARGED IRRIGATION PLAN JUNIOR HIGH SCHOOL ENLARGED IRRIGATION PLAN RRIGATION DETAILS AND NOTES **ARCHITECTURAL**

A00.01 ABBREVIATIONS & SYMBOLS WALL TYPES - MASONRY WALL TYPES - METAL STUDS PHASING PLAN HIGH SCHOO PHASING PLAN JUNIOR HIGH DEMOLITION PLAN - COMPOSITE - HS & JHS DEMOLITION PLAN - SEG E AD00.03 **DEMOLITION PLAN - SEG H-J DEMOLITION PLAN - SEG K DEMOLITION PLAN - SEG L** SITE PLAN - OVERAL! SITE PLAN - COMPOSITE - HIGH SCHOOL SITE PLAN - COMPOSITE - JUNIOR HIGH **ENLARGED SITE PLAN - SEG F** ENLARGED SITE PLAN - SEG F & H

ENLARGED SITE PLAN - SEG L & M A01.06 SITE DETAILS ENLARGED SITE PLAN JHS PORTABLE PLAN FLOOR PLAN - LEVEL 01 - SEG. F & G FLOOR PLAN - LEVEL 01 - SEG. H

FLOOR PLAN - LEVEL 01 - SEG. J FLOOR PLAN - LEVEL 01 - SEG. K FLOOR PLAN - LEVEL 01 - SEG. K FLOOR PLAN - LEVEL 01 - SEG. I FLOOR PLAN - LEVEL 01 - SEG. M FLOOR PLAN - LEVEL 02 - SEG. I FLOOR PLAN - LEVEL 02 - SEG. M **ENLARGED PLANS**

A09.17 GYM STRIPING PLAN - SEG L

A09.10

<u>√1</u> A09.12

WALL SECTIONS WALL SECTIONS WALL SECTIONS WALL SECTIONS A07.18 WALL SECTIONS WALL SECTIONS SECTION DETAILS DOOR SCHEDULE DOOR & FRAME TYPES DOOR & FRAME TYPES DOOR & FRAME TYPES TYPICAL OPENING DETAIL DOOR & WINDOW DETAILS A08.07 DOOR & WINDOW DETAILS DOOR & WINDOW DETAILS DOOR & WINDOW DETAILS DOOR & WINDOW DETAILS ROOM FINISH SCHEDULI FINISH FLOOR PLAN - COMPOSITES FLOOR FINISH PLAN - LEVEL 01 - SEG E FLOOR FINISH PLAN - LEVEL 01 - SEG F FLOOR FINISH PLAN - LEVEL 01 - SEG L FLOOR FINISH PLAN - LEVEL 01 - SEG M FLOOR FINISH PLAN - LEVEL 02 - SEG M

STAIR & RAMP DETAILS

ROOF PLAN - COMPOSIT

ROOF PLAN - SEG F

ROOF PLAN - SEG G-J

PLAN DETAILS

PLAN DETAILS

PLAN DETAILS

PLAN DETAILS

PLAN DETAILS

ROOF DETAILS

ROOF DETAILS

BUILDING SECTIONS

BUILDING SECTIONS

BUILDING SECTIONS

BUILDING SECTIONS

BUILDING SECTIONS

WALL SECTIONS

WALL SECTIONS

WALL SECTIONS

WALL SECTIONS WALL SECTIONS

WALL SECTIONS

WALL SECTIONS

STANDING SEAM ROOF DETAILS S2.03G S2.03J S2.03K S2.03L S2.03M S2.05 S2.06

REFLECTED CEILING PLAN - LEVEL 02 - SEG. L

DIMENSIONAL PLAN - SEG. F & G, L & M

FOUNDATION FRAMING PLAN - SEG. F CAFETERIA

SECOND FLOOR FRAMING - SEG. L GYM/LIBRARY

ROOF FRAMING PLAN - SEG. J BAND HALL & TRAIN. RM.

ROOF FRAMING PLAN - SEG. K BAND HALL ADDITION

COMPOSITE SECOND FLOOR & ROOF PLAN

ROOF FRAMING PLAN - SEG. F CAFETERIA

ROOF FRAMING PLAN - SEG. L GYM_LIBRARY

ROOF FRAMING PLAN - SEG. M LOCKER ROOM

ROOF FRAMING PLAN - SEG. G CTE

CANOPY FRAMING PLANS

TYPICAL FOUNDATION DETAILS

ENLARGED PLANS

ENLARGED PLANS

SECTIONS AND DETAILS

BRACE DETAILS AND ELEVATIONS

LEGEND, ABBREV., GENERAL NOTES - HVAC

FIRST FLOOR - JUNIOR HIGH - AREA L - HVAC

FIRST FLOOR - JUNIOR HIGH - AREA M - HVAC

ROOF PLAN - JUNIOR HIGH - AREA L - HVAC

ROOF PLAN - JUNIOR HIGH - AREA M - HVAC

FIRST FLOOR - AREA F - HVAC DEMO

FIRST FLOOR - AREA G - HVAC DEMO

SECOND FLOOR - JUNIOR HIGH - AREA L - HVAC

SECOND FLOOR - JUNIOR HIGH - AREA M - HVAC

BRACE ELEVATIONS

CMU NOTES AND DETAILS

TYPICAL CMU DETAILS

SCHEDULES - HVAC

SCHEDULES - HVAC

FIRST FLOOR - AREA E - HVAC

FIRST FLOOR - AREA F - HVAC

FIRST FLOOR - AREA G - HVAC

FIRST FLOOR - AREA H - HVAC

FIRST FLOOR - AREA J - HVAC

ROOF PLAN - AREA F - HVAC

ROOF PLAN - AREA J - HVAC

ROOF PLAN - AREA K - HVAO

DETAILS - HVAC

DETAILS - HVAC

CONTROLS - HVAC

ELEVATIONS

MECHANICAL

VOLUME 02

S7.01

M2.1F

MD2.1F

TYPICAL FRAMING DETAILS

TYPICAL COMPOSITE DETAILS

RAMP FRAMING

SITE SECTIONS

FOUNDATION FRAMING PLAN - SEG. J BAND HALL & TRAIN. RM.

FOUNDATION FRAMING PLAN - SEG. G CTE

STRUCTURAL NOTES

SPECIAL INSPECTIONS

INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS

INTERIOR ELEVATIONS NTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS NTERIOR ELEVATIONS INTERIOR ELEVATIONS MILLWORK DETAILS REFLECTED CEILING PLAN - COMPOSITES

REFLECTED CEILING PLAN - LEVEL 01 - SEG. E REFLECTED CEILING PLAN - LEVEL 01 - SEG. F REFLECTED CEILING PLAN - LEVEL 01 - SEG. G REFLECTED CEILING PLAN - LEVEL 01 - SEG. H REFLECTED CEILING PLAN - LEVEL 01 - SEG. J REFLECTED CEILING PLAN - LEVEL 01 - SEG. K

Cooper-Lochte Landscape Architecture, LLC 12770 Cimarron Path, Suite 100 San Antonio, Texas 78249 PH: 210/821-6570

STRUCTURAL ENGINEER

Alpha Consulting Engineers 8023 Vantage Drive, Suite 1101 San Antonio, Texas 78230 PH: 210/227-3647 www.alphaconsultingengineers.com

MEP ENGINEER

MEP Engineering 9830 Colonnade Blvd San Antonio, Texas 78230 PH: 210/349-1400 www.mepengineering.com

AUDIO/VISUAL/TECHNOLOGY

WJHW, Inc. 12175 Network Blvd, Suite 150 San Antonio, Texas 78249 PH: 972/934-3700 www.wjhw.com

FOOD SERVICE

Cosper & Associates 13061 S Hwy 181, Suite 3 San Antonio, Texas 78223 PH: 210/633-2020 www.cosperfsc.com

ARCHITECT

ENLARGED PLANS

ENLARGED PLANS

ENLARGED PLANS

ENLARGED PLANS

ENLARGED PLANS

STAIR PLANS & SECTIONS

Pfluger Architects 200 E. Grayson Street, Suit 115 San Antonio, Texas 78215 PH: 210/227-2724 www.pflugerarchitects.com

CIVIL ENGINEER

Pape-Dawson Engineers, Inc.

2000 NW Loop 1604

San Antonio, Texas 78213

PH: 210/375-9000

www.pape-dawson.com

www.cooper-lochte.com

LANDSCAPE ARCHITECT

COVER - PKG 02

VOLUME 01

G00.01

PACKAGE 2

PROJECT NO.

REVISIONS:


1 ADD. 01 2 ADD. 02 4 ADD. 04

43 PR # 28

05/31/2024


06/07/2024 06/14/2024 06/19/2024

09/16/2025



22-075 05/31/2024

PR # 28 2 of 4









PROJECT NO. 05/31/2024 09/16/2025 **ENLARGED SITE** PEDESTRIAN PATH

PACKAGE 2

PR # 28 3 of 4





<u>LEGEND</u>

| | PROPERTY LINE |
|------------------|--------------------|
| | EXISTING CONTOUR |
| 780 | PROPOSED CONTOUR |
| + 786.75 | PROPOSED SPOT ELI |
| + HP | PROPOSED HIGH POI |
| — — — GB — — — — | PROPOSED GRADE B |
| SWALE | PROPOSED SWALE |
| | EXISTING ROOF DRAI |
| | |

PROPOSED CONTOURS PROPOSED SPOT ELEVATION PROPOSED HIGH POINT PROPOSED GRADE BREAK PROPOSED SWALE EXISTING ROOF DRAIN EXISTING ROOF DOWNSPOUT

PROPOSED ROOF DOWNSPOUT

1:12 RAMP (WITH HANDRAILS WHERE LENGTH > 6') SLOPED WALK (2% – 5%)

ABBREVIATIONS

EX EXISTING

TOC TOP OF CURB G GUTTER

/-514.10 MATCH EX


RELOCATE SIGNAGE IN FRONT OF OR MOUNTED ON FENCE (CONFIRM

LOCATION WITH OWNER)

-514.85

- INVERT SD STORM DRAIN
- TW TOP OF WALL BW BOTTOM OF WALL

NOTES:



WIDE HIGH


DISTRICT \

INDE

VERNIA

SEE GENERAL NOTES C1.00
 SEE GRADING NOTES C4.00

LA VERNIA INDEPENDENT SCHOOL DISTRICT 13600 US HIGHWAY 87 V LA VERNIA, TX 78121



PROJECT NO. 05/30/2024 REVISIONS: 43 NEW SHEET/PR28 9/12/25

GRADING PLAN -LIBRARY WALK

TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #10028800

PACKAGE 2

#4 BARS @ 12" O.C. HORIZONTAL SELECT FILL — BASE OF TURNDOWN ELEV 508.5 (MAY STEP UP WHERE NOTED) **ELEVATED RAMP SECTION (TYP.)** PAPE-DAWSON ENGINEERS 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000

BASE OF EDGE TURNDOWN ALONG THIS RAMP MAY STEP
UP AS LONG AS BASE REMAINS
AT LEAST 1' BELOW ADJACENT GRADE

513.75

- WALKWAYS OTHER THAN RAMPS TO INCORPORATE 12" THICKENED EDGES BOTH SIDES, REF. DETAIL

RELOCATE EXISTING FENCE

^L514.70

ALL WALKWAYS ALONG
ACCESSIBLE ROUTE TO HAVE MAX
1:12 SLOPE ON RAMPS, MAX 5%

GRADE ON SLOPES, MAX 5%
GRADE ON SLOPES, MAX 2%
SLOPE ON LANDINGS/CHANGES IN
DIRECTION, AND MAX 2% CROSS
SLOPE THROUGHOUT. CONTACT
ENGINEER IF ANY EXISTING
CONDITIONS REQUIRE
ADJUSTMENTS TO GRADES TO
MAINTAIN COMPLIANCE

514.85

∕-508.26 EX G

-509.30

TWO SETS OF 6"

HIGH BY 16" | WIDE STEPS

_508.64 EX G

TURNDOWN EDGES ALONG BOTH SIDES OF RAMPS AND LANDING REF. DETAIL SECTION THIS SHEET

MILL 1.5" OR REMOVE/REPLACE ASPHALT TO ENSURE SMOOTH
SURFACE WITH <2% CROSS SLOPE
ALONG ACCESSIBLE PATH

/——————510————————*—*

— REF ARCH. FOR RAILINGS RAMPS AND STAIRS

509.40¬

L_{510.50} EX TC

__ 5" CONC, #4 @ 12" O.C.E.W.

PROTECT EXISTING TREES AND
MINIMIZE DISTURBANCE WITHIN
TREE CANOPY/ROOT ZONE. TRIM
ANY TREE BRANCHES CONFLICTING
WITH PATHS. COORDINATE
TRIMMING WITH LANDSCAPE
ARCHITECT

ARCHITECT.

509.10

E509.28

509.20~

REPLACE CURB AND REPAIR — ASPHALT, REF. DETAIL C3.10

— DOWEL TO EXISTING FLATWORK WITH #3 @ 12"

L_{510.90} EX TC

510.50

511.10 ~ MATCH EX-\

^L511.50 EX TC