



January 9th, 2024

School District 23

Anne Sullivan Elementary School

700 N Schoenbeck Rd

Prospect Heights, IL 60070

Scope of Work: **\$25,652.00**

PPM will provide all labor, materials, and machinery to remove and replace concrete section per provided map. Proposed section of concrete will be excavated, hauled off site, and disposed of legally. PPM will install 5" of stone base and compact as required. PPM will frame and pour 5" of 4000 psi PCC concrete. Control joints will be provided as required. Light broom finish will be installed. Area will be roped off and secured from foot traffic until fully cured.

PPM will excavate earth and pour new concrete per provided map. Proposed section of earth will be excavated to a depth of 10", hauled off site, and disposed of legally. PPM will install 5" of stone base and roll to required compaction. PPM will frame and pour 5" of 4000 psi PCC concrete. Control joints will be provided as required. Light broom finish will be installed. Area will be roped off and secured from foot traffic until fully cured.

A required allowance of \$3,500.00 for fence removal is not included in this price.

All work to be performed Monday – Friday.

Any work not detailed above will incur an additional charge.

Accepted By: _____