



Prospect Heights School District 23

Landscaping proposal for MacArthur Middle School, Anne Sullivan School and Betsy Ross School

2022

MacArthur Middle School COURTYARD

Demolition

- Remove and dispose of some existing sod to create the planting beds per the landscape design.
- Remove some existing evergreens and dig out and dispose of trunks per the landscape design.

Construction Materials

13 cubic yards premium hardwood mulch.

5 cubic yards premium topsoil/compost mix.

15 flagstone steppers 18-24" irregular

600 pounds cobbles

1500 pounds Granite Boulders 36"

Plants

32 'Overdam' Feather Reed Grass	1 gallon
4 'Starlight' Baptisia	1 gallon
4 'Goldmound' Spirea	3 gallon
6 'Millenium' Allium	1 gallon
30 'Elfin' Creeping Thyme	4" pots
17 'Big Ears' Lambs Ear	1 gallon
7 'Bobo' Hydrangea	3 gallon

11 Woodland Phlox	1 gallon
15 Prairie Drop Seed	1 gallon
23 'Rozeanne' Perennial Geranium	1 gallon

Butterfly Garden:

12 Balloon Flower	1 gallon
12 'Moonshine' Yarrow	1 gallon
12 'Blue Star' Amsonia	1 gallon
3 Butterfly Bush	2 gallon
3 'Autumn Joy' Sedum	1 gallon
3 Butterfly Weed	1 gallon

Installation

- Install the soil/compost mix into the planting beds.
- Grade and rake the planting beds.
- Plant all plants per American Nursery & Landscape Association guidelines.
- Install the boulders, flagstone steppers and cobbles.
- Install the mulch into the planting beds.
- Remove all debris and thoroughly clean up the project area.

MacArthur Middle School FRONT ENTRANCE

Demolition

- Remove and dispose of some existing sod to create the planting beds per the landscape design.

Construction Materials

6 cubic yards premium hardwood mulch.
 3 cubic yards premium topsoil/compost mix.

Plants

20 'Overdam' Feather Reed Grass	1 gallon
5 'Goldmound' Spirea	3 gallon
20 Prairie Dropseed	1 gallon
1 'Tina' Crabapple	1.5" diameter trunk

25 'Rozeanne' Geranium

1 gallon

Installation

- Install the soil/compost mix into the planting beds.
- Grade and rake the planting beds.
- Plant all plants per American Nursery & Landscape Association guidelines.
- Install the mulch into the planting beds.
- Remove all debris and thoroughly clean up the project area.

Anne Sullivan School

Demolition

- Remove and dispose of some existing sod to create the planting beds per the landscape design.

Construction Materials

1 cubic yard premium topsoil/compost mix

2 cubic yards premium hardwood mulch

Plants

1 'Tina' Crabapple

1.5" diameter trunk

13 Prairie Dropseed

1 gallon

15 'Rozeanne' Geranium

1 gallon

Installation

- Install the soil/compost mix into the planting beds.
- Grade and rake the planting beds.
- Plant all plants per American Nursery & Landscape Association guidelines.
- Install the mulch into the planting beds.
- Remove all debris and thoroughly clean up the project area.

Betsy Ross School

Demolition

- Remove and dispose of some existing sod to create the planting beds per the landscape design.

Construction Materials

2 cubic yards premium topsoil/compost mix.

4.5 Cubic yards premium hardwood mulch.

Plants

7 'Dark Horse' Weigela 5 gallon

6 'Gold Flame' Spirea 3 gallon

9 'Overdam' Feather Reed Grass 1 gallon

Installation:

- Install the soil/compost mix into the planting beds.
- Grade and rake the planting beds.
- Plant all plants per American Nursery & Landscape Association guidelines.
- Install the mulch into the planting beds.
- Remove all debris and thoroughly clean up the project area.

Landscape Design

Landscape design by Andrea Rundblade for Matt Tures Landscaping & Design.

Total price of proposed 2022 project: \$22,450.00

Respectfully submitted,

Matthew J. Tures

Matt Tures Landscaping & Design, LLC