



Certified Track Builder on Staff

Proposal Quote

Date: April 13, 2018

Project:

Turnkey Running Track Project
Project # HHS15K0418
Hillsboro High School
Hillsboro, TX.

Running Track Synthetic Surface Description :

Poly Mat ISS 15K

Application of a **Poly Mat** – a cast-in-place, durable, resilient, all-weather, running track surface consisting of polyurethane bound rubber base mat.

The thickness of the rubber surface course shall be 13 mm. or 1/2-inch minimum and shall be black in color per plans and specifications. Rubber shall be specifically graded SBR with a gradation of 0.5 to 4.0 mm.

Application of a **Poly Sealer**. After curing of the base layer the pores and the edges are sealed off with a compatible two-component polyurethane. This product is applied with a rubber or metal flat squeegee or trowel, at a ratio of 1.2 kgm².

Poly Structural Spray –Application shall include the polyurethane structural spray coating applied as a single component, MDI based binder mixed with a polyurethane base color paste Black. The entire base mat shall receive two structural spray layers consisting 60% pigmented polyurethane structural spray binder and 40% EPDM colored rubber granulate graded to .5 to 1.5 mm in size. Each spray layer shall be applied uniformly at a rate of not less than 1.8 lbs per square yard on each coat, with a total of 3.6 lbs per square yard. The two layers shall be sprayed in opposite directions in order to achieve a uniform application.

5 year warranty on track surface.

Poly Mat Impermeable Structural Spray Black..... \$ 171,106.00

Track Asphalt Replacement :

- ❖ Remove and dispose of existing surface.
- ❖ Remove, mill and dispose existing 2" of asphalt at school property within 2 miles.
- ❖ Moisture condition and regrade existing base material.
- ❖ Application of tack coat SSH-1
- ❖ Provide and install 2" of new asphalt at track oval.

Construction site work..... \$ 96,482.00

CORPORATE OFFICE

Fisher Tracks, Inc.

1192 235th Street • Boone, IA 50036

800-432-3191 • 515-432-3191 • FAX 515-432-3193

www.fishertracks.com



SOUTHERN OPERATIONS

Fisher Tracks, Inc.

Mansfield, Texas

800-432-3191 x 22 • 817-473-1194 • FAX 817-539-0418

www.fishertracks.com



Certified Track Builder on Staff

Alternate # 1 :

- ❖ Construct new concrete 50'x100' high jump apron
- ❖ Remove soils, grade and prep subgrade for new 50 x 100' high jump.
- ❖ Build and construct a 6" x 12" perimeter concrete curb with 18" piers at 30 ft. OC.
- ❖ Provide, install and compact 6" of flex base material.
- ❖ Provide and install 2" of new asphalt 5,000 SF.
- ❖ Provide and install synthetic surface to match new track surface.

New 50' x 100' High Jump..... \$ 52,638.00

Not included:

- Irrigation of any kind.
- Engineer stamped drawings.
- Permits and or Taxes if applicable.
- Drainage System
- Soils stabilization if needed.
- Additional mobilizations will have a cost of \$3,500 each.

Total Proposal Quote:

Turnkey Project \$ 320,226.00**

Permeable Surface Option Deduct..... \$ 31,000.00
No sealer application (PM SS 10K)

*** Fisher Tracks, Inc. will provide a performance bond and insurance.*

Materials, equipment and installation by Fisher Tracks, Inc.

Quote does not include taxes, permit fees or allowances.

400m color coded metric striping of the 7 lane running track and field events included in quote.

Price includes application of new surface to the 7 lane running track and field events per existing layout with new high jump of 50x100 ft. included in alternate # 1

CORPORATE OFFICE

Fisher Tracks, Inc.

1192 235th Street • Boone, IA 50036

800-432-3191 • 515-432-3191 • FAX 515-432-3193

www.fishertracks.com



SOUTHERN OPERATIONS

Fisher Tracks, Inc.

Mansfield, Texas

800-432-3191 x 22 • 817-473-1194 • FAX 817-539-0418

www.fishertracks.com



Certified Track Builder on Staff

New asphalt or concrete will need to cure 28 days before application of the synthetic surface.

Asphalt and concrete will be within tolerance and requirements of the synthetic surface specifications and to the guidelines of the American Sports Builders Association (ASBA).

Fisher Tracks is an approved and authorized Buy Board and Tip-Taps Vendor allowing the project owner to award the project without a need of public bid. Approved pricing included.

If any questions, please do not hesitate to call.

Thank you for the opportunity to quote this project and we look forward to building not only a new facility for the District but also a long-lasting business relationship.

Cordially,

Victor Quiroga

Southern Operations Manager

(800) 432 – 3191 x 22

(817) 473 – 1194 x 22

(817) 539 – 0418 fax

(817) 751 – 6752 cell

vquiroga@fishertracks.com

Signature _____

Print _____

Date _____

PO# _____

CORPORATE OFFICE

Fisher Tracks, Inc.

1192 235th Street • Boone, IA 50036

800-432-3191 • 515-432-3191 • FAX 515-432-3193

www.fishertracks.com



SOUTHERN OPERATIONS

Fisher Tracks, Inc.

Mansfield, Texas

800-432-3191 x 22 • 817-473-1194 • FAX 817-539-0418

www.fishertracks.com