



September 3rd 2021

Customer: Horizon Montessori School/ Mark Garza

Site: 320 N Main St, McAllen, TX 78501

Installer: Benjamin Barrera of Trifutec via InstallerNet, Inc.

Description of work:

18 Camera Installation:

4 Cameras are to be exterior on block.

14 Cameras are to be interior on drop ceiling or sheetrock.

All cameras are to be mounted within 10' high.

There will be 8 cable runs within 100' of the DVR, 7 cable runs within 200' of the DVR, and 3 cable runs within 250' of the DVR.

Core drilling will be done to break block on subfloor.

DVR will be installed in network room. The DVR will be connected to the router with a patch cable about 5' or less. Customer will be performing port forwarding.

Cables will be concealed as much as possible through drop ceiling, or PVC where needed.

**Materials being provided by installer: 7 spools of cable, 18 channel 12v power supply, bnc connectors and power pigtails, outdoor weatherproof boxes, PVC*

Labor and Miscellaneous Material Cost: \$4,900.00

-\$75.00 discount (1/2 of site survey fee)

3-Year Installation Warranty-Included!

Total cost: \$4,825.00

***Equipment is not included in this price. Only materials included are listed above with asterisk.**

***Trenching/ trenching of cable is not included.**

Please sign below if you accept this quote and would like to schedule installation. InstallerNet must process the full amount above in order to schedule installation. Your quote is valid for 60 days.

Horizon Montessori School/ Mark Garza