

## MEMORANDUM

**TO:** Board of Education

**FROM:** Taw Lindsey  
Superintendent of Schools

**RE:** ACTION ITEM

**Date:** April 15, 2025

---

**Status:** Seeking Board approval of purchasing a heating fuel day tank for the high school boiler from Renosa Corporation in the amount of \$14,000.

- Estimated cost of work: \$10,725.00
- Contingency: \$3,275.00
- **Total approval: \$14,000.00**

**Option 1:** The Board may choose to approve the above action item as listed.

**Option 2:** The Board may choose to *not* approve the above action item as listed.

**Recommendation:** The Superintendent recommends the Board to approve the above action item as listed.

**Issue Summary:**

The high school fuel system day tank is failing, which could cause it to overfill or run dry. This has been an on-going issue for several years. Attempts have been made to repair it. This system has outlived its useful life and needs to be replaced.

QUOTE DATE: **April 6, 2025**  
**RENOSA CORPORATION**  
**PO BOX 516**  
**MONROE, OR 97456**

Contact:  
Dustin Brimhall  
(208)915-0418  
dustin@renosacorp.com

Quote To:  
**Annette Island School District**  
**Attn: Brielle Pringle**  
**(907) 886-6332**  
**4 Milton St, Metlakatla, AK**  
**99926**

ShipTo:  
**TBD**

QUOTE NUMBER

REFERENCE

TERMS

F.O.B.

CARRIER

APPROX LEAD DAYS\*

**QU89567**

**Metlakatla High School**  
**30% ARO, Bal. upon Shipment**  
**Factory - WI**

**BEST WAY**

**70** (See Below)

QTY	PROD / OPT CODE	DESCRIPTION
1	PY75ULDW	DAY TANK - STANDARD - 75 Gal., U/L Listed, Double Wall SUPPLY / RETURN FUEL SYSTEM CONTROL VOLTAGE - 120vac DRY CONTACTS THIS TANK IS FOR INDOOR USE ONLY
1	210	ALARM, COMBINATION - High / Low Fuel Level
1	211	ALARM RELAY - For Remote Signal Of Opt. #210
1	295	LEAK DETECTOR - DOUBLE WALL - Alarm & P/M Shut Down
1	323B	VENT KIT W/CAP(S) & FITTING(S) - Double Wall - 3" NPT
1	334-2	COVER NEMA-1 - Duplex Pumps and Motors
1	355A	CHECK VALVE - Pump Intake, 1/2" NPT
	RETURN	
1	360A-120	SOLENOID VALVE - N/C - 1/2" NPT, 120vac
1	399-1-05	REVERSE FLOW CONTROLS & PIPING - 1/2" Plumbing
1	401V REV	PUMP - DUCTILE IRON - 4 GPM - REVERSE FLOW- BI ROTATIONAL
1	402V	PUMP - DUCTILE IRON - 2 GPM SUPPLY BI ROTATIONAL
2	414	MOTOR - 1 PHASE - 1/3 HP, 115vac, 60 HZ
1	462DW	AUXILIARY HAND PUMP - Rotary Type (Dw) (Ship Loose)
1	544	ENCLOSURE - Control Panel, NEMA-1

*Thank you for the opportunity to submit this quote...  
We look forward to your business!*

**NET TOTAL 10,725.00**

**THIS QUOTATION IS VALID FOR 15 DAYS.**

**Payment Terms: 30% at time of Order, Balance upon Shipment.**

\* Lead Days May Vary - Approximate Delivery Date Will Be Assigned At Time Of Order

FREIGHT NOT INCLUDED

Prices Shown and Payment Shall Be In U.S Dollars