



PROPOSED CHANGE ORDERS

Cantilever Gate

ARCHITECT	Wheaton Engineering and Environmental Science, LLC Corpus Christi, Texas	CONTRACT	#2418 - Robstown ISD RECHS Stadium Paving Improvements
PCO NUMBER/REVISION	3	CREATED DATE	08/08/2024
STATUS	pending	SCHEDULE IMPACT	No Impact
		FIELD CHANGE	no

CHANGE REASON: Existing Conditions

PCO DESCRIPTION: Existing sliding gate post on the north end of the parking lot falls inside the proposed concrete of the approach. Due to the elevation of the concrete the existing sliding gate will not function properly nor cover the new widened approach. Work includes removal of gate and 1 post, Install (2) new 4" OD gate post and (1) 20' wide cantilever slide gate. Cantilever gate frame to be 2 3/8" OD Sch 40, each gate set on (2) 4" OD Sch 40 posts with upper and lower nylon rollers. Only (1) new gate post to be installed by coring concrete and setting post in concrete footing. Straighten (3) existing posts by digging around footings, straightening posts, and adding concrete, and replace 40' of 8' tall chain link fabric.

TITLE	CATEGORY	TAXABLE	QTY	PRICE	AMOUNT
Sliding Gate	general		1	\$8,185.00	\$8,185.00

Subtotal \$8,185.00

Sales Tax \$0.00

Insurance \$0.00

Labor Burden \$0.00

Bond \$0.00

OH & P \$0.00

TOTAL \$8,185.00

BY: _____

BY: _____

DATE: _____

DATE: _____

S & J FENCE CO.

361-885-0503

www.sjfenceco.com

1825 North Padre Island Drive

Corpus Christi, TX 78408

CHANGE ORDER PROPOSAL - ROBSTOWN ISD STADIUM PAVING IMPROVEMENTS

Weaver & Jacobs Constructors, Inc.

August 7, 2024

Attn: Estimating Dept.

301 Cooperative Way

Cuero, TX 77954

361-277-9300

Scope of Work: Install (2) new 4" OD gate post and (1) 20' wide cantilever slide gate. Cantilever gate frame to be 2 3/8" OD Sch 40, each gate set on (2) 4" OD Sch 40 posts with upper and lower nylon rollers. Only (1) new gate post to be installed by coring concrete and setting post in concrete footing. Straighten (3) existing posts by digging around footings, straightening posts, and adding concrete, and replace 40' of 8' tall chain link fabric.

Exclusions: Coring of concrete. No warranty of fence repair portion of work.

	<u>Each:</u>	<u>Total (1):</u>
Install 20' Wide Cantilever Slide Gate & Repair Fence:	\$8,185.00	\$8,185.00
Subtotal:	\$8,185.00	\$8,185.00

TOTAL - THIS CHANGE ORDER:

\$8,185.00

Terms: Client to issue change order.

Employer Tax I.D. #27-0587418