



**Burrage Roofing -
Chicago**

Company Representative
Jack Molskow
Phone: (630) 267-3852
jack@burrageroofing.com

Retail Proposal 9-17-25

09/17/2025
Claim Information

Antwon Blake
150 N Winfield Road
Winfield, IL 60190
(708) 595-1924

Job: Antwon Blake

Roofing Section

Material	Qty	Unit
IKO Dynasty AR (3 BD/SQ)	16.33	SQ
IKO Hip and Ridge 12 AR (36')	2.00	BD
IKO Leading Edge Plus Starter (123')	1.42	BD
TopShield TS20 Synthetic Underlayment (10 sq)	1.63	RL
IKO Stormshield Ice & Water (2 sq)	2.20	RL
TopShield Galvanized Steel Roof Edge w/ Hem - 30GA - SR Style - 5" (10')	18.70	PC
TopShield Electro Galvanized Plastic Cap Nails - Ring Shank - 1" (2000 Cnt)	0.91	BX
TopShield Electro Galvanized Steel Roofing Coil Nails - 1 1/4" (7200 Cnt)	0.91	BX
Top Shield Elastomeric Sealant - Plastic Tube (10.1 oz)	2.00	EA
TopShield Aluminum Prebent Step Flashing w/ Crimp - 4"x4"x8" (100 PC/BD)	1.00	BD
Labor		
Install Shingles	17.77	SQ
Additional Layer Shingles Removal	16.00	SQ
Steep Roof 9/12	16.00	SQ
2 Story Roof	16.00	SQ
Flashing (End Wall, Step)	10.00	LF
Haul Off Debris	1.00	EA
General		
Material Tax	1.00	EA
Delivery Charge	1.00	EA
Eagleview	1.00	EA

\$10,500.00

Siding Section

install vinyl siding on gables and short wall adjoining flat roof

	Qty	Unit
CertainTeed Restoration Classic Vinyl Siding - Select Cedar - D4	800.00	SF
CertainTeed Vinyl Standard Outside Corner Post - Woodgrain - 3/4" (10')	48.00	LF
CertainTeed Vinyl Pocket J-Channel - 3/4" (12'6")	96.00	LF
match siding		

CertainTeed Undersill Trim (12' 6")	92.00	LF
OSI Quad Sealant (10 oz)	2.00	EA
1/4" fanfold	700.00	SF
TopShield HouseWrap - 9'x100'	770.00	SF
Tyvek Housewrap Tape - 1.88"x164'	70.00	LF
Electro Galvanized Roofing Nails - 2 1/2" (30 lb)	1.00	BX
TopShield Aluminum Painted Trim Coil - .017 - 24"x50' - White/White	1.00	RL
Labor		
R+R siding	700.00	EA
Haul Off Debris	1.00	EA
remove battens prep substrate	700.00	EA
General		
Eagleview	1.00	EA
Delivery Charge	1.00	EA
		\$9,093.93
Gutters Section		
	Qty	Unit
Seamless Gutters 6"	80.00	EA
Downspouts 3x4	40.00	EA
		\$2,950.00
Siding Section		
Soffit and fascia on gables		
	Qty	Unit
ACM Painted Aluminum Trim Coil - 24"x50'	1.00	RL
ACM Norandex Aluminum Solid Soffit - T4	45.50	LF
ACM Aluminum Soffit - Center Vented - T4	19.50	LF
ACM Aluminum Universal F-Channel - 3/8" (12')	65.00	LF
ABC Stainless Steel Trim Nails - 1 1/4" (1 lb)	1.00	BX
Labor		
Soffit Labor	65.00	LF
Fascia Labor	65.00	LF
		\$2,609.41
Siding Section		
fascia on Eaves with subfascia wood replacement		
	Qty	Unit
ACM Painted Aluminum Trim Coil - 24"x50'	1.00	RL
ABC Stainless Steel Trim Nails - 1 1/4" (1 lb)	1.00	BX
Labor		
Fascia Labor	110.00	LF
replace subfascia boards	120.00	EA
		\$3,494.48
TOTAL		\$28,647.82

Note:
plywood replacement 90 per sheet billed additionally as change order where needed.
By signing this document, the customer agrees to the services and conditions outlined in this document. Please make all checks payable to Burrage Roofing. Total due in 14 days after completion of work. Overdue accounts subject to a service charge of 10% per month.

.....
.....

Company Authorized Signature

Date

Customer Signature

Date

Customer Signature

Date