

Football scoreboard & Delay of Game clocks

February 6, 2026

Quote Number 2514014

TO: Nelson Kortis Athletic Director
Groesbeck ISD

Job Site Address: 1202 N. Ellis
Groesbeck, TX 76642

RE: Groesbeck HS - Football scoreboard

Football scoreboard:

WF-FB-11832 [8ft x 32ft x 5in]

ID 2058380
\$28,637

"24"" Home, Visitor, 30"" Clock, 24"" Qtr, Down, T
(500 FT) - Cable 4 Cond 18 STD Sheild CB4 Cable
P4 - Red & White UltraBold LED Digits
Digits Time Outs Left
MSX5 Wired Scoreboard Controller
Vinyl Team Names
053 - Red (Cardinal) Cabinet Color
031 - Gray (Light) Trim Color
010 - White Caption Color
012 - Black Caption Outline
Standard 5-Year Parts Warranty
2 Year Labor Warranty
Arched Truss
012 - Black Truss Color
Non-illuminated Letters
33" x 32' Non-Illuminated Ad / Sponsor Panel
Includes Permacoat
Includes Logo on Board

1125T Delay of Game clocks :

WF-AC-1125T [4ft x 4ft x 6in]

ID 2058384
\$5,374

30" play clock (sold in pairs)
(1000 FT) - Cable 4 Cond 18 STD Sheild CB4 Cable
R4 - Red UltraBold LED Digits
Not Ordered/Not Needed (Wired) Scoreboard Controller
053 - Red (Cardinal) Cabinet Color
010 - White Trim Color
010 - White Caption Color
Standard 5-Year Parts Warranty
2 Year Labor Warranty
Includes Permacoat

Delivery & Installation :

Installation

ID 2058382
\$15,210

Physical Installation Scope:

Physical Installation Scope Inclusions:

Includes removal of existing scoreboard/signs and clocks, delivery and physical installation of new scoreboard, top truss and play clocks to existing support structures.

Includes signal/data cables, connectors and components as necessary for a complete and professional installation

Installation includes terminations of data/signal at each scoreboard component at scoreboard location

Installation includes termination of customer-supplied primary electrical power at scoreboard location

Includes installation, hook-up, test & demo of all scoring equipment

All aspects of the installation of this Scoring System to be performed by Insured and Factory-Trained Spectrum Employees & Licensed Sub-Contractors.

Physical Installation Scope Exclusions:

Does not include providing or setting new support structure, modifications to existing structure, primary electrical work, which may or may not include new conduit runs or cable pulls as needed between scorekeeper/operator and scoreboard location.

Pricing contingent upon primary electrical and/or data being provided by owner within 5' of the scoreboard and clocks final connection points upon installation.

Pricing is contingent upon the scoreboard being located outside the track and off any artificial turf surfaces. Locations on artificial turf restrict required crane truck access and will result in added costs

OPTION:

*To upgrade clocks to 1155T, **ADD**-----\$ 3,017

Timeline:

Production lead time for the entire project is currently expected to be 8-10 weeks from time of down payment and signed color layout.

TOTAL Delivered & Installed:	\$49,221
---	-----------------

Payment Terms: Net 30 days

Acceptance:

The below party hereby acknowledges and is agreeable to the Terms and Conditions contained within this quote along with the Standard Watchfire Terms and Conditions. (available upon request)

For Terms of Sale, please visit <https://tos.watchfiresigns.com/TermsOfSaleSI.pdf>

Accepted by:

Accepted Date:

Proposal valid until April 6, 2026