



NAME	COUNT	TYPE MARK	DESCRIPTION	CONTRACT STATUS	MODEL	MANUFACTURER	TYPE COMMENT
BEE SPRING RIDER W/O SOUND	1	4	SPRING RIDER TOY	CSCI	#ZZXX0567	PLAYWORLD	SEE SPEC; INTALL GUIDE
LADYBUG SPRING RIDER W/O SOUND	1	5	SPRING RIDER TOY	CSCI	#ZZXX0565	PLAYWORLD	SEE SPEC; INTALL GUIDE
HORSE SPRING RIDER W/O SOUND	2	6	SPRING RIDER TOY	CSCI	#ZZXX0563	PLAYWORLD	SEE SPEC; INTALL GUIDE
COW SPRING RIDER W/O SOUND	1	7	SPRING RIDER TOY	OSCI	#ZZXX0561	PLAYWORLD	SEE SPEC; INTALL GUIDE
CONCRETE DRUM WITH SEATING	2	8	CUSTOM MADE DRUM WITH SEATING SEE DTL.	CSCI	CUSTOM MADE		SEE DTL.
PLAYGROUND SIGNAGE	5	9	CUSTOM "POSITIVE SAYING" SIGNS	CSCI	#ZZXX0155	PLAYWORLD	SEE SPEC; INTALL GUIDE
BASKETBALL HOOP	2	10	8' FIXED BASKETBALL HOOP	CSCI	SPORT COURT SLAM SYSTEM 8' FIXED BASKETBALL SYSTEM	SPORT COURT	SEE SPEC
UNITY HOOPLA SWING	1	1	SWING TOY	CSCI	#ZZXX0199	PLAYWORLD	SEE DTL.
NE-1012 MINI NET EFFECT	1	2	CLIMBING NET TOY	CSCI	NE - 1012	PLAYCRAFT SYSTEMS	SEE SPEC; INTALL GUIDE
PLAYCUBE 7.0	1	3	INTERLOCKING CUBES	CSCI	PLAYCUBES-7.0	PLAYWORLD	SEE SPEC; INTALL GUIDE
PLAYCUBE 4.0	1	11	INTERLOCKING CUBES	CSCI	PLAYCUBES-4.0	PLAYWORLD	SEE SPEC; INTALL GUIDE

PLAYGROUND EQUIPMENT SCHEDULE
 1/4" = 1'-0"

SURFACE NAME	SURFACE COLOR/ HATCH	TOTAL AREA IN SQ. FT.
BORGERT 4HS HOLLAND STONE PAVERS 60MM TRACK SYSTEM- CHARCOAL	[Hatch]	7,100 SQ. FT.
BORGERT 4FP FILTRAPAVE 60MM PERMEABLE PAVER - ASHLAR AUTUMN BLEND	[Hatch]	3,400 SQ. FT.
NEW CONCRETE SURFACE	[Hatch]	9,000 SQ. FT.
1/4" MINUS PEA GRAVEL SURFACE	[Hatch]	6944 SQ. FT.
NEW GROWING MEDIUM (SOD)	[Hatch]	20,000 SQ. FT.
8' BLACK CHAIN LINK FENCE	[Hatch]	1,415 FEET

NOTE:
 TRACK SYSTEM AND PERMEABLE PAVER SURFACES MUST COMPLY WITH ADA REQUIREMENTS OF SLOPE <= 5%

UTILITY LOCATION
 THE LOCATIONS OF UNDERGROUND UTILITIES REPRESENTED ON THIS DRAWING HAVE BEEN DETERMINED FROM A FIELD SURVEY AND FROM RECORDS OBTAINED FROM THE VARIOUS UTILITY COMPANIES. THE NUMBER AND LOCATION OF ALL UNDERGROUND UTILITIES SHOWN ARE FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR SHALL MAKE HIS OWN INVESTIGATION TO OBTAIN THE EXACT INFORMATION NECESSARY TO PROTECT OR ACCESS ALL UNDERGROUND UTILITIES. THE CONTRACTOR SHALL CALL THE FOLLOWING NUMBER FOR ASSISTANCE: 406-755-8344 OR 800-551-8344.
"CALL BEFORE YOU DIG"

NOTE:
 ALTHOUGH NOT IDENTIFIED ON THE CONSTRUCTION DRAWINGS, SHALLOW BURIED TELEPHONE AND FIBER OPTIC CABLE EXISTS THROUGHOUT THE SITE. CONTRACTORS SHALL LOCATE ALL BURIED COMMUNICATION CABLING WITH THE ASSISTANCE OF THE OWNER'S REPRESENTATIVE AND THE UTILITY COMPANY PRIOR TO CONSTRUCTION. ALL DAMAGED COMMUNICATION INFRASTRUCTURE WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO SCHEDULE AND PAY FOR REPAIRS.

GAS & ELECTRICAL METER TO REMAIN IN THE SAME LOCATION GROUND SURFACE TO REMAIN AS IS;
REMOVE EXISTING FENCE - REPLACE WITH BLACK CHAIN LINK FENCE

ARCHITECTURAL SITE PLAN - PHASE 2
 1" = 20'-0"

Revision Schedule		
No.	Revision	Date

Submittal Schedule		
No.	Submittal	Date

THIS DRAWING IS THE PROPERTY OF THE ARCHITECT. IT HAS BEEN PREPARED SPECIFICALLY FOR THIS SITE AND IS NOT TO BE USED FOR ANY OTHER PURPOSES. LOCATION OR OWNER WITHOUT WRITTEN CONSENT OF THE ARCHITECT.

© 2015 LHEUREUX PAGE WERNER, PC

DRAWN BY:	MA-C
CHECKED BY:	TMP
DATE:	05/31/16
PROJECT NUMBER:	15-050
SHEET NUMBER:	SP1.1

