

## Quote: Q-0032154

**Opportunity Name:** Nevis, MN - Nevis School Bus Garage -  
Compliance Repairs  
November 20, 2024



**Prepared For:**  
Nevis School Bus Garage  
106 Woodland Dr N  
Nevis, MN 56467

**Prepared By:** Aaron Cammack  
*Install Project Mgr*  
aaron.cammack@westmor-ind.com  
763-434-2725

**For Work At:**  
Nevis School Bus Garage  
106 Woodland Dr N  
Nevis, MN 56467

**Contact:**  
Dustin Wroolie  
218-616-1500  
dwroolie@nevis308.org

**On Behalf of:** Jesse Schmidgall  
*Territory Manager*  
jesse.schmidgall@westmor-ind.com  
+1 7152145548

Dustin,

Westmor Industries is thankful for the opportunity to present this quote to you.

RE: Failed items noted during your recent compliance inspection.

### Scope of Work:

- Sawcut, hammer and remove the concrete (approx. 4'x4') areas around the spill bucket, ball float and over the product line
- Excavate to the top of the tank at the ball float and spill bucket
- Remove the spill bucket and install (1) new five gallon grade level spill bucket including riser pipe, internal nipple, cap, adapter and drop tube with overfill valve set at 95% tank capacity
- Hydro test the spill bucket and function test the drop tube
- Excavate to the product line and add (1) 32lbs magnesium anode
- Saturate the anode for immediate polarization of the steel line and perform a CP test
- Cut the vent line where it comes out of the tank and remove the ball float
- Thread the cut section of pipe or taper the pipe and install a 2" bell x female pipe thread coupling in case it is fiberglass and reconnect it to the tank with new pipe and fittings from the first fitting out of the hex bushing to the newly threaded pipe section
- Backfill excavated areas, dowel into existing cement and pour back concrete to grade
- Barricade the area with disposable material you can get rid of after 7 days for the concrete to cure without traffic on it
- Supply you with an emergency stop switch for your electrician to install (minimum 20' maximum 100' from the fueling location)
- Provide you with testing documentation

Concrete disposal is not included in this price. We will stockpile the rubble on site in a location of your choosing or we will load your hauler if prior arrangements are made with us.

De-watering is not expected but the water table must be below the tank top for this work to be completed. If required it would be handled on a T&M basis.

Electrical is not included in this quote and will be your responsibility.

Taxes included.

Qty	Part	Description
1.00	Compliance Repair Configurator	
1.00	5 Gallon SW GL Spill Bucket w/o Drain	5 Gallon SW GL Spill Bucket w/o Drain
1.00	4" X 12' Drop Tube w/ Overfill Valve	4" X 12' Drop Tube w/ Overfill Valve
1.00	E-Stop Kit Outside	
1.00	58-000953	Service Charge for Anode to Tank Pipe Connection, i.e., cad welds, certified install.
1.00	Mobilization For Small Concrete Removals	Mobilization For Small Concrete Removals
60.00	Cost Per Sq Ft to Remove Concrete - Kit	Kit Cost Per Sq Ft to Remove Concrete, Labor and Concrete
1.00	Mobilization for Small	Mobilization for Small Concrete Pours



60.00	Concrete Pours Cost Per Sq Ft to Replace Concrete - Kit	Kit Cost Per Sq Ft to Replace Concrete, Labor and Concrete
24.00	14-702058	REBAR, #4, 1/2"x12"
1.00	58-001051	Rental of Concrete Saw - Per Day
1.00	58-001053	Hydraulic Hammer Rental (skid steer attachment)
1.00	58-001049	Skid Steer Rental
2.00	08-02546	PIPE, ELBOW, 0200, 90, BLK, THRD,
4.00	08-700414	NIPPLE 2"x4" STD BLK ERW
1.00	08-702038	UNION 2" DIELECTRIC
1.00	08-700368	COUPLING 2" BLK API THRD
1.00	63-701098	ADAPTOR 2" U.L. RED THREAD B
1.00	63-706096	ADHESIVE-KIT, SMITH, 6OZ

**Total Investment:** **\$24,951.39**  
*Does not include selected options*

BY YOUR EXECUTION OF THIS QUOTE, OR ACCEPTANCE OF THE GOODS SET FORTH HEREON, PURCHASER ACKNOWLEDGES AND AGREES THAT IT HAS HAD THE OPPORTUNITY TO REVIEW THOSE TERMS AND CONDITIONS OF WESTMOR INDUSTRIES, LLC ATTACHED BELOW. A DIGITAL COPY OF THE TERMS ARE AVAILABLE ONLINE AT WESTMOR-IND.COM/TERMS. THE PARTIES INTEND TO BE BOUND BY SUCH TERMS AND CONDITIONS, WHICH ARE HEREBY INCORPORATED BY REFERENCE.

**Payment Terms:** Thirty percent (30%) down on Westmor-Supplied items. Progressive billing once equipment is on job site or special ordered equipment is in Westmor Industries inventory. Balance due upon completion of project. There will be a thirty percent (30%) restocking charge if parts have been ordered and the job is cancelled.

Please note that this contract must be signed and the deposit paid before any equipment is manufactured or ordered. We will be able to schedule your project after these conditions have been met.

*While Westmor is doing all we can to maintain quoted prices, in the current environment Westmor has been experiencing vendor price increases without prior notice as well as unexpected increases in freight costs. Again, Westmor is doing all we can to mitigate the effects of these third-party price changes on our customers, but in some instances these effects are beyond Westmor's control.*

*For these reasons, and only in cases of documented third-party vendor price increases (including surcharges, adjustments, recovery charges, freight charges, and shipping and handling fees), Westmor reserves the right: (a) prior to acceptance of this proposal, to increase the quoted price by the amount of the third-party vendor price increase by written notice to the customer; and (b) after acceptance of this or any subsequent or modified proposal, to pass along any third-party vendor price increase in the invoiced amount to the customer.*


*In both cases (a) and (b) above, documentation of the third-party vendor price increase will be provided either with the new quote or invoice, or upon written request from the customer.*

**\*Other than as provided above under "Third-Party Price Increases", this proposal is valid for 10 days from the date of this proposal.**

**Nevis School Bus Garage**

**Westmor Industries, LLC**

Signature: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_  
Date: \_\_\_\_\_  
PO#: \_\_\_\_\_

Signature:   
Name: Jesse Schmidgall  
Title: Territory Manager  
Date: November 20, 2024