Gonzales Architecture
Architect + Planner + Consultant

Joseph E. Gonzales, AIA
4514 Buckmoor Street
San Antonio, Texas 78217
(210) 218.7522

February 1. 2026

Change Order Request at High School Vestibule Project

The Brackett ISD has made a pause on the Vestibule Project at the High School. They are relocating the school office to the first classroom off the on the street entrance to the building.. I am providing a floor plans showing their intentions.

Scope of work to be removed from the contract.

Item 1, The removal of the two hollow metal frames, doors and hard surface walls. tempered glaas, security film and bonding on these items.

Item 2. These items are marked on the attached drawings.

Item 3. The remaining items are still in place of the original bid contact. Bonding of all existing windows and doors that having the film previously installed.

Scope of new work for the new vestibule and school office location at High school

Item 1. One new vestibule hollow metal frame, door, tempered glass and security film and bonding.

Item 2. A pass-through window cut into existing cmu wall.

Item 3. A new office conference room in classroom with solid core door and hollow metal frame, wa;;s of 5/8" gyspeum wall board on 2 x4 wood frame 24" om center , taped and floated with a smooth texture painted wall match existing color.

Item 4. New office counter cabinet with plastic laminate top. Drawers with locks and open shelving under the cabinet.

Item 5. Remove existing acoustic ceiling and replace with 2' x 2' gypsum ceiling tile painted co;or as selected.

School items to be performed by Maintenance and Internet Department

Items from original contract camera locations, electronic locking devices.