



December 8, 2016

Erasm Rodriguez – Assistant Superintendent
Beeville Independent School District
Phone: 361.549.0092
Email: erodriguez@beevilleisd.net

RE: **Running Track Surfacing**
Beeville High School

Mr. Rodriguez,

As requested, **Hellas Construction, Inc.** has visited the site and made an evaluation based on the Owner's requirements and recommendations, and is providing the scope of work below.

Track Surfacing Removal and Resurface

1. **Hellas** will remove and dispose of $\pm 3,519$ SF of existing track surfacing system on the existing high jump pad and event runways (two). **Hellas** will inspect existing track surfacing with Owner and identify any surface cracks prior to commencement of surfacing operations
2. Provide and install $\pm 3,519$ SF of **epiQ Tracks™ V300** (red) polyurethane structural spray surfacing system on existing high jump pad and event runways (*there are no track surface or asphalt pavement repair included with the price provided*).
3. Repair seam in running track oval between the 25 and 15 yard line of the west side.
4. Stripe per existing markings. *No logos, lettering, or distance tick marks are included in proposal amount.*
5. Clean up as necessary.

Proposal Amount:

\$39,742.00

12710 Research Boulevard
Suite 240
Austin, Texas 78759



Phone (512) 250-2910

Fax (512) 250-1960

info@hellasconstruction.com

WWW.HELLASCONSTRUCTION.COM



Owner Contingency

1. Provide \$5,000.00 Owner Contingency for asphalt pavement repairs at existing track oval.

Contingency Add: _____ **\$5,000.00**

No price for track surface repair is provided. Hellas will inspect the existing track surface with the Owner/Owner's representative. Hellas can make no assumptions and assumes no liability as to the fitness and usability of the track surface during repair operations.

Exclusions (but not limited to):

1. Any item of work not explicitly listed above.
2. Engineering.
3. Any asphalt pavement repair.
4. Any landscaping or grassing of the immediate surrounding areas.
5. Irrigation installation or repair.
6. Any Allowances or Contingencies.
7. Fencing or fence repair.
8. Permits.
9. Taxes.
10. Bonds.
11. Owner shall provide ingress/egress for ALL personnel, equipment and materials; typical construction traffic shall be expected for the duration of this contract. Contractor NOT responsible for damage due to typical construction traffic ingress/egress to the construction site.

Notwithstanding anything to the contrary in any of the Contract documents, under no circumstances shall the Performance bonds, maintenance bonds or the obligations of the Surety be liable for any warranty obligations that exceed 1 year from the date of substantial completion as defined in the Contract documents.

Please contact this office should you have any questions regarding this quotation. **Hellas Construction, Inc.** looks forward to the award of this project, and is eager to work with you.

Sincerely,

Lisa Thoma
Estimator

