PROPOSAL
QUALITY FENCE COMPANY

Quincy Says...
...NO JOB TOO LARGE
...NO JOB TOO SMALL

CCB # 8936

2077 NE Diamond Lake Blvd
Roseburg, OR 97470

(541) 673-8055
Fax: (541) 672-8892

Find us also at:
180 McDonald Lane
Grants Pass, OR 97527

114 W. Pine Street
Central Point, OR 97502

PROPOSAL SUBMITTED TO	PHONE	DATE
Winston Dillard School District	541-671-6331	February 11, 2026
STREET: 620 Elwood St	JOB NAME: Winston Middle School	
CITY, STATE AND ZIP CODE: Winston, OR 97496	JOB LOCATION: 330 SE Thompson	
ATTENTION: "Guy" Shelby Beard	EMAIL: beards@wdsd.org	CELL PHONE:

We hereby submit specifications and estimate for:

#1: Install approximately 450 linear feet of 6' high heavy commercial grade galvanized chain link fencing along the East Property Line.

Note: Estimate includes resetting existing 2 3/8 corner post inside property line (to be marked by surveyor)

#1 Total: $12,477.00

Specs: End/ Corner Posts: 2-3/8" schedule 40 galvanized steel pipe.
Line Posts: 2-3/8" galvanized steel pipe
All posts set in concrete
Top Rail: 1-5/8" galvanized steel pipe
Mesh: 9 gauge, 2" diamond, galvanized chain link fabric
Bottom Tension Wire: 7 gauge galvanized coil spring

#2: Install New 42" wide x 6' high pedestrian gate with von Duprin panic bar & LCN HD hydraulic closer. Also to include new gate post and header above opening.

#2 Total: $6,645.00

Specs: (1) 3'x6' walk gate
(1) set of elite hinges
(1) Von Duprin closer w/ cylinder assembly
(1) LCN CLOSER
(1) 2-7/8 X 10'6" wt-40 post
(1) 2"x4"x36" header

**** DUE TO CURRENT MARKET INFLATION, PROPOSAL IS SUBJECT TO REVIEW AFTER 14 DAYS FROM PROPOSAL DATE ****

We Propose hereby to furnish materials and labor--complete in accordance with above specifications, for the sum of:

Please Refer to Above Listed Estimate Options

Payment to be made as follows:

DEPOSIT 1/2 DOWN, BALANCE ON COMPLETION

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation insurance. This proposal is also subject to all terms and conditions contained on the reverse side hereof.

Authorized Signature: *Greg Rietmann*

KM

Note: This proposal may be withdrawn if not accepted within 14 days

Acceptance of Proposal--All prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above. I have read the entire contract and agree to its content. conten content.

Note: Quality Fence Co. not responsible for any damage to anything in or below the ground or concrete. This includes private water line, electrical line, sprinkler systems, etc. Your signature indicates that you fully understand the limits of Quality Fence Co.

Signature _____

Signature _____

Date of acceptance: _____