

Prime Maintenance & Construction

103 Commerce Road
Alice, TX 78332
(Cell) 361.701.8809



PROPOSAL

Beeville High School Gymnasium 2

Attn:	Roy Galvan
Date:	11/7/2016
Section:	Painting
Terms:	Draws

Bid Amount	\$44,965.42
Total	\$ 44,965.42

DESCRIPTION

No Sales Tax

We hereby propose to furnish all the labor, equipment, general liability, and supervision for the completion of: Specified Work for Beeville Independent School District ~ A.C. Jones High School located 1902 North Adams Street, Beeville, Texas 78102.

SCOPE OF WORK: Gymnasium 2 - Marion B. Horton Gym

Areas of work include: Entry, Boys and Girls Restroom, Concession, 2 Coaches Office, 2 Equipment Rooms and Gym (paint areas that are previously painted)

- Cover and protect floors, bleachers, lighting, etc from paint work
- PMC will provide the necessary manlifts and scaffolding necessary to complete work. Also provide plywood to protect floors as needed
- Surface Prep and Prime Top Section (Tectum Panel and up) Gym Walls with S/W Pro Industrial Multi-Surface Primer
- Finish Paint Top Section Gym Walls with S/W ProMar 200 Zero VOC Latex Eg-She!
- Surface Prep and Prime Lower Section (below Tectum Panels) Gym Walls with S/W Pro Industrial Pro-Cryl Primer
- Finish Paint Lower High Traffic Section of Gym Walls with S/W Pro Industrial Pre-Catalyzed Epoxy
- Surface Prep and Prime Gym Ceiling "S" Purlins/Insulation/Cables with S/W Pro Industrial Multi-Surface Primer
- Finish Paint Ceiling "S" Purlins/Insulation/Cables a Solid Color with S/W ProMar 200 Latex Zero VOC Latex Flat
- Surface Prep and Prime Gym Main Structural Support Beams with S/W Pro Industrial ProBlock Primer
- Finish Paint Gym Main Structural Support Beams "Trojan Orange" with S/W Pro Industrial Urethane Alkyd Enamel
- Cosmetic Patch, Prime and Paint Gypsum Board Columns
- Surface Prep and Prime Doors and Trim with S/W ProBlock Oil-Base Primer; including Exterior Door Units
- Finish Doors and Trim with S/W Pro Industrial Urethane Alkyd Enamel; including Exterior Door Units
- Paint Basket Ball Supports and Goals "Black" same as existing
- Surface Prep, Prime and Paint previously painted surfaces at (2) Equipment Rooms Ceilings & Walls
- Surface Prep, Prime and Paint Railing above Equipment Rooms
- Paint Colors to be a 2-tone color scheme which includes School Color for Trim Work

* **Note:** Work to be scheduled and coordinated with school administration which may include nights and weekends.

EXCLUSIONS:

- No Painting of Floors
- No Lockers

**** If bond is required, please add 5% for bond fee.****

The above prices and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature →

Date: →

All material are guaranteed to be as specified, and the above work to be performed in a substantial workmanlike manner. Any alterations or deviations from the above specifications involving extra costs will become an extra charge over and above the estimate. This proposal is Valid for 30 days from day submitted.

Respectfully Submitted: _____
Christina Celeste Cruz - Owner

Prime Maintenance & Construction

103 Commerce Road
Alice, TX 78332
(Cell) 361.701.8809



PROPOSAL		Beeville High School Athletic Dept. & Field House	
Attn:	Roy Galvan	Bid Amount	\$39,615.78
Date:	11/7/2016		
Section:	Painting		
Terms:	Draws		
		Total	\$ 39,615.78
No Sales Tax			

DESCRIPTION

We hereby propose to furnish all the labor, equipment, general liability, and supervision for the completion of: Specified Work for Beeville Independent School District ~ A.C. Jones High School located 1902 North Adams Street, Beeville, Texas 78102.

SCOPE OF WORK: Athletic Dept. & Field House

Areas of work include: Boys Locker Rooms, Girls Locker Rooms, Shower Areas, Corridors, Training Area, Coaches Offices, Directors Offices, Storages, Restrooms, Laundry & Equipment Rooms (paint areas that are previously painted)

- Cover and protect floors, furniture, fixtures, etc from paint work
- Surface Prep and Prime CMU Walls with S/W Pro Industrial Multi-Surface Primer
- Finish Paint CMU Walls with S/W ProMar 200 Zero VOC Latex Eg-Shel; including Accent Bands
- Surface Prep and Prime Doors and Trim with S/W ProBlock Oil-Base Primer; including Exterior Door Units
- Finish Doors and Trim with S/W Pro Industrial Urethane Alkyd Enamel; including Exterior Door Units
- Surface Prep, Prime and Paint previously painted Ceilings
- At designated areas surface prep and paint Concrete Floors with S/W Treadplex Paint; PMC will not warranty adhesion to previously painted concrete floors due to unknown prior coats of paint
- Surface Prep and Prime CMU Walls at Old Field House with S/W Pro Industrial Multi-Surface Primer
- Finish Paint CMU Walls at Old Field House with S/W ProMar 200 Zero VOC Latex Eg-Shel
- Boys and Girls Locker Room and Trainers Area will have Paint Shield Microbicidal Paint

*** Note:** Work to be scheduled and coordinated with school administration which may include nights and weekends.

EXCLUSIONS:

- No Painting of Floors except where noted
 - No Lockers
 - No Painting of Weight Room
- ** If bond is required, please add 5% for bond fee.****

The above prices and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature →

Date: →

All material are guaranteed to be as specified, and the above work to be performed in a substantial workmanlike manner. Any alterations or deviations from the above specifications involving extra costs will become an extra charge over and above the estimate. This proposal is Valid for 30 days from day submitted.

Respectfully Submitted: _____
Christina Celeste Cruz - Owner

Prime Maintenance & Construction

103 Commerce Road
Alice, TX 78332
(Cell) 361.701.8809



PROPOSAL		Beeville High School Auditorium	
Attn:	Roy Galvan	Bid Amount	\$29,854.25
Date:	11/7/2016		
Section:	Painting		
Terms:	Draws		
		Total	\$ 29,854.25

DESCRIPTION No Sales Tax

We hereby propose to furnish all the labor, equipment, general liability, and supervision for the completion of: Specified Work for Beeville Independent School District ~ A.C. Jones High School located 1902 North Adams Street, Beeville, Texas 78102.

SCOPE OF WORK: Auditorium

Areas of work include: Entry, Boys and Girls Restroom, and Main Auditorium (paint areas that are previously painted)

- Cover and protect floor, seating, stage, lighting, etc from paint work
- PMC will provide the necessary manlifts and scaffolding necessary to complete work
- Remove and Demo water damaged plywood / pegboard wall panels as needed - approx. 10 sheets
- Supply and Install new plywood / pegboard wall panels where they were demo
- Surface Prep and Prime Plywood and Peg Board panel walls with S/W ProBlock Primer
- Finish Paint Plywood and Peg Board walls with S/W ProMar 200 Zero VOC Latex Eg-Shel
- Surface Prep and Prime Wood Ceilings with S/W ProBlock Primer
- Finish Paint Wood Ceilings with S/W ProMar 200 Latex Zero VOC Latex Flat
- Surface Prep and Prime Doors and Trim with S/W ProBlock Oil-Base Primer
- Finish Doors and Trim with S/W Pro Industrial Urethane Alkyd Enamel
- Paint Colors to be a 2-tone color scheme which includes School Color for Trim Work

* **Note:** Work to be scheduled and coordinated with school administration which may include nights and weekends.

EXCLUSIONS:

- No Painting of Floors ** If bond is required, please add 5% for bond fee.**
- No Removing of Seating.

The above prices and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature →

Date: →

All material are guaranteed to be as specified, and the above work to be performed in a substantial workmanlike manner. Any alterations or deviations from the above specifications involving extra costs will become an extra charge over and above the estimate. This proposal is Valid for 30 days from day submitted.

Respectfully Submitted: _____
Christina Celeste Cruz - Owner

Prime Maintenance & Construction

103 Commerce Road
Alice, TX 78332
(Cell) 361.701.8809



PROPOSAL

Hampton-Moreno-Dugat Early Childhood Center

Attn:	Erasmo
Date:	12/5/2016
Section:	Canopy / Walkway
Terms:	Draws

Bid Amount	\$13,827.50
Total	\$ 13,827.50

DESCRIPTION

No Sales Tax

We hereby propose to furnish all the labor, equipment, general liability, and supervision for the completion of: Specified Work for Beeville Independent School District ~ Hampton-Moreno-Dugat Early Childhood Center located 2000 South Mussett, Beeville, Texas 78102.

SCOPE OF WORK: Southside Bus Stop Pick-Up Canopy / Walkway

Construct a Canopy Walkway and Bus Stop Canopy

- Form a 8 ft. wide x 50 L/F concrete walkway to Bus Stop
- Provide 12in. Concrete piers to set in steel support posts with anchor plates
- Pour 3000 psi concrete and Set in anchor plates
- Weld and Frame a 50 L/F Overhead Canopy at Concrete Walkway with 8in. C-Channel; Canopy will be approx. 8 ft. height
- Supply and Install R-Panels at Walkway, color to be selected by owner
- Supply and Install Steel support posts with anchor plates for a 12 ft. x 40 ft. Bus Stop Canopy
- Weld and Frame a 12 ft x 40 ft Overhead Single Slope Canopy at Concrete Bus Stop with 8" C-Channel; canopy will be 9-10 ft. height slant
- Supply and Install R-Panels at Bus Stop
- Supply and Install Gutter w/Boot Downspouts a rear of Bus Stop Canopy
- Clean and dispose of construction debris

Option: Paint Canopy Steel Structure

\$2,595.00

- Surface Prep Walkway and Bus Stop Canopies to receive paint
- Prime with S/W Kem Kromik Universal Primer with Rust Inhibitor
- Finish with (2) coats of S/W Pro Industrial Acrylic Paint

**** If bond is required, please add 5% for bond fee.****

The above prices and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature →

Date: →

All material are guaranteed to be as specified, and the above work to be performed in a substantial workmanlike manner. Any alterations or deviations from the above specifications involving extra costs will become an extra charge over and above the estimate. This proposal is Valid for 30 days from day submitted.

Respectfully Submitted: _____

Christina Celeste Cruz - Owner