

Roach Plumbing & Heating Co., Inc.
5535 Greenwood Road
Shreveport, Louisiana 71109

James (Jim) B. Roach
Louis G. Roach
Owners

Phone : (318) 631-4533
Fax: (318) 631-9995

February 26, 2015

Waskom ISD

Re: Waskom Middle School Cafeteria
Water Heater Replacement

We propose to disconnect and replace one Commercial 100 Gallon Gas 199,000 BTU Cyclone Water Heater and install a new 100 Gallon Gas 199,000 BTU Water Heater in the Cafeteria Storage Room. The current water heater was installed in 2007 and is over seven years old. We have repaired the water heater several times during the last two years. This water heater in my opinion needs to be replaced during the summer months to prevent a shut down of the Cafeteria during school hours.

For an estimated cost of Ten Thousand Three Hundred Fifty – Four Dollars (\$ 10,354.00). This includes Labor and Materials.

We hope this bid is acceptable and look forward to working for you in a safe and professional manner.

Sincerely,



Louis Roach
Roach Plumbing Co., Inc.

Roach Plumbing & Heating Co., Inc.

5535 Greenwood Road
Shreveport, Louisiana 71109

James (Jim) B. Roach
Louis G. Roach
Owners

Phone : (318) 631-4533
Fax: (318) 631-9995

February 26, 2015

Waskom ISD

Re: Waskom Middle School
Main Water Service Replacement

There is a 2" galvanized water main from the water gate valve located in the front of the school by the gas meter under the asphalt driveway (Bus Drop Off) to the front side of the Gym that is in need of replacement. This line has been repaired numerous times due to the age of the pipe.


We propose to dig up the galvanized water service at the cut off valve. Saw cut 280' of asphalt driveway to the front of the Gym. Use a track hoe to dig up the water line to the edge of the Gym. Locate the copper stub out at the Gym. Saw cut the sidewalk if necessary and replace the galvanized line if not stubbed out with copper. Install new 2" Sch. 40 PVC water service. Install cut off valves with valve boxes where needed. Backfill the ditches with clean dirt and compact. Install new asphalt on the saw cut work area. Resod with grass at the sidewalk area. Haul off the asphalt and old dirt from the job site.

For an estimated cost of Twenty Thousand Five Hundred Eighty Dollars (\$ 20,580.00). This includes all Labor and Materials.

If any unforeseen work is found during the repairs, we will stop and the School Administration will be notified before the additional repairs are made.

We hope this bid is acceptable and look forward to working for you in a safe and professional manner.

Sincerely,



Louis Roach
Roach Plumbing Co., Inc.