



Z3 Solutions
 1350 E Touhy Avenue, Suite 120W
 Des Plaines, Illinois 60018
 P: (847) 730-3945
 F: (847) 724-1249

Project: 17161 - 17161 - Lincoln Hall Phase 3
 6855 N. Crawford Ave.
 Lincolnwood, Illinois 60712
 P: 847-730-3945

CHANGE EVENT #002 - Stage Curtain Modifications

Origin:
Date Created: 4/18/2018
Status: Pending
Type: Design Modification
Description: Modification of stage batton hoist system to a system more in line with an auditorium for a Middle School vs a high school
Attachments: Stage Equipment.pdf

Created By: Nicholas Zouras
Scope: In Scope
Change Reason: Design Development

CHANGE EVENT LINE ITEMS

Cost Code	Cost Type	Vendor / Contract	Prime PCO	ROM	RFQ	Commit.	Budget Mod.
0610-06100 - Rough Carpentry	Other	Ostrander Construction, Inc. SC-005		\$(23,635.00)			
Description: Stage Curtain Modifications							
9400-94000 - General Liability Insurance	Other			\$(236.35)			
Description: 1% GL Insurance							
9500-95000 - Fee	Other			\$(835.49)			
Description: 3.5% Fee							
Grand Totals			\$0.00	\$(24,706.84)	\$0.00	\$0.00	\$0.00

2001 BUTTERFIELD RD SUITE1120
DOWNERS GROVE, IL 60515
630 971 2211
STEVE@OSTRANDER.BIZ

**Ostrander
Construction, Inc.**

Extra Request

To: Mr. Nick Zouras
From: STEVE KOSS
CC:
Date: 5/10/18
Re: Stage Equipment and Curtain Changes Lincoln Hall School

THE FOLLOWING EXTRA WORK HAS BEEN PRICED FOR THE ABOVE REF. PROJECT:

Revise stage equipment to eliminate motorized light batten system to fixed system. CREDIT \$(26,550.00)

Revise stage curtain system per April 30, 2018 meeting with Arcon. ADD \$2915.00

OH Fee \$00.00

TOTAL THIS CHANGE CREDIT (\$23,635.00)

Please call me with any questions.

Sincerely,

Steven G Koss

Approved by _____



GRAND STAGE

Chicago Spotlight art drapery studios

Rentals, Events & Production

Stage Rigging & Drapery

Lincoln Hall Middle School
Phase One Additions and Remodeling
Lincolnwood, Illinois

May 8, 2018

Page 1 of 1

Grand Stage drapery and rigging equipment, consisting of:

set# - description (distance from plasterline)

- #1 - Front curtain; 25 oz. IFR Charisma velour fabric, inherently flame retardant, 40 ft. wide pair x 14 ft. high, with 50% fullness sewn into flat box pleats, 12" onstage turnbacks, dust ruffle, chain weighted bottom, and H & H Specialties #401S heavy duty curtain track complete with all necessary accessories for manual, bi-parting operation, and 3/16" proof coil chain for dead hung installation (1 ft. 0 in.)
- #2 - Grand border; 25 oz. IFR Charisma velour fabric, inherently flame retardant, 34 ft. wide x 5 ft. high, with 50% fullness sewn into flat box pleats, grommet and tie top, sewn flat, 32 ft. wide x 4 ft. 6 in. high, and 1.5" schedule 40 pipe batten complete with internal expanding splice and 3/16" proof coil chain for dead hung installation (2 ft. 0 in.)
- #3 - First electric (provided and installed by electrical contractor - 3 ft. 4 in.)
- #4 - First pair legs; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 12 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and 2 sections of H & H Specialties #401W heavy duty curtain track complete with all necessary accessories for walk draw operation, and 3/16" proof coil chain for dead hung installation (2 ft. 0 in. to 7 ft. 6 in.)
- #5 - First border; ; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 34 ft. wide pair x 5 ft. high, with 50% fullness sewn into flat box pleats, and 1.5" schedule 40 pipe batten complete with internal expanding splice and 3/16" proof coil chain for dead hung installation (8 ft. 0 in.)
- #6 - Second pair legs; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 12 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and 2 sections of H & H Specialties #401W heavy duty curtain track complete with all necessary accessories for walk draw operation, and 3/16" proof coil chain for dead hung installation (8 ft. 6 in. to 14 ft. 0 in.)
- #7 - Second electric (provided and installed by electrical contractor - 9 ft. 6 in.)
- #8 - Rear traveler; 20 oz. black IFR Crescent velour fabric, inherently flame retardant, 34 ft. wide pair x 15 ft. high, with 50% fullness sewn into flat box pleats, chain weighted bottom, and and H & H Specialties #401S heavy duty curtain track complete with all necessary accessories for manual, bi-parting operation, and 3/16" proof coil chain for dead hung installation (14 ft. 6 in.)
- #9 - Cyclorama electric (provided and installed by electrical contractor - 16 ft. 0 in.)
- #10 - Cyclorama; 108" white muslin fabric, treated for flame retardancy, 36 ft. wide x 16 ft. high, sewn flat, with combination pipe pocket and chain weighted bottom and H & H Specialties #401W heavy duty curtain track complete with all necessary accessories for walk draw operation, and 3/16" proof coil chain for dead hung installation (locate at 8" from upstage wall – extend stage left track to side wall for stacking)