



Proposal

Date	Proposal No.
7/31/2014	43478

Name/Address
San Diego ISD Dr. Sam Bueno 609 Labbe Ave. San Diego, TX 78384

Ship To
San Diego ISD Dr. Sam Bueno 609 Labbe Ave. San Diego, TX 78384

Description	Qty	Cost	Total
Removing Existing Running Track Surface and Applying a New Mat and Spray Surface Scope of Work: 1. Remove surface of entire track and infield events, clean base of all dirt and debris. 2. Edge track and events where needed. 3. Prime all asphalt and/or concrete 4. Apply a base layer of 1-4 mm SBR black rubber granules with polyurethane 5. Apply two coats of structural spray coating, red. 6. Layout and paint lane lines and event markings according to ASBA & NFSHA. 7. Clean up job site. Projected life span of new mat and spray is 7-15 years, with proper maintenance. Project can be completed around football games and events scheduled at stadium. However, if the project starts after September 2014, we will provide an off-season discount of \$5000.00 from the total. This quote does not include repairs to any existing cracks. Should we encounter any existing cracks that require repair, this will be brought to your attention for guidance on the various options available for repairing them. Note: We are proud to warranty our work on your track surface but are not able to warranty other contractors' work, such as the existing track base and the track surfaces underneath.	1	165,800.00	165,800.00
Total			\$165,800.00

½ payment due with order and valid purchase order (if applicable), remaining ½ payment due at completion.

ACCEPTANCE: The undersigned ("Purchaser") by execution hereof accepts this document and all of its form and conditions contained herein as a binding contract
 Signature _____

*HUB Certified Vendor*BBB Member*TIPS Member*BuyBoard*Region 7 Coop*TRAPS Member
 State of Texas Purchasing Coop-CMBL Harris County Department of Education Coop



Playgrounds Today Inc.
 248 Woodsy Hollow
 Goodrich, Texas 77335
 936-756-PLAY (7529)
 www.pticexperts.com

Proposal

Date	Proposal No.
8/1/2014	43477

Name/Address
San Diego ISD Dr. Sam Bueno 609 Labbe Ave. San Diego, TX 78384

Ship To
San Diego ISD Dr. Sam Bueno 609 Labbe Ave. San Diego, TX 78384

Description	Qty	Cost	Total
Structural Spray Re-Surfacing of Running Track Scope of Work: 1. Clean entire track and events free of all dirt and debris. 2. Repair surface on track and infield events as necessary and filling in the cold joints on straight away with EPDM rubber. 3. Resurface coating shall consist of a blend of pigmented polyurethane and colored EPDM rubber granules. The top surface shall be applied in two coats over the existing polyurethane track at the rate of 1.5 pounds per square yard per coat (3.0 pounds total). 4. Granules shall be pure EPDM crumbs .5-1.5mm in size. 5. The material ratio of the top surface shall consist of sixty percent binder and forty percent EPDM rubber. 6. The existing track shall be marked for 8-42" lanes and include all event markings as recommended by National Federation of State High School Athletic Association and ASBA guidelines. 7. Clean up job site. Projected life span of structural spray is 5-8 years Project can be completed around football games and events scheduled at stadium. However, if the project starts after the end of September 2014, we will provide an off-season discount of \$5000.00 from the total. Note: We are proud to warranty our work on your track surface but are not able to warranty other contractors' work, such as the existing track base and the track surfaces underneath.	1	75,600.00	75,600.00
		Total	\$75,600.00

½ payment due with order and valid purchase order (if applicable), remaining ½ payment due at completion.

ACCEPTANCE: The undersigned ("Purchaser") by execution hereof accepts this document and all of its form and conditions contained herein as a binding contract
 Signature _____

*HUB Certified Vendor*BBB Member*TIPS Member*BuyBoard*Region 7 Coop*TRAPS Member
 State of Texas Purchasing Coop-CMBL Harris County Department of Education Coop