

120 MPH, EXP 'C'

CANTILEVERED COLUMN

EQUIVALENT LATERAL

FORCE ANALYSIS

SYSTEM DETAILED


TIMBER FRAMES

*0.*046 W

R = 1.5

Cs = 0.046

17.6 PSF



R-19 INSULATION -

∠ 2x8 CEILING

JOISTS AT

(ALIGN WITH COLUMNS)

CONCRETE SLAB

10'-0" MAX

DETAIL

1 SCALE: 3/8" = 1'-0" (SECTION)

24" oc

- 4x8 DF-L BEAM

- R-19 INSULATION

GRADE STUDS

AT 16" 0c

2x6 SYP STUD -

GRADE AT 24" oc

6 1 PTI/PTI

- STANDING

5

SEAM ROOFING

TRANSVERSE

CEILING

- STEEL SIDING


BUILDING)


BRICK WAINSCOT


(MATCH MODULAR


(DESIGN BY OTHERS)

BEAM












2'-6"

SCALE: 1-1/2" = 1'-0" (FOOTING/STEMWALL)





SHOWN IN THE TITLE BLOCK. ET STAMPED PE SEAL IS ONLY VALID WHEN RED W BLUE SIGNATURE (COPIES NOT PERMITTED) ELECTRONIC SIGNATURE ONLY VALID WITH A VALID CERTIFICATE



UME

10/2025 SHOWN 250835

OF 1 SHEET

GENERAL FRAMING NOTES 1.) FOUNDATION DESIGN LOADS:

> ROOF LIVE LOAD = 20 PSF WIND LOAD: a.) IMPORTANCE FACTOR: b.) ULT. WIND SPEED: c.) PRESSURE: EARTHQUAKE DESIGN DATA:

a.) SEISMIC IMPORTANCE FACTOR: 1.00 RISK CATEGORY: b.) MAPPED SPECTRAL RESPONSE ACCELERATIONS: Ss=0.065a S1=0.034g c.) SITE CLASS:

d.) SPECTRAL RESPONSE COEFFICIENTS: SDS=0.069 SD1=0.054 e.) SEISMIC DESIGN CATEGORY:

f.) BASIC SEISMIC FORCE RESISTING SYSTEM:

q.) DESIGN BASE SHEAR: h.) SEISMIC RESPONSE COEFFICIENT: i.) RESPONSE MODIFICATION FACTOR: J.) ANALYSIS PROCEDURE USED:

k) REDUNDANCY FACTOR USED:

2.) ALL WORK MATERIALS SHALL BE IN STRICT COMPLIANCE WITH THE LATEST EDITION OF

THE IBC AND ALL LOCAL ORDINANCES. 2.) THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS PRIOR TO

CONSTRUCTION. THE ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCIES.

3.) ALL 2x DIMENSIONAL LUMBER SHALL BE DOUGLAS FIR LARCH NO. 2 OR BETTER UNLESS INDICATED OTHERWISE.

4.) ALL WOOD CONNECTIONS MUST CARRY THE CAPACITY OF THE MEMBER. THE CONTRACTOR IS RESPONSIBLE FOR ALL CONNECTIONS. IF OTHER THAN STANDARD CONNECTIONS ARE REQUIRED, CONTACT PROJECT ENGINEER FOR ASSISTANCE. USE SIMPSON OR OTHER ICC LISTED CONNECTIONS.

5.) ANY WOOD IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE TREATED WITH PRESERVATIVE.

6.) ALL WOOD CONNECTORS SHALL BE INSTALLED WITH ALL REQUIRED FASTENERS IN COMPLIANCE WITH THEIR LISTING.

7.) ALL WOOD MEMBERS SHALL BE FASTENED IN COMPLIANCE W/ 2021 IBC TABLE. UNLESS NOTED OTHERWISE.

8.) IF SOFFIT IS APPLIED, CANOPY SHALL BE VENTILATED WITH SCREENED SOFFIT VENTS (1 SQ. FT. OF VENT PER 150 SQ. FT. OF ROOF AREA)

9.) MINIMUM ALLOWABLE CONCRETE COMPRESSIVE STRENGTH SHALL BE 3000 PSI AT 28 DAYS. MAXIMUM AGGREGATE SIZE IS 1". MAXIMUM AIR ENTRAINMENT IS 3%. CEMENT SHOULD BE TYPE II OR TYPE III.

10.) SOIL BEARING CAPACITY IS ASSUMED TO BE 2000 PSF. ALL SOIL PREPARATION AND FOOTING PLACEMENT SHALL COMPLY WITH RECOMMENDATIONS FOUND IN GEOTECHNICAL REPORT (ECS SOUTHWEST, LLP - JOB NO. 20:2347, DATED JULY 30, 2025).

11.) ALL MACHINE BOLTS TO BE ASTM A307.

12.) ALL FASTENERS IN CONTACT WITH PRESERVATIVE TREATED LUMBER SHALL BE HOT-DIPPED GALVANIZED OR STAINLESS STEEL.

13.) ALL SIMPSON CONNECTORS IN CONTACT WITH PRESERVATIVE TREATED LUMBER SHALL HAVE 'Z - MAX' FINISH.

14.) ACUMEN ENGINEERING WILL NOT INSPECT THE INSTALLED STRUCTURE. THE OWNER AGREES TO INDEMNIFY ACUMEN ENGINEERING FOR DAMAGES ARISING FROM IMPROPER INSTALLATION.