Werner Restoration Services, Inc.

PO Box 496

Colona, IL 61241 Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

Insured: Thomas Jefferson Elementary Home: (309) 314-3272

Property: 1307 4th St W

Milan, IL 61264

Estimator: Jason Vanopdorp Business: (309) 520-4849

Company: Werner Restoration Services Inc

Claim Number: Type of Loss:

Date of Loss: Date Received:

Date Inspected: Date Entered: 4/2/2025 3:36 PM

Price List: ILMO8X_MAR25

Restoration/Service/Remodel

Estimate: THOMASJEFFERSON-R



Werner Restoration Services, Inc. PO Box 496

Colona, IL 61241 Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

THOMASJEFFERSON-R

Source - Encircle

Main Level

Main Level

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
General				
1. Haul debris - per pickup truck load - including dump fees	0.50 EA	182.72	0.00	91.36
2. Negative air fan/Air scrubber (24 hr period) - No monit.	3.00 DA	0.00	75.68	227.04
3. Add for HEPA filter (for negative air exhaust fan)	0.50 EA	0.00	218.84	118.10
5. Equipment decontamination charge - per piece of equipment	1.00 EA	0.00	38.97	39.51

Total: Main Level 476.01



Music room Height: 8'

1,370.18 SF Walls 2,644.26 SF Walls & Ceiling 141.56 SY Flooring 171.27 LF Ceil. Perimeter 1,274.08 SF Ceiling 1,274.08 SF Floor 171.27 LF Floor Perimeter

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
Drywall				
6. 1/2" drywall - hung, taped, with smooth wall finish	143.66 SF	0.00	5.18	752.59
8. Tape joint for new to existing drywall - per LF Painting	75.83 LF	0.00	17.96	1,365.46
9. Seal the surface area w/latex based stain blocker - one coat*2 walls effected by water	574.66 SF	0.00	1.02	590.55

^{*} Price is inclusive of sales tax paid at point of purchase THOMASJEFFERSON-R

4/3/2025 Page: 2




Werner Restoration Services, Inc. PO Box 496

Colona, IL 61241 Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

CONTINUED - Music room

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
11. Paint the surface area - two coats	574.66 SF	0.00	1.67	973.85
*2 walls effected by water				
Millwork				
14. Finish Carpenter - per hour	2.00 HR	0.00	86.75	173.50
*labor to re-install 1x6 trim boards removed for drywall repai	r.			
Contents				
12. Content Manipulation charge - per hour	2.00 HR	0.00	50.59	101.18
*Labor to detach and reset chalk board and marker board for	drywall repair.			
Framing				
16. R&R 2" x 4" lumber - treated (.667 BF per LF)	28.00 LF	0.71	5.47	175.28
*Replace damaged sill plate and studs.				
18. Add. charge - drilled treated plate in framed wall, 2"x4"	20.00 LF	0.00	2.21	44.61
Totals: Music room				4,177.02



Storage Area/Room	Height: 8'
-------------------	------------

805.67 SF Walls 1,360.74 SF Walls & Ceiling 61.67 SY Flooring 100.71 LF Ceil. Perimeter 555.07 SF Ceiling 555.07 SF Floor 100.71 LF Floor Perimeter

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
Drywall				
23. 1/2" drywall - hung, taped, with smooth wall finish	62.66 SF	0.00	5.18	328.26

^{*} Price is inclusive of sales tax paid at point of purchase THOMASJEFFERSON-R

4/3/2025



Werner Restoration Services, Inc. PO Box 496

Colona, IL 61241 Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

CONTINUED - Storage Area/Room

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
24. Tape joint for new to existing drywall - per LF Painting	35.33 LF	0.00	17.96	636.18
25. Seal the surface area w/latex based stain blocker - one coat *2 walls effected by water	250.66 SF	0.00	1.02	257.59
26. Paint the surface area - two coats* 2 walls effected by water	250.66 SF	0.00	1.67	424.78
Totals: Storage Area/Room				1,646.81



HALL1 Height: 8'

483.25 SF Walls 670.60 SF Walls & Ceiling 20.82 SY Flooring 60.41 LF Ceil. Perimeter 187.34 SF Ceiling 187.34 SF Floor 60.41 LF Floor Perimeter

DESCRIPTION **QTY REMOVE REPLACE** *TOTAL **Drywall** 19. 1/2" drywall - hung, taped, floated, ready for paint 43.00 SF 0.00 2.64 116.01 20. Tape joint for new to existing drywall - per LF 17.96 48.00 LF 0.00864.32 **Painting** 21. Seal the surface area w/latex based stain blocker - one coat 344.00 SF 0.00 1.02 353.51 *1 wall effected by water 22. Paint the surface area - two coats 344.00 SF 0.00 1.67 582.96 * wall effected by water

^{*} Price is inclusive of sales tax paid at point of purchase



Werner Restoration Services, Inc. PO Box 496 Colona, IL 61241

Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

CONTINUED - HALL1

DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
Totals: HALL1				1,916.80
Total: Main Level				8,216.64
Total: Source - Encircle				8,216.64
Labor Minimums Applied				
DESCRIPTION	QTY	REMOVE	REPLACE	*TOTAL
17. Framing labor minimum	1.00 EA	0.00	35.76	35.76
Totals: Labor Minimums Applied				35.76
Line Item Totals: THOMASJEFFERSON-R				8,252.40

Grand Total Areas:

5,361.16	SF Walls SF Floor SF Long Wall	595.68	SF Ceiling SY Flooring SF Short Wall	1,098.38	SF Walls and Ceiling LF Floor Perimeter LF Ceil. Perimeter
,	Floor Area Exterior Wall Area	,	Total Area Exterior Perimeter of Walls	8,987.17	Interior Wall Area
	Surface Area Total Ridge Length		Number of Squares Total Hip Length	0.00	Total Perimeter Length

4/3/2025 Page: 5

^{*} Price is inclusive of sales tax paid at point of purchase THOMASJEFFERSON-R



Werner Restoration Services, Inc. PO Box 496 Colona, IL 61241

Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

Summary

Line Item Total Overhead Profit		8,252.40 825.27 825.27
Replacement Cost Value Net Claim		\$9,902.94 \$9,902.94
	Jason Vanopdorp	_

Werner Restoration Services, Inc. PO Box 496 Colona, IL 61241

Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

Recap by Room

Estimate: THOMASJEFFERSON-R

Area: Source - Encircle

Subtotal of Areas	8,252.40	100.00%
Labor Minimums Applied	35.76	0.43%
Area Subtotal: Source - Encircle	8,216.64	99.57%
Area Subtotal: Main Level	8,216.64	99.57%
HALL1	1,916.80	23.23%
Storage Area/Room	1,646.81	19.96%
Music room	4,177.02	50.62%
Area: Main Level	476.01	5.77%

Werner Restoration Services, Inc. PO Box 496 Colona, IL 61241

Ph: 309-792-0912 Fax: 309-949-2513

www.wernerrestorationinc.com

Recap by Category

O&P Items	Total	%
CONTENT MANIPULATION	101.18	1.23%
GENERAL DEMOLITION	111.24	1.35%
DRYWALL	4,062.82	49.23%
FINISH CARPENTRY / TRIMWORK	173.50	2.10%
FRAMING & ROUGH CARPENTRY	235.77	2.86%
PAINTING	3,183.24	38.57%
WATER EXTRACTION & REMEDIATION	384.65	4.66%
O&P Items Subtotal	8,252.40	83.33%
Overhead	825.27	8.33%
Profit	825.27	8.33%
Total	9,902.94	100.00%



Main Level