MCWHORTER ELECTRIC, INC. TECL#:21804 LICENSED P.O. Box 808 Portland, TX 78374

Estimate

Date	Estimate #
1/15/2025	18700

Name / Address		
Gregory-Portland		
1200 Broadway		
Portland, TX 78374		
<i>'</i>		

		ſ	Project
		Γ	Temporary Structure
Description		·	Total
Temporary Structure on High School Student Parking Lot			
 Electrical as described below: Materials, labor and Equipment: 1. Directional drill for parallel feed conduits from parking lot to AEP transformer per walk thre James and AEP Engineer. 2. Provide and install Two 4" underground conduits from center of parking lot to transformer. 3. Install a Nema 3R 800 amp 480 volt 3 phase 4 wire distribution Panel. 4. Pull parallel feed from distribution to transformer. 5. Rough in surface conduits along side of temporary shelter to feed 5 A/C units. 6. Provide and install Five 3 phase breakers, and service disconnects for A/C units. 7. Install a 3 phase 15KVA 480/120/208 3R Transformer. 8. Install a 3 phase breaker to feed transformer. 9. Install a 3 phase 120/208 200 amp main breaker 40 circuit panel. 10. Install 2 ground rods, and bond system. 11. Energize and test. 	ough with		120,450.00
Note: Price is based on all 5 of the A/C's being on the South end of the building.			
Sent: 1/15/24			
Thanks: Monte McWhorter			
	Subtotal		\$120,450.00
Thank you for your	Sales Tax	x (0.0%)	\$0.00
business! Card has a 3% transaction fee but checks	Total		\$120,450.00