

Carr Construction LLC

103 West Stonington Ct
Coeur D Alene, ID 83815 US
(208) 618-1318
mrcarr888@gmail.com

Estimate

ADDRESS

Julie Henshaw
WBCSD
134 W MAIN ST
PRIEST RIVER, ID 83856

ESTIMATE

DATE 1066
05/19/2025

DATE	SERVICE	DESCRIPTION	QTY	RATE	AMOUNT
06/09/2025	Roofing	<p>PRIEST RIVER HIGH SCHOOL</p> <p>Overlaying or replacing existing TPO roofing areas that have yet to be replaced including areas of metal roofing. This includes all purchase of materials safety equipment, and proper insurances for the project start date. The TPO will be Mechanically installed over 1/2 inch recovery board with no ISO insulation. Bid does not include the roofs replaced in 2022 and 2024.</p> <p>The sections are the gym roof which will be overlayed in TPO approx. 16,500sqft., also includes replacing 320ft of conduit with heat tape on perimeter. Coping will be reused and will be replaced where needed.</p> <p>The main roof section which the existing roofing will be removed and replaced with TPO Mechanically installed over 1/2 inch recovery board .Coping will be reused and will be replaced where needed. APPROX. 30,500 sq ft</p> <p>The Industrial arts section which will be done in metal- approx-4,500sqft, - also will be repairing trusses and replacing sheeting as needed on the metal section.</p> <p>Project will be completed in 30 days of official start. Includes a 15 year manufacture warranty.</p>	1	545,000.00	545,000.00

SUBTOTAL 545,000.00

TAX

0.00

TOTAL

\$545,000.00

Accepted By

Accepted Date