

To: AURORA SCHOOL DISTRICT Michael Engel	Project: SODEXO - East Aurora High School - SERVING AREA 500 Tomcat Lane Aurora, IL 60505	From: TriMark Marlinn LLC Justin Zerin 6100 W. 73rd Street, Suite 1 Bedford Park, IL 60638 708-496-1700 708-496-5747 (Contact)
---	--	---

Project Code: 238677

Job Reference Number: 176656

Item	Qty	Description	Sell	Sell Total
106A	1	CUSTOM Delfield Model No. 000-40014LKY1 SHELLEY CUSTOM FABRICATION SH2CR-96-BP 96" HOT/COLD CNTR (2 HOT WELL, 52" X 21.62" COLD PAN), R290 36 INCHES HIGH, 96" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, S/S OPEN UNDERSTORAGE P-60/P-74 16" HEIGHT, S/S OPEN UNDERSTORAGE 16" HEIGHT, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$19,739.54	\$19,739.54
			ITEM TOTAL:	\$19,739.54
106A	1 ea	Delfield Model No. W00007AN 7 year compressor warranty, standard		
106A	1 ea	Delfield Model No. 0550000 2 year parts & labor warranty (NET priced – no further discount)	\$1,243.00	\$1,243.00
			ITEM TOTAL:	\$1,243.00
106A	1	CUSTOM Delfield Model No. 000-CCA14LKY1 SHELLEY CUSTOM FABRICATION FLEXIBLE SHIELD, CONVERTS TO THREE POSITIONS 93.378 INCHES LONG X 19.5 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF, WITH HEATLAMP,HATCO,GR5AL-30, 120V ON FIRST TIER, WITH LED LIGHT ON FIRST TIER, 503N PLEXIGLAS END PANEL MODIFY TO BE TEMPERED GLASS END PANEL BETWEEN HOT AND COLD WELLS.	\$12,491.67	\$12,491.67
			ITEM TOTAL:	\$12,491.67

Item	Qty	Description	Sell	Sell Total
111	1	CUSTOM Delfield Model No. 000-40014LKY2 SHELLEY CUSTOM FABRICATION SCSC-96-BP 96" REFRIGERATED COLD PAN SERVING COUNTER, R290 36 INCHES HIGH, 96" S/S V- TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, 1027H 4" CASTERS IN LIEU OF 6" CASTERS , GLASS FRONT COUNTER PROTECTOR 94.06 INCHES LONG X 18 INCHES WIDE. FIRST TIER S/S TOP AND FIXED GLASS FRONT	\$14,999.66	\$14,999.66
			ITEM TOTAL:	\$14,999.66
111	1 ea	Delfield Model No. W00007AN 7 year compressor warranty, standard		
111	1 ea	Delfield Model No. 0550000 2 year parts & labor warranty (NET priced – no further discount)	\$1,243.00	\$1,243.00
			ITEM TOTAL:	\$1,243.00
106B	1	CUSTOM Delfield Model No. 000-40014LKY3 SHELLEY CUSTOM FABRICATION SH-6 SIX WELL HOT FOOD COUNTER WITH HEATED UNDERSTORAGE HINGED LEFT 36 INCHES HIGH, 96" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, 1027H 4" CASTERS IN LIEU OF 6" CASTERS , GLASS FRONT COUNTER PROTECTOR 94.06 INCHES LONG X 18 INCHES WIDE. FIRST TIER S/S TOP AND FIXED GLASS FRONT, RADIANT HEAT LAMP ON FIRST TIER 208 VOLTS	\$21,374.16	\$21,374.16
			ITEM TOTAL:	\$21,374.16
109A	1	CUSTOM Delfield Model No. 000-40014LKY4 SHELLEY CUSTOM FABRICATION SH2CR-74-BP 74" HOT/COLD CNTR (2 HOT WELL, 26" X 21.62" COLD PAN), R290 36 INCHES HIGH, 74" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 74" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, S/S OPEN UNDERSTORAGE P-60/P-74 16" HEIGHT, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$15,516.53	\$15,516.53
			ITEM TOTAL:	\$15,516.53
109A	1 ea	Delfield Model No. W00007AN 7 year compressor warranty, standard		

Item	Qty	Description	Sell	Sell Total
109A	1 ea	Delfield Model No. 0550000 2 year parts & labor warranty (NET priced – no further discount)	\$1,243.00	\$1,243.00
ITEM TOTAL:				\$1,243.00
109A	1	CUSTOM Delfield Model No. 000-CCA14LKY4 SHELLEY CUSTOM FABRICATION GLASS FRONT FOOD SHIELD, SINGLE TIER WITH GLASS SHELF, SINGLE SERVICE 71.378 INCHES LONG X 16 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF	\$3,603.38	\$3,603.38
ITEM TOTAL:				\$3,603.38
109A	1	CUSTOM Delfield Model No. 000-40014LKYK SHELLEY CUSTOM FABRICATION SFW-1-NU 28IN (1) WELL INDIVIDUALLY CONTROLLED, FLEXIWELL HOT/COLD/FREEZE PAN SERVING COUNTER W/O UNDERSTORAGE 36 INCHES HIGH, 28" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$15,042.55	\$15,042.55
ITEM TOTAL:				\$15,042.55
109A	1 ea	Delfield Model No. W00007AN 7 year compressor warranty, standard		
109A	1 ea	Delfield Model No. 0550000 2 year parts & labor warranty (NET priced – no further discount)	\$1,243.00	\$1,243.00
ITEM TOTAL:				\$1,243.00
109A	1	CUSTOM Delfield Model No. 000-CCA14LKYK SHELLEY CUSTOM FABRICATION GLASS FRONT FOOD SHIELD, SINGLE TIER WITH GLASS SHELF, SINGLE SERVICE 25.378 INCHES LONG X 16 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF	\$1,363.44	\$1,363.44
ITEM TOTAL:				\$1,363.44
109B	1	CUSTOM Delfield Model No. NOTE EMPTY SPACE - EQUIPMENT BY OTHERS SPACE FOR GRAB AND GO BY OTHER.		

Item	Qty	Description	Sell	Sell Total
108A	1	CUSTOM Delfield Model No. 000-40014LKY6 SHELLEY CUSTOM FABRICATION SH-2-NU TWO WELL HOT FOOD COUNTER WITH ENCLOSED BASE 36 INCHES HIGH, 38" TOP EXTENSION, 74" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 74" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS , SG19A RECESSED HEATED TOP 17"X25"X1" ON RIGHT SIDE.	\$13,670.17	\$13,670.17
			ITEM TOTAL:	\$13,670.17
108A	1	CUSTOM Delfield Model No. 000-CCA14LKY6 SHELLEY CUSTOM FABRICATION FLEXIBLE SHIELD, CONVERTS TO THREE POSITIONS 71.378 INCHES LONG X 19.5 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF, WITH HEATLAMP,HATCO,GR5AL-54, 120V ON FIRST TIER	\$10,364.76	\$10,364.76
			ITEM TOTAL:	\$10,364.76
108B	1	CUSTOM Delfield Model No. 000-40014LKY7 SHELLEY CUSTOM FABRICATION SH-2-NU TWO WELL HOT FOOD COUNTER WITH ENCLOSED BASE 36 INCHES HIGH, 38" TOP EXTENSION, 74" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 74" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS , SG19A RECESSED HEATED TOP 17"X25"X1" ON LEFT SIDE.	\$13,670.17	\$13,670.17
			ITEM TOTAL:	\$13,670.17
108B	1	CUSTOM Delfield Model No. 000-CCA14LKY7 SHELLEY CUSTOM FABRICATION FLEXIBLE SHIELD, CONVERTS TO THREE POSITIONS 71.378 INCHES LONG X 19.5 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF, WITH HEATLAMP,HATCO,GR5AL-54, 120V ON FIRST TIER	\$10,364.76	\$10,364.76
			ITEM TOTAL:	\$10,364.76

Item	Qty	Description	Sell	Sell Total
106C	1	CUSTOM Delfield Model No. 000-40014LKY9 SHELLEY CUSTOM FABRICATION SH-6 SIX WELL HOT FOOD COUNTER WITH HEATED UNDERSTORAGE HINGED LEFT 36 INCHES HIGH, 96" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$17,965.55	\$17,965.55
			ITEM TOTAL:	\$17,965.55
106C	1	CUSTOM Delfield Model No. 000-CCA14LKY9 SHELLEY CUSTOM FABRICATION GLASS FRONT FOOD SHIELD, SINGLE TIER WITH GLASS SHELF, SINGLE SERVICE 93.378 INCHES LONG X 16 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF	\$4,674.66	\$4,674.66
			ITEM TOTAL:	\$4,674.66
106D	1	CUSTOM Delfield Model No. 000-40014LKYA SHELLEY CUSTOM FABRICATION SH-6 SIX WELL HOT FOOD COUNTER WITH HEATED UNDERSTORAGE HINGED LEFT 36 INCHES HIGH, 96" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$17,965.55	\$17,965.55
			ITEM TOTAL:	\$17,965.55
106D	1	CUSTOM Delfield Model No. 000-CCA14LKYA SHELLEY CUSTOM FABRICATION GLASS FRONT FOOD SHIELD, SINGLE TIER WITH GLASS SHELF, SINGLE SERVICE 93.378 INCHES LONG X 16 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF	\$4,674.66	\$4,674.66
			ITEM TOTAL:	\$4,674.66
106E	1	CUSTOM Delfield Model No. 000-40014LKYC SHELLEY CUSTOM FABRICATION SH-6 SIX WELL HOT FOOD COUNTER WITH HEATED UNDERSTORAGE HINGED LEFT 36 INCHES HIGH, 96" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, 96" S/S WORKSHELF 10" WIDE, LOCATED ON OPERATOR SIDE, MOUNTED 36" HIGH, LINE-UP INTERLOCK, FLEXISHIELD FACTORY INSTALLED TO BASE, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$17,965.55	\$17,965.55
			ITEM TOTAL:	\$17,965.55

Item	Qty	Description	Sell	Sell Total
106E	1	CUSTOM Delfield Model No. 000-CCA14LKYC SHELLEY CUSTOM FABRICATION GLASS FRONT FOOD SHIELD, SINGLE TIER WITH GLASS SHELF, SINGLE SERVICE 93.378 INCHES LONG X 16 INCHES WIDE X 16 INCHES HIGH WITH GLASS SHELF	\$4,674.66	\$4,674.66
ITEM TOTAL:				\$4,674.66
106F	4	CUSTOM Delfield Model No. 000-40014LKYL SHELLEY CUSTOM FABRICATION SCS-36 , 36" CASHIER'S COUNTER 36 INCHES HIGH, DRAWER ON RIGHT END, 36" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS LOCATED ON CUSTOMER SIDE 34" HIGH, 30" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS LOCATED ON LEFT END 34" HIGH, LINE-UP INTERLOCK, CASH DRAWER INSERT, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$5,874.60	\$23,498.40
ITEM TOTAL:				\$23,498.40
106G	1	CUSTOM Delfield Model No. 000-40014LKYM SHELLEY CUSTOM FABRICATION SC-60-NU 60" ALL PURPOSE COUNTER WITH ENCLOSED BASE 36 INCHES HIGH, 60" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, LINE-UP INTERLOCK, S/S OPEN UNDERSTORAGE P-60/P-74 24" HEIGHT, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$5,781.23	\$5,781.23
ITEM TOTAL:				\$5,781.23
106H	1	CUSTOM Delfield Model No. 000-40014LKYN SHELLEY CUSTOM FABRICATION SC-28-NU 28" ALL PURPOSE COUNTER WITH ENCLOSED BASE 36 INCHES HIGH, 2" TOP EXTENSION, 30" S/S V-TRAY SLIDE 12" WIDE WITH 3 RIBS, LOCATED ON CUSTOMER SIDE, MOUNTED 34" HIGH, LINE-UP INTERLOCK, S/S OPEN UNDERSTORAGE 24" HEIGHT, 1027H 4" CASTERS IN LIEU OF 6" CASTERS	\$3,643.14	\$3,643.14
ITEM TOTAL:				\$3,643.14

Item	Qty	Description	Sell	Sell Total
112	1 ea	OPEN DISPLAY MERCHANDISER Beverage Air Model No. VMHC-18-1-B Vuemax Series Open-Air Merchandiser, 52"W x 31-3/4"D x 83-3/8" H, 18.6 cu. ft. capacity, tempered thermal glass sides, (5) shelves, price tag molding, night curtain, 36° F - 40° F operating temperatures, LED interior lighting, maintenance-free condenser, automatic defrost, R290 Hydrocarbon refrigerant, painted steel interior, black vinyl wrapped exterior, (2) 1/3 HP, cETLus, ETL-Sanitation	\$8,632.83	\$8,632.83
	1 ea	3 Year Parts/Labor warranty. 5 year compressor warranty (excludes maintenance items)		
	1 ea	115v/60/1-ph, 12 amps, NEMA 5-20P		
ITEM TOTAL:				\$8,632.83
1	1 ea	INSTALLATION Advanced Installation Management Model No. EQUIPMENT INSTALL Accept delivery of new equipment. Check for damage, inventory and report. Remove existing cafeteria food service line. Dispose of old equipment. Pull new conductors for new service line equipment. Assemble and install according to provided CAD drawings. Any modification from the drawings is a change order. Gas lines to be turned off and removed back to ball valve and capped. Any other modification or removal of gas lines will be a change order. Equipment to Be Installed: (2) 5-well hot serving lines (Model SH-6-NU) (2) cashier stands (Model SCS-50) (2) cold serving lines (Model SCSC-74-BP) Flexible food shields ***Delivery Trucks Must Have Liftgate Service ***Note Hood And Walk-In Work Not Included ***Note Final Electrical, Plumbing And Gas Connections Not Included ***Note Start Up Not Included ***Note Night, Weekend, Prevailing Wage, And Union Labor Not Included ***Note 1st Floor Install Quoted ***Note Budget Quote. Pricing May Vary At That Time Based On Site Conditions ***QUOTE VALID FOR 60 DAYS***	\$25,000.00	\$25,000.00
ITEM TOTAL:				\$25,000.00
Subtotal				\$291,649.02
Total				\$291,649.02

PRICE ADJUSTMENTS

Prices may not reflect applicable tariffs, duties, import fees, taxes, or other governmental charges. TriMark reserves the right to correct or adjust quoted prices at any time due to tariffs, market fluctuations, supply chain disruptions, third-party supplier cost changes, general contractor delays, or any other factors outside of TriMark's control. TriMark will use commercially reasonable efforts to hold pricing for (7) seven calendar days from the date of the quote; however, all pricing remains subject to correction or adjustment as set forth above, including during the seven-day hold period.

TRIMARK RETURN POLICY

All returns must be unused, undamaged and in their original packaging. All returns are subject to inspection. If a returned item is not in its original packaging, the customer will be responsible for the repackaging cost. If a returned item is damaged or cannot be sold as new, partial or no credit will be provided based on the condition of the item(s).

Please contact your TriMark representative to initiate a return.

Custom fabricated and made-to-order items are non-cancellable and non-returnable unless the return is due to TriMark's mistake. This includes any product that has custom configurations or accessories.

Stock Supplies and Equipment can be returned within 30 days of delivery for a refund of the selling price and any taxes paid. Return freight charges are the responsibility of the customer.

Non-Stock, non-custom Supplies and Equipment may be returned to the OEM subject to their return policy for a refund of the selling price plus any taxes paid. The customer is responsible for return freight charges and a minimum 30% restocking fee.

TRIMARK TERMS AND CONDITIONS OF SALE

This Quote shall be subject to TriMark's Terms of Sale

(<http://www.trimarkusa.com/SiteMedia/SiteResources/Terms/TriMark-Terms-and-Conditions-of-Sale.pdf>), which are incorporated herein by reference and shall govern.

The parties specifically agree that no signature shall be required in order for this Quote or its applicable terms and conditions to be deemed legally binding and enforceable on Customer where the intent to be so bound can be inferred (including by acceptance or retention of products or services), notwithstanding contrary requirements under any law.

Acceptance: _____ Date: _____

Printed Name: _____

Project Grand Total: \$291,649.02