

ESTIMATE

Integrated Construction Solutions, LLC.
1100 West St Ste 100
Wausau, WI 54401

accountsreceivable@icsusa.co
+1 (715) 432-9003
Brian +1 (715) 432-1337



Bill to
DCE School District
6100 Alderson St.
Weston, WI 54476

Ship to
DCE School District
6100 Alderson St.
Weston, WI 54476

Estimate details

Estimate no.: 1246
Estimate date: 03/26/2026

P.O. Number: Fiber Relocate

Product or service	Description	Qty	Rate	Amount
	Project Location: Alderson St. & Jelinek Ave. Weston, WI 54476			
.	This is a fiber relocate due to a major road project. Apply for all proper permits and plans, along with a detailed as-built of new fiber route. We will directional drill new 1 1/4" conduit (Approx. 929') to follow the new right-of-way. We will install (4) new vaults along this path with pea gravel, ground rods, and duct plug. Blow new 24ct. fiber in new conduit with appropriate slack loops in each vault. Dig up approx. 60' of existing conduit (with fiber) on east and south ends of the project so we have enough fiber slack for splicing. We will coordinate with the School District Staff to set up a time to splice the old and new fibers. This will take place during off hours so that service is not disrupted during operational times. All fibers will be spliced. This will have (2) new splice enclosures that are bonded and grounded. This bid includes spotting of all existing utilities. Any hard surface restoration is included. This is a labor and materials bid.	1	\$26,536.44	\$26,536.44

Total

\$26,536.44

Note to customer

Estimate good for 30 days from Estimate Date.
Contact Brian DeLisle (715)432-1337 with questions.

Accepted date

Accepted by