

PHYBS Proposal for Electricity

Scope

PHYBS would like to extend electricity from Betsy Ross (on wall across from Green ground box-west to Center field (scoreboard), then Southwest to the shed (approximately 290 feet in total). Our Electrician will add a new box outside Betsy Ross next to other electrical boxes with a 60 amp circuit. Bolder will run 4-gauge wire (4 strands which includes a ground) through 1 and ¾ PVC buried at 18 inches deep per city code. This PVC/wire would run under the walking path as to not disturb the structure and approximately 90 feet west of school to area designated for the scoreboard (if approved). An electrical box will be installed on the scoreboard beam (City Electric) and PVC/wire will then run from that box to the shed (approximately 200 feet). The shed would have a locked outlet (City Electric to install) on exterior as well as an interior outlet. Electricity for scoreboard and occasional PHYBS use is estimated at less than \$5 per month throughout the season (May 1st to July 31)

Vendor: Home Depot

Installer: City Electric 5410 Newport Dr, Suite 21 Rolling Meadows, IL 60008.
Bolder Landscaping 314 W School St Villa Park, IL 60181

Projected date of work: March 27/28



PHYBS Board



Proposal

5410 Newport Drive, Suite 31 Phone # (773) 282-7186
 Rolling Meadows, IL. 60008

Date	Estimate #
2/26/2025	24440-JC

Name / Address	Project Information
Prospect Heights School District 23 700 N. Schoenbeck Rd. Prospect Heights, IL 60070	Baseball Field Power Sullivan Elementary School 710 N Schoenbeck Rd. Prospect Heights, IL 60070

Description	Total
<ul style="list-style-type: none"> - Furnish and install conduit and wire from electrical panel, with spare space, for new 2 pole 30 amp breaker. - Provide J-box on exterior wall. - 1" conduit and #4 THHN. - Provide 600' of #4 THHN and 200' of #6 THHN for ground. - Trenching, backfill, and 1" conduit run will be done by others. - City Service will pull in new cable and provide a new 30 amp fused disconnect. - Permit by others. <p>Notes:</p> <ul style="list-style-type: none"> - All work to be done on straight time; Monday-Friday 7:00a.m.-3:30p.m. - No accelerated schedule. - No fire alarm included. - No permit fees included. - No painting or patching included. - No other electrical work is included in this proposal. - Invoices paid with a credit card will be charged a 3% convenience fee. 	5,620.00

Terms	WE HEREBY PROPOSE TO FURNISH LABOR AND MATERIALS COMPLETE IN ACCORDANCE WITH THE ABOVE SPECIFICATIONS, FOR THE SUM OF:	\$5,620.00
-------	--	------------

ACCEPTANCE OF PROPOSAL

The above prices, specifications and conditions are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

DATE _____ Signature _____

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written change orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accident or delays beyond our control. This proposal is subject to acceptance within 30 days and it is void thereafter at the option of City Service Electric, Inc.

ESTIMATE

Bolder Lawns LLC

314 West School Street
Villa Park, IL 60181
(847) 754-4763
info@bolderlawns.com



To:
Brad Alpert
103 East Kenilworth Avenue
Prospect Heights, IL 60070

Estimate # 18738
Estimate Date 02/26/2025
Total Amount \$8,640.00

Item	Quantity	Price	Line Total
labor sidework excavate 700 Schoenbeck Road (Betsy Ross)	1.0	\$2,160.00	\$2,160.00
labor sidework pvc + pull wire	1.0	\$2,160.00	\$2,160.00
labor sidework- install sign	2.0	\$2,160.00	\$4,320.00

Subtotal: \$8,640.00
Tax: \$0.00
Past Due Amount: \$0.00
Total Amount: \$8,640.00

Any revisions or additions to this estimate will require a new estimate and scheduled date for work. All check payments are to be made payable to "Bolder Lawns LLC". Any variations will not be accepted and marked VOID. For side-work projects, upon accepting this estimate, a non-refundable "Placeholder" will be invoiced. The remaining payments are as follows: 70% when scheduled and 30% due upon completion.

Notes

labor sidework - Description

Labor includes,
Includes Excavate
At a depth of 18"
Pvc electrical line

Labor Pvc + wire pull

Glue pvc
Install pvc and
pull wire as we go.
Materials provided by client(donated by home depot)

Labor install sign

Day 1

Pick up metal post. (Post provided by client)

Cut post to size.

Make holes in soil for concrete base.

Install steel post secure them Level and parallel to each other.

Pour concrete base around the post.

Or mount them to the concrete base depending on post base.

Day 2

Prime steel post (will work with my paint supplier to see if they can donate primer and paint.)

Paint steel post

install sign (provided by client)

No additional cost.

Install fence socket kit 49.

Socket kit provide by client.

SCAN WITH PHONE CAMERA TO OPEN THIS ESTIMATE ONLINE

