



101 Josephine Ln (P) 972-721-9796  
 Grand Prairie, TX 75050 (F) 972-721-1755

# Bid Proposal

Date	Rep	Estimate #
3/23/2019	RRA	89859

<b>Billing / Customer Name</b>
Quanah ISD PO Box 150 Quanah, TX 76252

<b>Service Address</b>
Quanah ISD PO Box 150 Quanah, TX 76252

PO Number	Terms	Project
	Net 30	

Item	Description
Concrete	<p>INSTALL NEW CONCRETE SPEED HUMP/RAISED WALKWAY: (Approx 480 SqFt (16x30 drivelane), 1 area, 20 CY, 95 R, 2D,96H )</p> <ol style="list-style-type: none"> <li>1. Sawcut, excavate and remove concrete, pavers and related debris from job site.</li> <li>2. Rework and compact base with vibratory compactor as needed.</li> <li>3. Install cushion sand pad as necessary.</li> <li>4. Drill and dowel vertical surfaces on adjacent concrete.</li> <li>5. Install 8" of 4000 PSI concrete with #4 rebar on 16" centers (6" above grade).</li> <li>6. Install steel piping beneath concrete along curbs for water to flow</li> <li>7. Saw control joints to match existing or a maximum 15' on center and perimeter of each repair.</li> <li>8. Hand trowel and broom to finish.</li> </ol> <p>***Not responsible for irrigation or items buried in concrete.</p>
Concrete Sidewalk	<p>INSTALL SIDEWALK LEVEL WITH NEW WALKWAY/SPEED HUMP: (Approx 80 SqFt (10X4 each side of street), 2areas)</p> <ol style="list-style-type: none"> <li>1. Barricade work area, excavate and remove damaged debris from job site.</li> <li>2. Rework and compact base with vibratory compactor as needed.</li> <li>3. Install cushion sand pad as necessary.</li> <li>4. Drill and dowel vertical surfaces on adjacent concrete.</li> <li>5. Install 6-8" of 4000 PSI concrete with #3 rebar on 18" centers.</li> <li>6. Hand trowel and broom to finish.</li> </ol> <p>**Does not include landscape repair.</p>
Trip Charge	

Thank you for the opportunity.	<b>Subtotal</b>
CI Pavement is not responsible for damage to underground utilities or graffiti on new pavement. Any invoice past due will be subject to a late fee compounded at a rate of 2.0% per month prorated. Any alteration from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the proposal. Payment terms shall be 50% up front 50% upon completion. This proposal expires 30 days from date listed.	<b>Sales Tax (0.00)</b>
	<b>Total</b>

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. CI Pavement. is authorized to do the work as specified. Payment will be made as outlined above.

Signature: \_\_\_\_\_

Phone #	Fax #
972-721-9796	972-721-1755



101 Josephine Ln (P) 972-721-9796  
 Grand Prairie, TX 75050 (F) 972-721-1755

# Bid Proposal

Date	Rep	Estimate #
3/23/2019	RRA	89859

Billing / Customer Name
Quanah ISD PO Box 150 Quanah, TX 76252

Service Address
Quanah ISD PO Box 150 Quanah, TX 76252

PO Number	Terms	Project
	Net 30	

Item	Description
Concrete Sidew...	Added 2/5/19 REPAIR DAMAGED SIDEWALK: (Approx 144 SqFt (9X16). 1 area) 1. Barricade work area, excavate and remove damaged debris from job site. 2. Rework and compact base with vibratory compactor as needed. 3. Install cushion sand pad as necessary. 4. Drill and dowel vertical surfaces on adjacent concrete. 5. Install 4" of 4000 PSI concrete with #3 rebar on 18" centers. 6. Hand trowel and broom to finish. **Does not include landscape repair.
Concrete recess...	INSTALL NEW ADA ACCESSIBLE RAMP: (Approx 240 SqFt, (15x16) 1 areas) 1. Barricade work area, Sawcut, excavate and remove damaged concrete and related debris from job site. 2. Rework and compact base with vibratory compactor as needed. 3. Install cushion sand pad as necessary. 4. Drill and dowel vertical surfaces on adjacent concrete. 5. Install 4" of 4000 PSI concrete with #3 rebar on 18" centers. 6. Hand trowel and broom to finish.

Thank you for the opportunity.	<b>Subtotal</b>
CI Pavement is not responsible for damage to underground utilities or graffiti on new pavement. Any invoice past due will be subject to a late fee compounded at a rate of 2.0% per month prorated. Any alteration from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the proposal. Payment terms shall be 50% up front 50% upon completion. This proposal expires 30 days from date listed.	<b>Sales Tax (0.00)</b>
	<b>Total</b>

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. CI Pavement. is authorized to do the work as specified. Payment will be made as outlined above.

Signature: \_\_\_\_\_

Phone #	Fax #
972-721-9796	972-721-1755



101 Josephine Ln (P) 972-721-9796  
 Grand Prairie, TX 75050 (F) 972-721-1755

# Bid Proposal

Date	Rep	Estimate #
3/23/2019	RRA	89859

Billing / Customer Name
Quanah ISD PO Box 150 Quanah, TX 76252

Service Address
Quanah ISD PO Box 150 Quanah, TX 76252

PO Number	Terms	Project
	Net 30	

Item	Description
	<p>Notes:</p> <ol style="list-style-type: none"> <li>1) Includes approximately 20 square feet in asphalt parking area to accomdate new slope</li> <li>2) Estimate exludes permit from city of Quanah</li> <li>3) Entire area to be shut down and work completed in one mobilization</li> <li>4) Dimensions are provided by customer. This is a unit price bid. If measurements exceed stated dimensions, additional charges will apply</li> </ol>

Thank you for the opportunity.	<b>Subtotal</b>	\$17,230.00
CI Pavement is not responsible for damage to underground utilities or graffiti on new pavement. Any invoice past due will be subject to a late fee compounded at a rate of 2.0% per month prorated. Any alteration from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the proposal. Payment terms shall be 50% up front 50% upon completion. This proposal expires 30 days from date listed.	<b>Sales Tax (0.00)</b>	\$0.00
	<b>Total</b>	\$17,230.00

ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted. CI Pavement. is authorized to do the work as specified. Payment will be made as outlined above.

Signature: \_\_\_\_\_

Phone #	Fax #
972-721-9796	972-721-1755