P.O. Box 2048 Graham, Texas 76450 940.549.5700 Fax 940.549.5723

May 12, 2008

To: Abilene Wylie I.S.D.

Re: Wylic High School Football Renovations(Visitor Side)

PROPOSAL

Steel Stadiums is pleased to offer the following scope and proposal for the above project. Our proposal will be for delivered materials and installation.

Inclusions: Visitor Grandstand Additions

- Rise and Depth Dimensions: Vertical rise and horizontal depth per row: 11 inches x 25 inches. Seat is 17 inches above its respective tread.
- Footprint: 20 Rows X 84'-0",
- Structure: Horizontal Beam w/ stringer spacing at 6-foot (max.) intervals and wide flange column and beam supports.
- Seats: Nominal 2 x 12 anodized aluminum plank with 2 x 12 anodized end caps.
- Treads: Full Deck planking arrangement anodized end caps and contrasting step nose at all aisle areas.
- Risers: Nominal 1 x 9.5 anodized aluminum riser planks.
- Guard railing: Galvanized 9 gauge chain link w/ top rail 43 inches above seat on both sides of bleacher and across back of bleacher.
- Entry Ramp: Ramp shall be included. Ramp will have galvanized 9 gauge chain link w/ top rail at 43" above walking surface and a 2 x 4 kick board below.
- Aisles: One aisle at each end of bleacher with continuous handrail at 34" above the nosing line. Aluminum tread nosing of contrasting color on aisle steps.
- Anchor Bolts and templates.
- All steel on grandstand will be hot-dipped galvanized steel.
- Design drawings stamped by a Professional Engineer licensed in the state of Texas.

Alternate Inclusions:

Aluminum skirt; Anodized aluminum risers for façade at front of the grandstand for Home and Visitor sides.

Exclusions:

- Concrete not included in pier design.
- Bonds
- Taxes
- Permits and fees, including state and/or local plan approval fees.
- Electrical (Press box is wired and ready for service to be connected).
- Signage.
- Testing and inspection.
- · Items not specifically included.
- Payment and performance bonds, add for bond below.
- Any required assisted listening devices or other electronic assistance devices.
- Clear and adequate access to be provided.

Base bid total for delivered materials and installation: \$177,000.00

Alternate bid for Home & Visitor Facade: \$24,500.00

Mike Riley
Steel Stadiums
Office (940) 549-5700
Fax (940) 549-5723
Cell (832) 221-9258
mniley@steelstadiums.com
www.steelstadiums.com

Best Begards,