



Z3 Solutions
 1350 E Touhy Avenue, Suite 120W
 Des Plaines, Illinois 60018
 P: (847) 730-3945
 F: (847) 724-1249

Project: 17161 - 17161 - Lincoln Hall Phase 3
 6855 N. Crawford Ave.
 Lincolnwood, Illinois 60712
 P: 847-730-3945

CHANGE EVENT #006 - Entrance #1 Canopy

Origin:

Date Created: 6/11/2018 **Created By:** Nicholas Zouras
Status: Pending **Scope:** TBD
Type: Design Modification **Change Reason:**

Description:

Attachments: [Lincoln Hall Canopy Proposal w Letterhead.docx](#)

CHANGE EVENT LINE ITEMS

Cost Code	Cost Type	Vendor / Contract	Prime PCO	ROM	RFQ	Commit.	Budget Mod.
0200-02000 - Demolition	Other	Green Demolition Contractors, Inc. SC-001		\$4,600.00			
0610-06100 - Rough Carpentry	Other	Ostrander Construction, Inc. SC-005		\$1,995.00			
0750-07500 - Membrane Roofing	Other	DCG Roofing Solutions, Inc. SC-007		\$36,780.00			
0925-09250 - Drywall Package	Other	Drive Construction Inc. SC-010		\$2,266.00			
0991-09910 - Painting & Wallcoverings	Other	Nikolas Painting Contractors, Inc. SC-014		\$480.00			
1540-15400 - Plumbing	Other	DeFranco Plumbing SC-017		\$6,900.00			
1600-16000 - Electrical	Other	Block Electric SC-019		\$5,900.00			
9400-94000 - General Liability Insurance	Other			\$589.21			
	Description: 1% General Liability Insurance						
9500-95000 - Fee	Other			\$2,082.86			

Cost Code	Cost Type	Vendor / Contract	Prime PCO	ROM	RFQ	Commit.	Budget Mod.
	Description: 3.5% Fee						
9600-96000 - Payment & Performance Bond	Other			\$36.07			
	Description: 1.35% Bond						
Grand Totals			\$0.00	\$61,629.14	\$0.00	\$0.00	\$0.00

DCG Roofing Solutions Incorporated

2045 Janice Ave., Melrose Park, Illinois 60160 phone (847) 296-6611 cell (815)378-8340 fax (847)296-4604



May 30, 2018

Construction Manager: Z3 Solutions

1350 Touhy Avenue
Des Plaines, IL 60018

PROJECT: Door 1 Canopy Roof Alternate 2

Nick Zouras:

I want to thank you for the opportunity to provide our proposal to you for the specified additional work at Lincoln Hall Middle School. Our company is insured, licensed, very safety and detail conscious and certified to install the roof system.

Scope of Work

Canopy Roof Area 21.0 Revised

1. Tear off existing roof to concrete deck.
2. Install specified 2 ply temporary roof in hot asphalt.
3. Install 1/8" tapered polyisocyanurate in hot asphalt.
4. Install 1/2" specified cover board in hot asphalt.
5. Furnish and install specified Soprema BUR Roof system per ARCON specifications
6. Furnish and install flashings for all drains and plumbing vents.
7. Furnish and install prefinished raised standard color metal roof edge and counter flashings.
8. Furnish and install standard color composite wall panels.
9. Furnish and install metal soffit and trim.
10. Fabricate and install prefinished sheet metal cover over drain pipe.
11. Furnish 20 Year Manufactures Warranty.

Total Cost \$36,780.00

Exclusions: Dumpsters, Electrical, Decking, Framing, Fiber cement, structural steel, plumbing, masonry work

We look forward to successfully completing another project with you.

Thanks again,

Daniel Stanton
VP DCG Roofing Solutions, Inc.

